

**FINAL**

## **CMC Bozeman Facility Supplemental Investigation Report**

*Prepared for:*

**City of Bozeman**

*P.O. Box 1230  
Bozeman, Montana 59771-1230  
(406) 582-2329*

*Prepared by:*

**Tetra Tech**

*303 Irene St.  
Helena, MT 59601  
406-443-5210  
Fax 406-449-3729*

Tetra Tech Project No. 1157720035.200

January 6, 2009



## ACRONYM LIST

<b>ASHERA</b>	Asbestos Hazardous Emergency Response Act
<b>AIHA</b>	American Industrial Hygiene Association
<b>ASTM</b>	American Standard for Testing and Materials
<b>BGS</b>	Below Ground Surface
<b>CARB</b>	California Air Resources Board
<b>CECRA</b>	Comprehensive Environmental Cleanup and Responsibility Act
<b>CFR</b>	Code of Federal Regulations
<b>CIH</b>	Certified Industrial Hygienist
<b>cm</b>	Centimeter
<b>DEQ</b>	Montana Department of Environmental Quality
<b>EBM</b>	Empire Building Materials, Inc.
<b>EPA</b>	U.S. Environmental Protection Agency
<b>GPS</b>	Global Positioning System
<b>HASP</b>	Health and Safety Plan
<b>HAZWOPER</b>	Hazardous Waste Operations and Emergency Response
<b>HVAC</b>	Heating, Ventilation, and Air Conditioning
<b>ISO</b>	International Organization for Standardization
<b>lpm</b>	Liters per Minute
<b>MCE</b>	Mixed Cellulose Ester
<b>MDT</b>	Montana Department of Transportation
<b>mm</b>	Millimeter
<b>NHB</b>	North Harrington Building
<b>NICET</b>	National Institute for Certification in Engineering Technologies
<b>NIOSH</b>	National Institute of Occupational Safety and Health
<b>NP</b>	Non-Porous
<b>NVLP</b>	National Voluntary Laboratory Accreditation Program
<b>O&amp;M</b>	Operations and Maintenance
<b>OSHA</b>	Occupational Safety and Health Administration
<b>P</b>	Porous
<b>PCI</b>	Pavement Condition Index
<b>PLM</b>	Polarized Light Microscopy
<b>QA/QC</b>	Quality Assurance/Quality Control



## ACRONYM LIST (continued)

<b>RTI</b>	Resource Technologies, Inc.
<b>SI</b>	Supplemental Investigation
<b>SHB</b>	South Harrington Building
<b>SOW</b>	Statement of Work
<b>SP</b>	Semi-Porous
<b>TEM</b>	Transmission Electron Microscopy
<b>TWA</b>	Time Weighted Average
<b>VCP</b>	Voluntary Cleanup Plan



## TABLE OF CONTENTS

<b>1.0 EXECUTIVE SUMMARY .....</b>	<b>1</b>
<b>2.0 BACKGROUND .....</b>	<b>3</b>
2.1 Site Characterization Summary .....	3
2.2 Purpose.....	4
<b>3.0 SUPPLEMENTAL INVESTIGATION METHODS.....</b>	<b>5</b>
3.1 Supplemental Investigation Work Plan .....	5
3.2 Site-Specific Health and Safety Plan .....	5
3.3 Pavement Condition Assessment .....	6
3.4 Soil Sampling .....	6
3.4.1 Soil Sample Analysis .....	8
3.5 Asbestos Air-Related Sampling .....	8
3.5.1 Asbestos Dust Sampling.....	9
3.5.2 Asbestos Air Sampling.....	11
<b>4.0 RESULTS AND ANALYSIS .....</b>	<b>12</b>
4.1 Pavement Condition Assessment .....	12
4.2 Soil Sampling .....	15
4.2.1 South Harrington Building .....	15
4.2.2 Heeb's.....	16
4.2.3 Story Distributing Property .....	17
4.3 Asbestos Air-Related Sampling .....	19
4.3.1 Asbestos Dust Sampling.....	19
4.3.2 Asbestos Occupational Air Sampling.....	21
4.4 Quality Assurance .....	22
4.4.1 Sampling Design .....	23
4.4.2 Measurement Data Acquisition .....	24
<b>5.0 RECOMMENDATIONS AND CONCLUSIONS .....</b>	<b>27</b>
5.1 Pavement Assessment .....	27
5.2 Soil .....	27
5.3 Air and Dust .....	28
<b>6.0 REFERENCES .....</b>	<b>27</b>



## List of Tables

TABLE 1: SAMPLE COLLECTION, PREPARATION AND ANALYSIS .....	5
TABLE 2: PAVEMENT ASSESSMENT: SOUTH WALLACE AVENUE.....	13
TABLE 3: SOUTH HARRINGTON BUILDING SOIL SAMPLE RESULTS.....	16
TABLE 4: HEEB'S ALLEY BUILDING SOIL SAMPLE RESULTS .....	17
TABLE 5: STORY DISTRIBUTING PROPERTY SOIL SAMPLE RESULTS.....	19
TABLE 6: ASBESTOS DUST SAMPLE RESULTS .....	20
TABLE 7: ASBESTOS OCCUPATIONAL AIR SAMPLE RESULTS.....	22
TABLE 8: SOIL, DUST AND AIR QUALITY CONTROL SAMPLES .....	23

## List of Figures

Figure 1	CMC Bozeman Facility
Figure 2	Investigation Boundaries
Figure 3	Asphalt Pavement Condition and Utilities
Figure 4	Asphalt Pavement Removal or Repair Recommendations
Figure 5	SHB-Test Pit Diagram
Figure 6	Heebs Test Pit Diagram
Figure 7	Story Test Pit Diagram
Figure 8	Soil Sample Locations for SI and Previous Investigations
Figure 9	Areas of Potential and Observed Asbestos
Figure 10	NHB Attic Level
Figure 11	NHB Main Level
Figure 12	NHB Third Level
Figure 13	NHB Lower Level
Figure 14	SHB Salvation Army

## List of Appendices

APPENDIX B	Site Specific CMC Bozeman Facility SI Work Plan - HASP
APPENDIX C	Documentation of Accreditation
APPENDIX D	Tetra Tech 6-16-08 Revised Pavement Condition Assessment
APPENDIX E	Test Pit Excavation Logs
APPENDIX F	Test Pit Photo Log with Location Descriptions
APPENDIX G	Asbestos Ore Waste Volume Calculations
APPENDIX H	Soil Sample Analytical Laboratory Results
APPENDIX I	Asbestos Dust Sample Field Log Notes
APPENDIX J	Asbestos Dust Sample Analytical Results
APPENDIX K	Asbestos Occupational air Sample Analytical Results
APPENDIX L	Quality Assurance Laboratory Results for Soil, Dust, and Air Samples
APPENDIX M	Data Validation Reports



## 1.0 EXECUTIVE SUMMARY

Tetra Tech performed a Supplemental Investigation (SI) at the CMC Bozeman Facility (Facility) from December 17 – December 21, 2007, and completed test pit excavations at the Story Distributing Property on December 31, 2007, in accordance with Tetra Tech's *Final Revision – CMC Bozeman Facility Supplemental Investigation* (Work Plan) (Tetra Tech, 2007a) as referenced in the Montana Department of Environmental Quality (DEQ) December 6, 2007, approval letter. The SI focused on previously uninvestigated areas where asbestos may be located; an evaluation of pavement condition in areas suspected to contain asbestos; and, an investigation of potential airborne and settled dust concentrations of asbestos within the former ore storage/mill building and attached building addition.

The pavement assessment documented several South Wallace Avenue and City of Bozeman (City) right-of-way areas that contained a “low” Pavement Condition Index (PCI) value which is directly related to deterioration or deterioration potential of these surfaces. The surfaces evaluated were asphalt roadways/parking lots, concrete sidewalks, concrete curbs and gutters, and additional paved areas that surround buildings. Most areas were acceptable with an overall “fair-to-good” rating; however, some areas were significantly deteriorated and/or damaged. These significantly deteriorated and/or damaged areas of pavement, as well as those areas where utility work may occur, may present a potential risk for future human exposure to asbestos ore and should be addressed as part of an addendum to the DEQ-Approved 2002 Voluntary Cleanup Plan (VCP) for the Facility.

The test pit investigation focused on the alley south of Heeb's East Main Grocery (Heeb's), the Harrington property along the east elevation of the South Harrington Building (SHB), and the Story Distributing property – from the north property boundary line to 15 feet south, into the Story Distributing property. These areas were found intermittently to be visually contaminated with anthophyllite (asbestos ore) at depths ranging from 1 to 4 feet. Five test pits were excavated in the alley behind Heeb's, six test pits were excavated on the east side of the SHB, and seven test pits were excavated from the Harrington/Story Distributing property. Composite soil samples were collected for laboratory analysis from the side walls of each test pit across intervals where there was no visible asbestos was observed. Additionally, grab samples were collected from the base of each test pit, where no visible asbestos ore was noted. None of the composite or base samples contained detectable traces of asbestos. Throughout the test pit excavations, none of the environmental upwind, work zone, or downwind air samples contained detectable quantities of airborne asbestos fibers.

The dust samples collected throughout areas of the North and South Harrington buildings did not indicate a detectable quantity of anthophyllite structures throughout each level and Heating, Ventilation, and Air Conditioning (HVAC) zone in each building; rather, a single sample contained one structure of chrysotile asbestos and one structure of amosite asbestos. These fibers may have come from a variety of sources in the building or surrounding exterior environments; however, they were detected at levels below the detection limit for ASTM D 5755-03.



The occupational air samples collected during work activities performed in the North Harrington Building (NHB) during normal business activities for two consecutive days did not indicate a detectable quantity of airborne asbestos fibers. Mr. Jeff Harrington, owner of Harrington's Attic, a new and used furniture store, donned the sampling train for two consecutive days while working in the sales office, main floor, basement, attic, and loading dock of this building.

Based on this SI, Tetra Tech recommends the excavation and removal of all accessible soils containing asbestos along the east and south sides of the Harrington's building and on Story Distributing property, the alley behind Heeb's, and the Empire Building Materials property. Further, Tetra Tech recommends the implementation of a combination of protective paving and encapsulation measures, institutional control measures, and an Operations and Maintenance plan, for those inaccessible areas where asbestos contamination is known to exist or has the potential to exist. These areas include South Wallace Avenue and associated right-of-way, areas beneath buildings, and other paved areas.



## 2.0 BACKGROUND

On behalf of the City, Tetra Tech has prepared and is submitting this SI Report, for the CMC Bozeman Comprehensive Environmental Cleanup and Responsibility Act (CECRA) Facility **Figure 1**. This SI was conducted to satisfy a DEQ requirement for additional investigation of specific areas in the Facility as documented to the City in a Proper and Expeditious Letter and Scope of Work (SOW) dated November 22, 2006. Work was conducted in accordance with a Work Log Plan (Tetra Tech 2007a) approved by DEQ on December 6, 2007. Documents, such as the 2002 VCP for this Facility, containing information appropriate and relevant to the SI are cited herein and incorporated by reference.

### 2.1 SITE CHARACTERIZATION SUMMARY

The additional properties addressed in this SI are part of the existing CMC Bozeman CECRA Facility. The City requested and gained access from the owners of the Harrington property, Heeb's property, and Story Distributing, Inc. property to allow characterization of these additional areas of the Facility.

A comprehensive site characterization summary of the CMC Bozeman Facility is presented in Section 4.0 of *Environmental Assessment in the Voluntary Cleanup Plan for the CMC East Main Depot* (RTI 2002a). Previous investigations along the right-of-way west of Empire Building Materials, Inc. (EBM) revealed asbestos at a depth of 2.5 – 3.0 feet beneath ground surface (BGS) imbedded in utility concrete conduits. The asbestos was observed while digging test pits to depths of approximately one to four feet BGS by RTI (VCP Addendum Construction Completion Report dated August, 2004 (RTI, 2004) and RTI's VCP Addendum Report dated October 9, 2003 (RTI, October 9, 2003)). During RTI's supervision of the cleanup, asbestos contaminated soil was noted to have been removed down to the concrete with imbedded asbestos as well as in the area of a small piece of observable asbestos noted in the south excavation wall adjoining the NHB property line (*Revision 1, Addendum to the Voluntary Cleanup Plan for the CMC East Main Depot Facility, Bozeman, Montana* (RTI, September 23, 2003)). Additionally, RTI's previous soil investigations indicated visible asbestos in Test Pit Nos. 02-2 and 03-5, 03-7, and 03-2 and 03-3 and visible asbestos beneath the north asphalt driveway pavement of the NHB, beneath the South EBM Warehouse, and throughout the gravel yard of EBM (RTI, 2004). The asbestos contaminated soils may extend further north of RTI's Test Pit No. 03-6 as there was no confirmation test pits east of Test Pit No. 03-5 and 03-7. Previously remediated areas are outlined in Section 4.0 of this report.

In Tetra Tech's *Limited Soil Investigation Results Report* for the Nash-Finch/Bozeman Public Library property, dated July 5, 2007 (Tetra Tech, 2007b), compacted sand and gravel backfill was encountered above the native dark brown silty clay material at depths from 0 to 4 feet in the four bore holes. The intent of the July 2007 investigation was to evaluate the presence of lead in native soil under paved parking areas. Note that the presence of asbestos was not evaluated, as previous investigations have shown no detectable asbestos in this area of the Facility.

During the week of August 27, 2007, asbestos was discovered by the Montana Department of Transportation (MDT) in the right-of-way along the southwest corner of Main Street and South Wallace Avenue (adjacent to Heeb's). This asbestos was found during a MDT project to remove and replace existing sidewalk, curb, and gutter along Main Street. The asbestos appeared to be used as backfill material beneath these removed surfaces. The asbestos impacted soil appeared to extend beneath the Heeb's north-facing parking lot, under the



sidewalk to the west along Main Street, and under the newly paved southwest corner of South Wallace Avenue and Main Street.

During utility work conducted on behalf of the City on October 9, 2007, additional asbestos was found in the unpaved alley behind, and to the south of Heeb's. The extent of contamination in the unpaved alley behind Heeb's was investigated as part of this SI and these additional asbestos discoveries will be addressed in an addendum to the 2002 VCP. In March of 2008 an individual who worked at the asbestos mill at 204 South Wallace in 1957, provided information to DEQ indicating that asbestos originating from a mine other than the Karst Mine was also stored and milled at the site.

## 2.2 PURPOSE

The purpose of this SI is to conduct additional investigation of the Facility as specified in the Work Plan (Tetra Tech, 2007a). This SI addressed the following areas and conditions:

- Previously uninvestigated areas on property owned by Harrington's, Inc. (i.e. unpaved areas);
- South and east sides and the newer southern building addition on Harrington property;
- Unpaved alley south of Heeb's Grocery Store;
- Pavement condition of known asbestos containing areas at the southwest corner of South Wallace Avenue and Main Street;
- Pavement condition of South Wallace Avenue and sidewalks within the right-of-way running south from Main Street to Curtiss Street;
- Upper (northern) portion of the Story Distributing, Inc. property; and,
- Potential airborne and settled dust concentrations of asbestos within the former ore storage/mill building and attached southern building addition on the Harrington property.

These areas are outlined on **Figure 1 and Figure 2** presents previously assessed areas of the facility. Historical documentation indicates that the original Harrington building may have been utilized for asbestos storage and/or milling during asbestos operations at the Facility. The possibility exists that any asbestos fibers present in the original building may have migrated or aerosolized (suspension of particles in air) into the more recently constructed building.

The City will prepare an addendum to the 2002 VCP for this Facility to address specific elements of the SOW not included in this investigation. These elements will include but are not limited to cleanup activities on property owned by EBM, the paved utility corridor along South Wallace Avenue, and in the alley south of Heeb's. Additional remedies may be proposed in the addendum to address remaining contamination at the Facility.



### 3.0 SUPPLEMENTAL INVESTIGATION METHODS

Tetra Tech conducted the following five tasks as part of the SI at the CMC Bozeman Facility:

- Site-Specific Health and Safety Plan (HASP) development;
- A pavement condition evaluation in previously uninvestigated areas on property owned by Harrington's, Inc., throughout South Wallace Avenue from Main Street south of Curtiss Street including right-of-ways, and in the alley south of Heeb's;
- A soil assessment to evaluate the extent of asbestos contamination in accessible soils on the Harrington's, Story Distributing, and the Heeb's alley properties;
- An air-related assessment to address the interior of the two structures located on the Harrington's Property; and
- Quality Assurance/Quality Control (QA/QC) program throughout all sampling events.

**Figures 1 and 2** present the boundary of assessed and/or remediated areas; the approximate areas where excavation of contaminated soils has taken place and also areas that have been previously investigated.

#### 3.1 SUPPLEMENTAL INVESTIGATION WORK PLAN

Two separate characterizations commenced at the Facility and specifically addressed the potential for asbestos in Facility soils and air-related asbestos located inside the two Harrington buildings. The ambient air, dust, soil, and pavement condition evaluation methodologies are presented in **Table I**.

<b>TABLE 1</b> <b>SAMPLE COLLECTION, PREPARATION AND ANALYSIS</b> <b>CMC Bozeman Facility Supplemental Investigation</b>		
<b>Medium</b>	<b>Collection/Preparation</b>	<b>Analytical Method</b>
Pavement	Visual Pavement Condition Index	ASTM D5340-04
Air	ISO Method 10312	TEM
Dust	ASTM Method D5755-03	TEM
Soil	CARB Method 435	PLM with QC @ 10% TEM

#### 3.2 SITE-SPECIFIC HEALTH AND SAFETY PLAN

Tetra Tech prepared a Site-Specific Health and Safety Plan (HASP) for the SI based on the DEQ-approved Work Plan. The HASP conformed to the requirements in 29 CFR 1910.120, and generally follows the same health and safety principles documented in the *Health and Safety Plan for the CMC East Main Depot Site Voluntary Cleanup Bozeman, Montana*, (RTI, 2002b) and as included in the *Voluntary Cleanup Plan for the CMC East Main Depot, Revision 2*, (RTI, 2002a). Appendix B contains the project HASP.

It should be noted that the HASP required personnel and/or work zone-upwind/downwind ambient air monitoring during the exterior test pit sample collection and interior dust samples for asbestos (with respective methodology) in accordance with National Institute of Occupational Safety and Health (NIOSH) Method 7400. Sampling conducted during the test pit excavation



did not indicate the presence of a detectable quantity of airborne asbestos either upwind or downwind throughout each day of test pit collection; sampling was determined to be unnecessary during interior dust sample collection as work practices did not warrant sample collection.

The HASP stipulated that all personnel on site, including all subcontractors, will be trained as required by the Occupational Safety and Health Administration (OSHA) Hazardous Waste Operations and Emergency Response (HAZWOPER) 29 CFR 1910.120 standard and provide proof of such training. Due to the presence of potential hazardous substances on site, Tetra Tech required excavation subcontractors to participate in a respiratory protection program as defined in 29 CFR 1910.134. As required under this OSHA standard, all personnel on site were required to receive physician's approval before wearing negative pressure air-purifying respirators and receive fit testing for the specific respirators worn. Prior to the onset of work, Tetra Tech informed and provided the excavation subcontractor with the HASP as well as necessary training prior to starting work. Documentation of this required training is included in Appendix B.

### 3.3 PAVEMENT CONDITION ASSESSMENT

Tetra Tech performed an evaluation of the existing pavement conditions, given current property uses, and potential for future required utility work. The pavement assessment was conducted as part of an evaluation of the potential for exposure to asbestos from paved areas of the Facility. During the evaluation an assumption was made that all Facility-defined areas addressed in this SI have the potential to contain asbestos as "fill" material beneath both paved and unpaved areas. Pavement areas which were addressed primarily include South Wallace Avenue (from Main Street to Curtiss Street) including but not limited to areas beneath sidewalks and curbs, alleys that may contain pavement, and the parking lots of Heeb's and Harrington's (Figure 2).

The pavement condition assessment was conducted in accordance with use of a modified version of American Standard for Testing and Materials (ASTM) Method D5340-04 *Standard Test Method for Airport Pavement Condition Index Surveys*. This test method covers the determination of airport pavement condition through visual surveys of asphalt-surfaced pavements, including porous friction courses, and plain or reinforced jointed Portland cement concrete pavements, using the Pavement Condition Index (PCI) method of quantifying pavement condition. ASTM Method D5340-04 documentation is included in the SI Work Plan (Tetra Tech 2007a). Tetra Tech used the PCI to evaluate the relative condition of the pavements and the potential for release of asbestos from soils beneath the pavement (i.e. pavements that are deemed to be damaged have a higher risk of exposure to sub-grade asbestos).

### 3.4 SOIL SAMPLING

Generally, exterior asbestos soil sampling consisted of completing a visual assessment and/or using test pit soil sampling methodologies. The visual assessment was completed for all test pit locations and consisted of documenting visible asbestos throughout the stratified layers of soil. Visible asbestos documentation was completed in accordance with a modified version of ASTM Method E 1386-05: *Standard Practice for Visual Inspection of Asbestos Abatement Projects*. Additionally, all visual inspections of each test pit were conducted by an Asbestos Hazardous Emergency Response Act (AHERA)-accredited asbestos inspector and/or a Certified Industrial Hygienist (CIH). Documentation of accreditation is included in Appendix C.



If asbestos was noted through visual inspection in a test pit, Tetra Tech did not collect a sample for laboratory analysis. The depth of the observed asbestos was just documented on the test pit log. If visible asbestos was not noted, soil samples were collected at 6-inch depth intervals from the vertical and horizontal extent of each test pit and submitted for laboratory analysis of asbestos. In this instance, the vertical extent is characterized with one grab sample from the floor of the excavation (base sample). The horizontal extent is identified as the northerly, southerly, easterly, and westerly locations along the test pit walls from which four samples were collected and composited into one (composite sample). The pit wall composite sample consisted of soil collected at 6-inch intervals to the base of the completed test pit.

Asbestos has been found in Facility soils at the surface and from depths up to 3-feet BGS. The asbestos is often mixed with native soil and/or fill material. Tetra Tech subcontracted a licensed and insured excavation company to use a backhoe to dig test pits for the collection of soil samples. The protocol for determining the depth of the test pits and the collection of soil samples at the Facility was as follows:

- Test pits were dug to a minimum depth of 3 ft BGS.
- Soil samples for laboratory analysis were only collected when no visible asbestos had been observed at a given depth or depth interval.
- If visible asbestos was present at 3-feet BGS, excavation continued until visible asbestos was no longer present; A single composite soil sample was then collected from the side walls for the depth interval where asbestos was not observed (e.g., if asbestos was observed from 2 to 3 ft BGS in a 4 ft deep test pit, then composite samples were collected from 0 to 2 ft and from 3 to 4 ft.
- If asbestos was not visibly present in a test pit, the excavation was advanced to around 3-feet and a composite sidewall sample and a base sample were collected.
- A soil sample was also collected from the base of the excavation at its deepest point (which always corresponded to a depth at which no asbestos was observed).

Six test pits were excavated from the area east of the SHB and three composite and six grab samples were collected. Visible asbestos was present throughout SHB TP1, TP3, and TP6; however, no visible asbestos noted in SHB TP2. SHB TP4 and TP5 contained small visible pieces of asbestos as noted in the test pit logs and **Table 3**. Tetra Tech collected composite samples to represent the majority of soils in the test pits. Seven test pits were excavated from the Story Distributing property and, six composite and six grab samples were collected. Five test pits were excavated from the alley behind Heeb's and five composite and five grab samples were collected. After test pit sample collection, Tetra Tech's subcontractor backfilled and bucket-compacted all excavations.

Asbestos soil samples were collected from excavation walls at 6-inch depth intervals in each test pit and placed in pre-labeled plastic sampling containers. Samples were visually screened to evaluate whether visible asbestos was present. One duplicate sample was collected of the entire vertical depth sampled with the same amount of soil collected from each 6-inch sub sample, and two duplicate samples were collected from the sample base. Samples were collected using clean mixing bowls and hand trowels. Between test pit locations, Tetra Tech field personnel donned a new pair of nitrile gloves and decontaminated the mixing bowls and hand trowels to prevent cross-contamination.



Tetra Tech followed the Unified Soil Classification system (ASTM D-2487-92 and ASTM D-2488-93) to describe soils in each test pit. This data is presented on a standard test pit log form (Appendix E). Additionally, Tetra Tech documented each test pit location using a Global Positioning System (GPS), appropriate measurements in reference to existing structures, and photographs with each sample identification number. GPS locations are presented on the test pit log forms and the photographs are presented in Appendix F.

Following the collection of samples, chain-of-custody procedures were used to establish a written record of sample handling and movement between the sampling site and the laboratory. Each shipping container had a chain-of-custody form completed in duplicate by sampling personnel. Tetra Tech kept one copy of this form and the other copy was sent to the laboratory. The shipping container was sealed so that it was obvious if the seal had been tampered with or broken; none of the sampling container seals were broken on arrival to the laboratory.

### 3.4.1 Soil Sample Analysis

The asbestos content in soils was determined through visual inspection and using a modified “bore hole sampling methodology” of California Air Resources Board (CARB) Method 435: *Determination of Asbestos Content of Serpentine Aggregate* as documented in the SI Work Plan (Tetra Tech, 2007a). This preparation methodology states that a minimum of three samples must be submitted per “area” sampled. This soil analysis method was chosen to document the asbestos content in soils. Per the method, each composite sample was crushed to produce a material with a nominal size of less than three-eighths of an inch. Before crushing, the sample was dried.

ASTM Method C-702-80 was used to reduce the size of the crushed grab sample to a one pint aliquot. The one pint aliquot was further crushed using a Braun mill or equivalent to produce a material of which the majority was less than 200 Tyler mesh.

Soil samples were analyzed using the CARB Method 435 preparation, followed by analysis using polarized light microscopy (PLM) to 0.25 percent. The CARB Method 435 contains an abbreviated PLM analysis, but the more comprehensive PLM analysis, as outlined in U.S. Environmental Protection Agency (EPA) Method 600/R-93/116 was used.

## 3.5 ASBESTOS AIR-RELATED SAMPLING

It is believed that the original Harrington’s building, located in the 2000 block of S. Wallace, Avenue, was used as an asbestos storage building and/or for the processing of asbestos. Objectives of sampling were to define the nature and extent of any asbestos contamination of the indoor air in the Harrington’s structures, and to determine the exposure potential to those who utilize the building.

To determine if air-related surficial asbestos contamination was located in the Harrington buildings, Tetra Tech collected dust samples using ASTM D 5755-03 and air samples in accordance with International Organization for Standardization (ISO) Method 10312:1995, as described in the SI Work Plan (Tetra Tech 2007a). Tetra Tech collected dust samples in specified zones in both buildings using ASTM D 5755-03. Based on recent information indicating a lack of correlation between asbestos concentrations in dust samples and concentrations in air, the EPA has determined that the collection of dust samples alone will not adequately assess potential indoor sources of exposure. As a result, Tetra Tech also collected



activity-based air samples during building owner/employer work activities throughout a typical workday.

### 3.5.1 Asbestos Dust Sampling

Asbestos dust sampling was performed using ASTM D 5755-03, *Standard Test Method for Microvacuum Sampling and Indirect Analysis of Dust by Transmission Electron Microscopy for Asbestos Structure Number Surface Loading*. Using this methodology, Tetra Tech collected a minimum of one composite sample per building with the following parameters:

- Each composite sample consisted of 10 sub samples (aliquots) per work area in the building (a work area is defined as a segregated section in the building (e.g., office space, shop, etc.)) using the following ratio of sub sample locations:
  - Four accessible areas;
  - Four infrequently accessed areas; and,
  - Two inaccessible areas.
- When possible, the sample order included collection of one sub sample initially from each of these areas (i.e. one accessible location, one infrequently accessed and one inaccessible area), so if filter loading occurred the collected sample was representative of all three areas.
- One composite sample was collected for each floor of each building on the property;
- When possible, one composite sample was collected for each separate HVAC system per floor of each zone in each building per property; and,
- One composite sample was collected inside the return plenum of each HVAC zone in each building.

A sub sample consisted of collecting ten (10) 100 centimeter (cm) x 100 cm samples throughout these defined composited spaces. A single template was used for each composite sample; therefore, per each aliquot in the composite sample, a single template was used. For each aliquot, Tetra Tech sampled the dust surface for approximately one minute to give a total of approximately 10 minutes for each sample collected. During the collection of each aliquot – with use of the respective 25-mm sampling media cassette – Tetra Tech covered the sampling surface and collected 15-second sub samples in the following directions from within the template area:

- Side-to-side across the entire width and length of the template;
- Top-to-bottom across the entire width and length of the template;
- Northwest corner to southeast corner across the entire width and length of the template horizontally; and,
- Southwest corner to northeast corner across the entire width and length of the template horizontally.



Tetra Tech's decontamination procedure consisted of disposal of plastic gloves per composite sampling event, disposal of the template per composite sampling event, and use of a separate cassette in-between each composite sampling event.

While ASTM D 5755-95 requires the identification of fibers with a 5:1 aspect ratio, Tetra Tech requested an aspect ratio of 3:1 be analyzed by the laboratory due to recent research involving amphibole asbestos risks associated with fiber sizes less than 5 microns in length. Additionally, Tetra Tech increased the target analytical sensitivity to 20 structures per square centimeter based upon increased aliquot points – as discussed above – in the initial sampling.

Samples were generally collected from “dusty” areas (areas that may not have been cleaned previously) and were collected from horizontal surfaces in each composite area; however, “non-dusty” surfaces encountered (routinely cleaned areas along the floor, window sills, frequently vacuumed area) were also sampled. The type of each surface sampled was documented as porous (P), semi-porous (SP), or non-porous (NP) (carpet, wood, floor tile/waxed or varnished wood, respectively) and was labeled on a floor plan figure and documented in the following manner(s):

- South Harrington Building, Composite Sample 10, Sub sample 7, Porous Surface
  - SHB-10-7-P.
- North Harrington Building, Composite Sample 10, Sub sample 6, Semi Porous Surface
  - NHB-10-6-SP

Tetra Tech documented each sampling location, building level, specific type of surface, and accessibility of each aliquot from each collected sample.

More specifically, Tetra Tech collected samples from the following composite locations with sub sample identification noted onsite:

- North Harrington Building
  - Basement: Shop/Office/Vault, HVAC Room, Showroom
  - Main Level: Bitterroot Stained Glass Shop and Storage Room, Main Office/Storage Room No. 1 & No. 2, Showroom/Closet, East Dock Area, and Southwest Office/Men's and Women's Restrooms
  - Attic Level: South Showroom, North Showroom, and Break room/East Office/Hallway.
  - 3<sup>rd</sup> Level: Big Sky Aikido
- South Harrington Building
  - Salvation Army Shop & Bathroom

Analysis indicated the type of asbestos (if any) present on each composite area analyzed. Analysis was completed using transmission electron microscopy (TEM). Through use of TEM analysis for all dust and air samples analyzed, Tetra Tech was able to differentiate between the different types of asbestos present on the sample medium.

Samples were handled in accordance with ASTM D 5755-03, which included donning a new pair of nitrile gloves between composite sample locations prior to each sample. A chain-of-custody form was filled out for each composite sample, with documentation of all aliquot sample identification numbers included for that sample.



Analysis was completed by EMSL Analytical Laboratories, Inc. in West Mont, New Jersey, for all samples. EMSL is accredited by the American Industrial Hygiene Association (AIHA) for asbestos analysis and participates in National Voluntary Laboratory Accreditation Program (NVLAP). By use of TEM for all dust and air samples analyzed, Tetra Tech was able to differentiate between the types of asbestos present on the sample medium and therefore, determine whether the specific morphology and crystallization was associated with the Karst Mine anthophyllite.

### 3.5.2 Asbestos Air Sampling

For the use of ISO Method 10312:1995, *Ambient Air – Determination of Asbestos Fibers – Direct Transmission Electron Microscopy Method*, Tetra Tech collected activity-based air samples throughout two 8-hour work periods via personal air monitoring of Harrington attic employees at the Harrington North building during an average work day. During a September 12, 2007, site visit, Jeff Harrington indicated he preferred that he and/or another employee participate in sample collection. Typical daily work activities (tasks) include cleaning and moving furniture, furniture sales, office work, limited janitorial duties, and management duties (including observing employees performing all above-mentioned duties).

The 25 millimeter (mm) conductive cowl cassette with 0.45 micron pore size mixed cellulose ester (MCE) sampling filter backed by a 5.0 micron pore size MCE filter were worn by Mr. Harrington within 7-inches of the mouth/nose area throughout the duration of the sampling period. Prior to and after sample collection the flow rate of the sampling pump was calibrated to 2.0 liters per minute (lpm) using a primary source. If samples were found to be out of tolerance by +/- 10 percent of the initial calibrated flow rate, the sample would have been considered void and a retest would have been performed. No retests were performed. All field equipment was decontaminated using wet wipes prior to the start of sampling, in-between sampling events, and after sampling events to prevent contamination of the equipment.

The analysis was conducted using TEM by EMSL Analytical Laboratories, Inc. in West Mont, New Jersey. This laboratory participates in the NVLAP and conducted the analysis in accordance with the specifications found in ISO 10312 including but not limited to the following procedures:

- Analytical Sensitivity ( $0.0002 \text{ cc}^{-1}$ );
- Filter Overload Target set at 10 percent with the laboratory notifying Tetra Tech of any overloaded filters prior to proceeding with analysis;
- Counting Rules specifying that the laboratory read a minimum of 10 grid openings and continue to count structures until the required analytical sensitivity has been reached, based on the sample volume and the number of grid openings counted. The count may be terminated upon completion of the grid opening containing the 50<sup>th</sup> structure, regardless of whether or not the target analytical sensitivity has been reached; and,
- A media blank and a field blank from the same sample media lot were submitted to the laboratory for quality control.



## 4.0 RESULTS AND ANALYSIS

Tetra Tech conducted field work for the SI from December 17 - 21, 2007 and additionally on June 11, 2008, for the pavement condition assessment, air-related sampling inside the Harrington buildings, and test pit excavations for the east side of the South Harrington building and the alley behind Heeb's. Tetra Tech returned to the project site and finished with the test pit excavation of the Story Distributing property on December 31, 2007. All work was performed in accordance with the SI Work Plan (Tetra Tech 2007a). The collected data is presented in tabular form, and the results are discussed and analyzed in the associated subsections below.

### 4.1 PAVEMENT CONDITION ASSESSMENT

On December 18 and 19, 2007, and additionally on June 11, 2008, Tetra Tech conducted a pavement condition assessment throughout the following areas: South Wallace Avenue from Main Street to Curtiss Street (including areas beneath sidewalks and curbs), alleys that may contain pavement, and the parking lots of Heeb's and Harrington's. The assessment used the PCI methodology (modified from ASTM D 5340-04) and specifically included the right-of-way areas along the west and east sides of South Wallace Avenue.

Pavement rated as highly degraded may require replacement, pavement that is moderately degraded may need repair and maintenance work, and paved areas with a low degradation rating may not require repair or replacement at this time. The PCI provides a quantitative rating to allow for a qualitative assessment of the pavement surfaces. Priority of action is defined as High, Moderate, and Low where a High rating would suggest immediate replacement action. A Moderate rating would suggest that immediate repair or preventative maintenance action be taken. Low rating suggests no immediate action is required; however, an O&M evaluation should be conducted yearly.

During the initial assessment some areas were not readily accessible for assessment purposes due to inclement weather conditions; however, these areas were assessed along with additional apron areas in the Heeb's alley in June, 2008. Mr. Jess Whitford, Construction Materials Manager, with National Institute for Certification in Engineering Technologies (NICET) Level IV (highest level) certification performed the assessment along with Mr. Marco Fellin, Professional Engineer (PE), a geotechnical engineer. Tetra Tech's Revised *CMC Bozeman Facility: Pavement Assessment* (Tetra Tech 2008) is provided in Appendix D. This report provides documentation of the aforementioned areas along South Wallace Avenue which contain pavement-covered surfaces that are deteriorated and/or damaged.

The following is a general assessment of the condition of pavement along South Wallace Avenue in the study area with respect to the Low, Moderate, and High levels of pavement deterioration from the PCI:

- Main Street to Babcock Street is rated Moderate due to the increased traffic flow through this area;
- Babcock Street to Olive Street is rated Low; and
- Olive Street to Curtiss Street and beyond is rated Low.



It should be noted that within these street segments localized areas of Moderate or High levels of deterioration exist. **Figure 3** outlines the “damaged” asphaltic pavement areas of South Wallace Avenue. Areas that are not defined contain no damage. **Table 2** provides documentation of the concrete surfaces that were considered to have High or Moderate deterioration. This includes sidewalks, gutters, curbs and portions of some driveways. This data is not presented on a figure because the small sizes of the features make it difficult to show at the scale of the maps used in this report.

<b>TABLE 2</b> <b>SIDEWALK, CURB AND GUTTER ASSESSMENT: SOUTH WALLACE AVENUE</b> <b>Concrete with High to Moderate Degradation</b>		
Section	PCI	Rating
Gutter: Curtiss Street Valley Gutter	56	Moderate
Driveway: west side of South Wallace Avenue between Curtiss Street and Olive Street; Parking Lot entrance Apron	50	Moderate
Curb: west side of South Wallace Avenue, 142' north of Curtiss Street to Parking Lot entrance apron	50	Moderate
Curb: northwest radius on Olive Street	18	High
Curb: west side of South Wallace Avenue, Olive Street to Babcock Street	44	Moderate
Sidewalk: west side of South Wallace Avenue, First 22 section north of Olive Street	55	Moderate
Sidewalk: west side of South Wallace Avenue, Sections 39-46 north of Olive Street	0	High
Sidewalk: west side of South Wallace Avenue, east end of Heeb's Market, (60' length)	32	High
Sidewalk: west side of South Wallace Avenue from northeast corner of Heeb's Market, to Parking Lot entrance apron	42	Moderate
Driveway: south of alley behind Heeb's Market west of South Wallace Avenue	30	High
Driveway: south of alley behind Heeb's approximately 100 feet west of South Wallace Avenue	42	Moderate

Tetra used the PCI ratings to evaluate the potential for release of asbestos fibers in areas where asbestos may be present in soils beneath paved surfaces. Although all of these asphalt-covered areas have the potential to incur damage in the future, Tetra Tech's interpretation to the referenced ASTM Method indicates that only those areas with High or Moderate ratings contain the potential for asbestos exposure at the Facility in the immediate future. These areas are outlined in **Figure 4**.

The timing of pavement replacement in this area by the City will be primarily dependent upon pavement condition and utility replacement. City water and sewer maps indicate that the existing water main's composition along South Wallace Avenue is cast iron, the existing sewer line from south of Curtiss Street to directly north of Olive Street is polyvinyl chloride (PVC), and the existing sewer line from directly north of Olive Street to East Main is clay, as shown on **Figure 3**. The life of cast iron is typically around 40 to 60 years dependant on the conductivity and pH of the soil surrounding the cast iron, the turbidity of the water inside the water main, and the chemical composition of the water contents of the main. Therefore, this main will require repairs and/or replacement in the future. The City may also determine the need to repair/replace the clay sewer line in the future. The PVC sewer line was replaced in the previous 20 years.



The EPA guideline for exposure assessment as documented in EPA Federal Register Notice: *Guidelines for Exposure Assessment* EPA Document No. 600/-Z-92/001, indicates the following additional environmental concerns for release and transport for the potential fate of the asbestos:

1. Common intrusive activities performed by residents (due to the right-of-way extending to the sidewalks which are approximately 6-feet from the curb stops)
  - a. Rototilling of soils in flower and vegetable gardens;
  - b. Rototilling for installing new landscaping when the existing lawn is dead;
  - c. Digging holes for planting trees and bushes;
  - d. Disturbance of the grass-covered yard soil from activities such as weeding, mowing the grass, aerating, and habitual digging by pets and wild animals;
  - e. Disturbances of sparsely vegetated areas of yard by walking, playing, biking, mowing, etc.;
  - f. Management of excavated soils by bagging and floor sweeping; and,
  - g. Disturbance by children of exposed soils.
2. Natural processes
  - a. Forces exerted by wind currents on existing free asbestos fibers in soil at the surface or excavated soils due to the above activities; and,
  - b. Forces exerted on asbestos-containing debris by shifting soils due to extreme changes in temperature, precipitation, or other natural processes.
3. Examples of activities that may result in large amounts of excavated soils and a resultant on-going source of asbestos release in air
  - a. Planting trees or bushes;
  - b. Excavating dead trees and bushes;
  - c. Outdoor minor construction such as installing an in-ground hot tub, play equipment, deck, patio fences or other structures;
  - d. Installing or repairing sprinkler systems;
  - e. Installing decorative pathways on the grass-covered yard; and,
  - f. Performing maintenance on underground utility service lines.
4. Examples of mechanisms by which asbestos may be transported outdoors or indoors
  - a. Wind transport through open doors and windows; and,
  - b. Track-in of adhered fibers on clothing and shoes of children, adults, and animals.



## 4.2 SOIL SAMPLING

Tetra Tech performed soil sampling and characterization throughout three separate areas at the Facility from December 19 - 28, 2007. All field work was conducted in accordance with methodology detailed in Section 3.4. A summary of the results and characterization of the soil samples collected by this investigation are presented below. Soil sample locations from this and previous investigations are presented on **Figure 5**.

### 4.2.1 South Harrington Building

The South Harrington building (SHB) was assessed on December 19, 2007. The assessed area was along the east side of the building and consisted of an approximately 7-foot wide by 100-foot long area of soil along the exterior concrete foundation/footing wall on the east side of the SHB and against the exterior concrete foundation/footing wall of the south North Harrington Building (NHB) dock. This SI area adjoined the "Previously Assessed Area" near the City library as documented in **Figure 2**. Visual assessment indicated the presence of asbestos in five of the six test pits (SHB TP-1, SHB TP-2, SHB TP-3, SHB TP-4, and SHB TP-6) with depths ranging from 0.5-feet to 4.0-feet BGS. Soil sampling results, visual observations of asbestos and the locations of each test pit relative to existing structures are presented on test pits logs in Appendix E and photographs of the test pits are presented in Appendix F. The wall and base of SHB TP-2 did not indicate observable asbestos; however, visible asbestos was noted in the pile of soils removed from the test pit (test pit tailings); therefore, the depth interval of the asbestos is unknown. Test pit logs additionally document different soil classifications and where native soil was encountered.

In test pits where native material was encountered at a depth less than three feet, a base sample was collected from the asbestos/native soil interface at 2.5 feet in depth. These test pits were advanced to three feet and the logs noted no visible asbestos. A cross-section of this area is shown on **Figure 6**. Tetra Tech estimates the volume of asbestos is 5.0 cubic yards (yd<sup>3</sup>) using actual depth intervals with visible asbestos, however, we estimate 80 yd<sup>3</sup> will need to be removed due to over-excavation, and the likelihood of discovering asbestos not encountered by the test pits. This should be considered a more likely waste volume for this area. With an estimated volume of 80 yd<sup>3</sup>, and assuming a 30 percent contingency, this equates to approximately 104 yd<sup>3</sup> of asbestos impacted soil to be removed. Tetra Tech's calculations are included in Appendix G.

Test pit data from the composite and base of each test pit is presented in **Table 3**. It should be noted that none of the laboratory samples reported a detectable concentration of anthophyllite asbestos. Laboratory soil analytical results are presented in Appendix H.

Based on visual evidence of asbestos within the test pit excavations and the randomness of test pit locations, it is Tetra Tech's opinion that all soils along the east side of the SHB are contaminated with asbestos to each respective test pit depth. All volume calculations have been based on these assumptions.



**TABLE 3**  
**SOUTH HARRINGTON BUILDING SOIL SAMPLE RESULTS**  
**Composite and Base Samples for SHB TP-1 through SHB TP-6**

Test Pit (TP) Sample Number with Soil Classification	Location of Sample*	Sample Depth (FT)	Asbestos Soil Result	Visual Observation of Asbestos
10 SHB TP-1; Dark Brown Clayey Silts w/no or very little gravels	Base	4.0	ND**	Visual observation to 3.5 ft
11 SHB TP-2; Dark Brown Clayey Silts w/no or very little gravels	Base	4.0	ND	Visual observation to 3.5
12 SHB TP-2; 12"-minus with poorly graded sandy soil with gravels	Side Wall Composite	0 – 3.0	ND	Asbestos in soils removed from test pit***
13 SHB TP-3; Dark Brown Clayey Silts w/no or very little gravels	Base	2.5	ND	Visual asbestos to 2ft
14 SHB TP-4; Dark Brown Clayey Silts w/no or very little gravels	Base	4.0	ND	Visual asbestos to 3.5 ft
15 SHB TP-4; 10"-minus with poorly graded sandy soil with gravels	Side Wall Composite	0 – 3.0	ND	Asbestos in soils removed from test pit***
16 SHB TP-5; Dark Brown Clayey Silts w/no or very little gravels	Base	2.5	ND	No visual asbestos
17 SHB TP-5; 10"-minus with poorly graded sandy soil with gravels	Side Wall Composite	0 – 2.5	ND	Asbestos in soils removed from test pit***
18 SHB TP-6; 10"-minus with poorly graded sandy soil with gravels	Base	2.5	ND	No visual asbestos

\* Where no composite sample is identified for a specific test pit, the asbestos was present to the full depth of the pit.

\*\* ND = None Detected based upon 0.25% Target Analytical Sensitivity with CARB 435

\*\*\* Asbestos visually noted in excavation material alongside test pit but not in test pit

#### 4.2.2 Heeb's

The alley directly south of the Heeb's Grocery building was assessed on December 20, 2007. The assessed area consisted of an approximately 18-foot wide by 158-foot long area of soil that extends from the exterior concrete foundation/footing wall of the Heeb's building, across the alley and to the north edge of adjoining properties on the south side of the alley (residential properties and an apartment complex). The assessed area is outlined on **Figure 2**.

Soil sample results from test pit bases and pit wall composites are presented in Table 4. It should be noted that none of the test pits samples submitted for laboratory analysis indicated a detectable concentration of anthophyllite asbestos. Laboratory soil analytical results are located in Appendix H.

With the exception of Heeb's TP-2, the visual assessment indicated the presence of asbestos in all of the test pits excavated in this area (**Figure 7**). Asbestos was observed on the soil surface and to a depth of 1.5-feet below ground surface in four of the five test pits located along the north and south edges of the alley. It is Tetra Tech's opinion that the asbestos is present throughout the assessed portion of the alley, hence the entire area has been included in waste volume calculations. Test pits logs and presented in Appendix E and photographs of the test pits are presented in Appendix F, with locations for each test pit noted with respect to existing structures. In addition to the test pits, visible asbestos was observed within two to three feet of test pit TP-2 along a concrete driveway. The test pit logs additionally document soil classifications and the depths at which native soil was encountered.



**TABLE 4**  
**HEEB'S ALLEY BUILDING SOIL SAMPLE RESULTS**  
**Composite and Base Samples for HEEB's TP-1 through HEEB's TP-5**

Test Pit (TP) Sample Number with Soil Classification	Location of Sample*	Sample Depth (FT)	Asbestos Soil Result	Visual Observation of Asbestos
1 HEEBS TP-1; Brown Clayey Silts w/no or very little gravels	Base	3.0*	ND**	Visual asbestos 0-3
2 HEEBS TP-2; Brown Clayey Silts w/no or very little gravels	Base	3.0	ND	No visual asbestos
3 HEEBS TP-2; Dark Brown 5-inch minus road mix with gravels	Pit Wall Composite	0 – 3.0***	ND	No visual asbestos
4 HEEBS TP-3; Brown Clayey Silts w/no or very little gravels	Base	3.0	ND	Visual asbestos 0-3
5 HEEBS TP-3; Dark Brown 5-inch minus road mix with gravels	Pit Wall Composite	0 – 3.0	ND	No visual asbestos
6 HEEBS TP-4; Brown Clayey Silts w/no or very little gravels	Base	3.0	ND	Visual asbestos 0-5
7 HEEBS TP-4; Brown Clayey Silts w/no or very little gravels	Pit Wall Composite	1.5 – 3.0	ND	Visual asbestos 0-5
8 HEEBS TP-5; Brown Clayey Silts w/no or very little gravels	Base	3.0	ND	Visual asbestos 0-1.5
9 HEEBS TP-5; Brown Clayey Silts w/no or very little gravels	Pit Wall Composite	1.5 – 3.0	ND	Visual asbestos 0-1.5

\* Where no composite sample is identified for a specific test pit, the asbestos was present to the full depth of that test pit.

\*\* ND = None Detected based upon 0.25% Target Analytical Sensitivity with CARB 435

\*\*\* Asbestos was observed in expansion joint of concrete driveway near this excavation

Tetra Tech collected samples from the following five test pits: Heeb's TP-1, Heeb's TP-2, Heeb's TP-3, Heeb's TP-4, and Heeb's TP-5. Samples were collected from the base of each test pit down to the 3-foot minimum test pit depth. A cross-section summarizing the test pit findings is shown on **Figure 7**. Tetra Tech estimates the actual volume of asbestos contaminated soil is 123 yd<sup>3</sup>, however we estimate 227 yd<sup>3</sup> of soil will need to be removed due to over-excavation and the likelihood of discovering asbestos not encountered by the test pits. With an estimated volume of 227 yd<sup>3</sup>, and assuming a 30 percent contingency, this equates to approximately 295 yd<sup>3</sup> of asbestos to be removed. Tetra Tech's calculations are included in Appendix G.

Based on visual evidence of asbestos in four of five completed test pits and on the surface in two locations along the alley, it is Tetra Tech's opinion that soils along the alley south of the Heeb's building are contaminated with asbestos to a depth of approximately 1.5 feet. All volume calculations have been based on these assumptions. In addition, it is likely that asbestos impacted soil found in the alley behind Heeb's was used as "fill" material to increase the elevation of the alley prior to construction of the apartment complex (located southwest of Heeb's). Tetra Tech understands the "fill" material was added to allow for a proper apron assisting the apartment complex patron with access from/into the alley. It is with this knowledge that Tetra Tech suggests that the asbestos "fill" material may extend beneath the apartment complex north apron and westerly down the rest of the length of the alley.

#### 4.2.3 Story Distributing Property

The Story Distributing property was assessed on December 28, 2007. The assessed area consisted of an approximately 100-foot wide by 15-foot long area of soil along the exterior concrete foundation/footing wall 15 ft south of the SHB (**Figure 8**). This SI area adjoined the



previously assessed area on the City library property. The visual assessment indicated the presence of asbestos from depths of 0.0-feet to 3.5-feet in the seven test pits in this assessment area as shown on test pits logs and photographs in Appendices E and F, respectively. The location for each test pit is presented on the logs with respect to existing structures. Tetra Tech collected samples from the following six test pits: Story TP-1, Story TP-2, Story TP-3, Story TP-4, Story TP-5, and Story TP-7; Tetra Tech did not collect additional soil samples from Story TP-6 as this test pit only contained engineered 1½-inch minus road base material due to this location's former documented excavation (RTI, 2004). Test pit logs additionally document soil classifications and depths at which native soil was encountered. Only test pits Story TP-1 through Story TP-3 were documented as containing visible asbestos. No visible asbestos was noted on the surface at the time of sampling. A cross-section summarizing the test pit findings of this area along with native soil depths is shown on **Figure 8**.

Tetra Tech estimates the actual volume of asbestos contaminated soil is 64 yd<sup>3</sup>, as represented by visible asbestos in each test pit. However, we estimate 78 yd<sup>3</sup> of soils will need to be removed due to over-excavation and discovery of materials not encountered by the test pits. With an estimated "bank" volume of 78 yd<sup>3</sup>, and assuming a 30 percent contingency, this equates to approximately 101 yd<sup>3</sup> of asbestos to be removed. Tetra Tech's calculations are included in Appendix G.

Soil sample results from test pit bases and pit wall composites are presented in **Table 5**. It should be noted that none of the test pits samples submitted for laboratory analysis indicated a detectable concentration of anthophyllite asbestos. Laboratory soil analytical results are presented in Appendix H.

Based on evaluation of visual evidence of asbestos in test pits it is Tetra Tech's opinion that soils along the north side of the Story Distributing property are contaminated with asbestos to the depths shown in **Table 5**. All volume calculations have been based on these assumptions and the assumption that the volumetric waste extended up to the nearest test pit that did not indicate any asbestos. For these volumetric waste calculations, the double end area method was used. Additionally, it is Tetra Tech's opinion, based on previous site experience, that asbestos may need to be remediated further south of the boundary established by this SI. This is due to the sampling methodologies previously used to determine the nature and extent of anthophyllite presence on the Story Property.

Based upon the findings of the soil sampling program on the South Harrington Building, Heeb's and Story Distributing properties, we have identified areas where asbestos has either been observed or may potentially exist. These areas are outlined on **Figure 9**. These areas were identified based upon evaluation of soil sample results and observations collected to date by this and previous investigations at the Facility.



<b>TABLE 5</b> <b>STORY DISTRIBUTING PROPERTY SOIL SAMPLE RESULTS</b> <b>Composite and Base Samples for STORY TP-1 through STORY TP-7</b>				
Test Pit (TP) Sample Number with Soil Classification	Location of Sample*	Sample Depth (FT)	Asbestos Soil Result	Visual Observation of Asbestos
19 STORY TP-1; Poorly graded dark brown silty sand with gravels	Pit Wall Composite	1.5 – 4*	ND**	Visual asbestos from 0-1.5'
20 STORY TP-1; Light Brown Clayey Silts w/no or very little gravels	Base	4.0	ND	No visual observation
21 STORY TP-2; Poorly graded dark brown silty sand with gravels	Pit Wall Composite	3.5 – 4	1 Structure (Chrysotile)	Visual asbestos from 0-3.5'
22 STORY TP-2; Light Brown Clayey Silts w/no or very little gravels	Base	4	ND	No visual asbestos
23 STORY TP-3; Poorly graded dark brown silty sand with gravels	Pit Wall Composite	1.5 – 3	ND	Visible asbestos from 0-1.5'
24 STORY TP-3; Light Brown sandy silt with gravels	Base	3	ND	No visible asbestos
26 STORY TP-4; Duff layer, sandy silt with 6" minus cobbles, dark brown silty sand, light brown sandy silt with gravels	Pit Wall Composite	0 – 3.0	ND	No visible asbestos
27 STORY TP-4; Light Brown sandy silt with gravels	Base	3	ND	No visible asbestos
28 STORY TP-5; Dark brown silty sand and 10-inch minus cobbles, light brown sandy silt with gravels	Pit Wall Composite	0 – 3.0	ND	No visible asbestos
29 STORY TP-5; Light Brown sandy silt with gravels	Base	3	ND	No visible asbestos
30 STORY TP-7; 1.5-inch minus road mix, 3-inch minus cobbles with dark brown clayey sand	Pit Wall Composite	0 – 3.0	ND	No visible asbestos
31 STORY TP-7; Light Brown sandy silt with gravels	Base	3	ND	No visible asbestos

\*, When asbestos was present to the full depth of a test pit no composite sample was collected.

\*\* ND = None Detected based upon 0.25% Target Analytical Sensitivity with CARB 435

### 4.3 ASBESTOS AIR-RELATED SAMPLING

Tetra Tech conducted both surficial dust sample collection and occupational air sample collection from December 17 to December 18, 2007, in accordance with referenced methodologies in Section 3.4. The following sections present air sampling results.

#### 4.3.1 Asbestos Dust Sampling

Tetra Tech collected 14 separate dust sample cassettes from the lower level, main level, attic level, and third level of the NHB that represent 122 aliquot samples from porous, semi-porous, and non-porous surfaces. Two samples consisted only of one sample area per cassette primarily due to the fact that only one HVAC zone return air plenum exists in the third floor and only one return plenum of two possible plenums were accessible along the main floor. Appendix I contains Tetra Tech's asbestos dust sample field log notes from the horizontal dust surface collection process. Additionally, Appendix I provides detailed documentation as to the specific surface types [Non-Porous (NP), Semi-Porous (SP), or Porous (P)] for each separate aliquot sampling point as well as documentation of the different accessibility characteristics with respect to the order with which the aliquot points were sampled. Generally, the aliquot sampling order was followed to include a non-accessible area, infrequently accessed area, and accessible area for the first three aliquot sample points to preclude filter overloading past the



first three collected aliquots. However, sampling variability precluded this from occurring for every collected dust sample. **Figures 10 - 14** present sample point locations, order of aliquot samples, and porosity characteristics for both the NHB and SHB.

Dust sample analyses reported no samples with detectable concentrations of asbestos structures (**Table 6**), which indicates that asbestos has either been previously removed or was not transported into the NHB or SHB. The NHB was built in 1927 and the SHB was added in the early 1980s. Asbestos may have been used as fill material beneath the SHB; however, Tetra Tech's dust sampling did not indicate a detectable or quantifiable amount of asbestos in this building on the sampled horizontal surfaces. Historical documentation suggests that asbestos was stored in the NHB and may have been milled into commercial products in this structure; however, evaluation of dust sampling results did not indicate a detectable or quantifiable amount of asbestos in this structure on the sampled horizontal surfaces. Asbestos appears to have been used as fill material beneath the concrete dock along the northeast end of the NHB, which was added in the late 1970s. Asbestos may also have been used as fill material beneath stairway enclosures and/or docks along the north, east, and west sides of the NHB, as these structures were also added to the original building after construction. Appendix J provides laboratory analytical data for the dust samples.

Sample 31 was documented to have detectable asbestos structures of amosite and chrysotile at levels below the limit of detection for ASTM D 5755 - 03. These samples were analyzed using transmission electron microscopy (TEM). It is Tetra Tech's opinion that these structures may have come from interior building components or may have been brought into the building from exterior sources. Considering the age of the building and the fact that multiple pieces of furniture are purchased from a variety of locations, asbestos structures at these levels would be considered normal for such commercial structures.

<b>TABLE 6</b> <b>ASBESTOS DUST SAMPLE RESULTS</b> <b>North &amp; South Harrington Building</b>			
Sample ID with Area Sampled*	Area Sampled (cm <sup>2</sup> )	Asbestos Type	Asbestos Structures
22 SHB – 1: Salvation Army Shop & Bathroom	1000	NA**	<3***
25 NHB – 1; Main Level SW Office and Men's/Women's Bathroom	1000	NA	<3
26 NHB – 2; Main level South Showroom/North Showroom w/closet	1000	NA	<3
27 NHB – 3; Main Floor entry hall, Main Office, Storage Rooms # 1 & 2	1000	NA	<3
28 NHB – 4; Main Level – East Dock Area	1000	NA	<3
29 NHB – 5; 3 <sup>rd</sup> Level – Big Sky Aikido	1000	NA	<3
30 NHB – 6; Main Floor – Bitterroot Stained Glass: Shop and Storage	1000	NA	<3
31 NHB – 7; Lower Level – Basement Showroom	1000	Chrysotile, Amosite	<3
32 NHB – 8; Lower Level – Basement HVAC Room	1000	NA	<3
33 NHB – 9; Lower Level – Basement Shop, Office, Vault	1000	NA	<3
34 NHB – 10; Attic Level – South Showroom	1000	NA	<3
35 NHB – 11; Attic Level – North Showroom	1000	NA	<3
36 NHB – 12; Attic Level – Break room, East Office, Hallway	1000	NA	<3
37 NHB – 13; 3 <sup>rd</sup> Floor – Big Sky Aikido HVAC Return Plenum	100	NA	<3
38 NHB – 14; Main Floor HVAC Return Plenum	100	NA	<3

\* As included in Appendix A Figures –10 - 14

\*\* NA = Not Applicable

\*\*\* < 3 = below the limit of detection for ASTM Method D5755-03 for asbestos counting criteria of 3:1 ratio



### 4.3.2 Asbestos Occupational Air Sampling

Tetra Tech collected two occupational air samples from Mr. Jeff Harrington on December 17 and 18, 2007, in accordance with the methodology referenced in Section 3.4. Throughout the course of each sampling event Tetra Tech monitored the air flow and sampling train to ensure that it was functioning at the desired calibrated flow rate with the attached equipment. Mr. Harrington's store opens for business at 0900 and closes at 1730 – 1800 Monday through Saturday.

On December 17, Mr. Harrington reported that the following tasks were performed throughout the course of his workday:

- 0950 – 1010: Working at desk in Main Level Front Office;
- 1010 – 1030: Steam cleaning in Lower Level Basement Shop Area;
- 1030 – 1230: Sales and assisting customers throughout Lower, Main, and Attic Level;
- 1230 – 1415: Furniture assembly in Main Level North Shop Area;
- 1415 – 1440: Sales in the Lower Level Basement Office and in Main Level North Dock;
- 1440 – 1530: Phone service and sales questions in Main level Front Office;
- 1530 – 1630: Furniture assembly in Main Level North Shop and Lower Level Basement Shop;
- 1630 – 1715: Sales and loading/unloading furniture in Attic South Shop, Main Level Shop area, Lower Level Shop area, and Main level North/West Loading Docks; and,
- 1715 – 1730: Sales at Main Level Front Office and Main Level Shop areas.

On December 18, Mr. Harrington reported that the following tasks were performed throughout the course of his workday:

- 0900 – 1015: Sales at Main Level Front Office;
- 1015 – 1045: Steam cleaning in Lower Level Basement Shop;
- 1045 – 1130: Sales calls and loading customers throughout Attic Level South Shop and Main Floor Shop;
- 1130 – 1140: Steam cleaning in Lower Level Basement Shop;
- 1140 – 1230: Assisting customers at Main Level North Loading Dock, Main Level Front Office, and Attic Level North/South Shop areas;
- 1230 – 1325: Furniture assembly in Attic Level South Shop area;
- 1325 – 1430: Sales in Attic Level South Shop area, Lower Level Basement Shop area, and Main Floor Shop area;
- 1430 – 1500: Stocking and furniture assembly in Main Floor Shop area; and,
- 1500 – 1621: Furniture assembly and loading at Main Floor Shop area and Main Floor North Dock.

None of the analyzed air samples indicated detectable concentrations of asbestos fibers using TEM. **Table 7** includes a summary of occupational air sample results. Appendix K contains the laboratory occupational air sample analytical results.



EPA's recommended framework titled *Framework for Investigating Asbestos-Contaminated Superfund Sites*, dated September 2008, describes the criteria used to assess risk to asbestos exposure for inhalable fibers with the following parameters:

- ELCR = excess lifetime cancer risk for less-than-lifetime scenario;
- EPC = the scenario-specific time exposure point concentration generated from activity-based sampling;
- TWF = the scenario-specific time weighting factor; and,
- IUR = the inhalation unit risk corresponding to the age at first exposure and exposure duration for the exposure scenario.

<b>TABLE 7</b> <b>ASBESTOS OCCUPATIONAL AIR SAMPLE RESULTS</b> <b>December 17 – 18, 2007 NHB – Mr. Jeff Harrington</b>			
Sample ID with Date Sampled	Liters of Air Sampled	Asbestos Type	Asbestos Structures/cubic centimeters
45 Field Blank – (FB-1)	NA*	NA	NA
46 Media Blank-1	NA	NA	NA
47 Media Blank-2	NA	NA	NA
48 P-121707-01, December 17, 2007	932.6	1 Structure Anthophyllite	<0.00066**
49 P-121807-01, December 18, 2007	857.7	NA	<0.00112

\* NA = Not Applicable

\*\* ND = Non Detected with an analytical sensitivity of 0.22 structure/liter for sample ID 48-P-121707-01 and 0.38 structures/liter for sample ID 49-P-121807-01 in accordance with ISO Method 10312

Subsequently, the following evaluation of the “worst-case” exposure sample (Sample 48-P-121707-01) was used as the task-based sample of a general exposure for an individual that works or is a patron at the Harrington Attic and is exposed daily completing the above-referenced tasks:

- 1 structure of anthophyllite was identified with 932.6 liters of air sampled. This equates to 932,600 of cubic centimeters (cc) of air;
- The sample concentration is 1 structure/932,600 cc =  $1 \times 10^{-6}$  s/cc;
- $1 \times 10^{-6}$  s/cc; TWF = (8 hours exposure estimated per day/24hours per day)\*(250 days exposed per year/365 days in a year) = 0.228;
- IUR is based upon 25 years exposure starting at age 20;
- IUR = 0.066 s/cc (EPA,2008);
- ELCR = EPC \* TWF\*IUR
- ELCR =  $1 \times 10^{-8}$ .

The risk to employees and/or individuals that give patronage to Harrington's is less than DEQ's total excess cancer risk of  $1 \times 10^{-5}$  for carcinogens as noted in DEQ's Voluntary Cleanup and Redevelopment Act Application Guide (DEQ, 2002). The absence of asbestos fibers in the dust wipes and air samples collected suggests little risk of indoor asbestos concentrations at the facility.

#### 4.4 QUALITY ASSURANCE

Tetra Tech collected quality control samples throughout the collection of environmental field samples to provide quality assurance and validity to the sampling results for the soil samples



collected from the test pits, dust samples collected from the interior of the NHB and SHB, and from the occupational air samples. Quality control samples consisted of field blanks, media blanks, and duplicate samples as required by the respective sampling methodologies and as documented in the SI Work Plan (Tetra Tech 2007a). Quality control sampling results are presented in **Table 8**. Appendix L contains laboratory analytical data for the QA sample results. Appendix M contains Tetra Tech's data validation reports for the soil, dust, and air samples collected during this SI.

<b>TABLE 8</b>						
<b>SOIL, DUST, and AIR QUALITY CONTROL SAMPLES</b>						
<b>Matrix</b>	<b>Analytical Method</b>	<b>Type of Sample</b>	<b>Sample ID</b>	<b>Sample Result</b>	<b>No. of Collected Samples/ Method</b>	<b>SI Work Plan Requirement/ Sample Type</b>
<b>Soil</b>	CARB 435 w/TEM 1000 Point Count	Duplicate	19-HEEBS-TP-4	ND* for Asbestos/ <0.1% asbestos	1	1
	CARB 435 w/PLM 400 Point Count	Duplicate	25-Story-TP-3	ND for Asbestos/ <0.25% asbestos	1	1
	CARB 435 w/PLM 400 Point Count	Duplicate	12-SHB-TP-2	ND for Asbestos/ <0.25% asbestos	1	1
	CARB 435 w/PLM 400 Point Count	Blank	MDT-111307-Q1	ND for Asbestos/ <0.25% asbestos	1	1
<b>Dust</b>	ASTM D5755-03 3:1 ratio	Field Blank	23-NHB-FB-1	ND for Asbestos/ < 3 Structures	2	2
			24-NHB-FB-2	ND for Asbestos/ < 3 Structures		
		Media Blank	20-NHB-Media Blank 1	ND for Asbestos/ < 3 Structures	2	2
			21-NHB-Media Blank 2	ND for Asbestos/ < 3 Structures		
<b>Air</b>	ISO Method10312	Field Blank	45-FB-1	ND for Asbestos/ < 23 structures/mm <sup>2</sup>	1	1
		Media Blank	46-Media Blank-1	ND for Asbestos/ < 23 structures/mm <sup>2</sup>	2	2
			47-Media Blank-2	ND for Asbestos/ < 23 structures/mm <sup>2</sup>		

Procedures described in this section were designed to guide quality assurance. This section presents a discussion of the SI methods used to ensure data validity throughout the sample collection and analysis for this SI, including sample identification, chain-of custody, shipping, field blanks, method blanks, duplicates, and laboratory analytical methodology through the sampling design used to characterize the Facility.

#### 4.4.1 Sampling Design

Section 2.2 of the SI Work Plan (Tetra Tech 2007a) details sampling protocols, including the types and numbers of samples, which were selected based on review of historic data and previous investigations completed at the Facility. The sampling design for the various media is described below.



#### **4.4.1.1 Pavement Condition Evaluation**

The visual assessment of pavement currently found in the SI Work Plan was used to characterize the degradation of current pavement conditions.

#### **4.4.1.2 Asbestos Soil Sampling**

Test pit asbestos soil sampling was used to estimate the quantity of asbestos impacted soil anthophyllite in soil present in the study area.

#### **4.4.1.3 Asbestos Air Sampling (Interior Dust Samples)**

Interior dust samples in the Harrington buildings evaluated whether anthophyllite structures exist along horizontal surfaces inside each of the buildings. Note that the North Harrington building has been documented to have stored asbestos and the South Harrington building has been documented as possibly having asbestos backfill material beneath the structure.

#### **4.4.1.4 Asbestos Air Sampling (Interior Worker Task Sampling)**

Interior worker task sampling evaluated whether if throughout the course of a work day, Harrington's Furniture employees are exposed to anthophyllite asbestos present in the air.

### **4.4.2 Measurement Data Acquisition**

The type and quantity of samples, sample identification, sampling methods, sample handling, chain-of-custody procedures, and analytical methods required for field investigations at the Facility are described in Section 2.2 of the SI Work Plan (Tetra Tech, 2007a). These measurement data acquisition tools were used throughout the collection of data for this SI with only the following derivations: no soil samples were collected in test pit Story TP-6; and, no HVAC dust samples were collected from specific areas of the return plenum on the 3<sup>rd</sup> Level and Main Level of the NHB due to the HVAC ventilation system design. Sample No.'s NHB-7 and NHB-8 contain aliquots that represent the HVAC room, including horizontal areas in the return as noted in Appendix I. No data was collected from the negatively-pressurized return plenum in these spaces due to limitations on accessibility, however, other samples from the system are believed to be reflective of conditions. It should be noted that the HVAC system was installed during the renovation process after the Harrington family took over ownership of the building.

#### **4.4.2.1 Field Quality Control Sampling**

##### ***Soil Sampling***

For the 17 composite samples collected from the side walls of the test pits, one duplicate sample for the complete side wall set was submitted to the laboratory for analysis. Additionally, one blank sample was submitted to the laboratory for the complete side wall assessment. The blank sample consisted of using soil that had previously been analytically tested for asbestos and was known not to contain asbestos. The purpose of the QA/QC sample collection is to ensure the laboratory does not enter sample contaminants into their sample handling procedures as well as to show that Tetra Tech does not enter contamination by route of sample handling into its sample collection process. Documentation of these blank samples increases the sample collection validity and accuracy for this SI.



For the 34 grab and composite samples collected, three duplicate samples were collected and submitted to the laboratory for analysis. One duplicate was from the set of composite test pit side wall samples, and two duplicates were from the set of test pit base samples. One of the duplicate samples (No. 19-Heebs-TP4) was reanalyzed to a higher level of sensitivity for additional confirmation of analytical results. Additionally, one blank sample was submitted to the laboratory.

Ten percent of soil samples collected were analyzed as specified above; but also analyzed using TEM, with the CARB 435 preparation method, to 0.10 percent.

### ***Dust Sampling***

Prior to the collection of the asbestos dust samples, two media blank samples from the lot of filter media cassettes were analyzed in accordance with sample methodology to ensure that these specific media were not contaminated with asbestos fibers. During collection of the dust samples, and in accordance with the method, Tetra Tech submitted one blank for 10 percent of the dust samples collected. This sample was collected by uncapping the filter cassette cap and allowing it to be exposed to building air for 30 seconds, thus acting as a field blank and providing sampler error information. None of the field or media blank cassettes contained a detectable concentration of asbestos fibers.

### ***Air Sampling***

One media blank sample and one field blank sample were submitted for analysis by ISO Method 10312 to meet a minimum suggested level of 20 percent for the laboratory samples submitted. Additionally, prior to the sampling and in accordance with ISO Method 10312, Tetra Tech submitted two cassettes from the lot of provided samples for TEM analysis to determine the mean asbestos structure count. If the mean count for all types of asbestos structures was found to be more than 10 structures/square millimeter, or if the mean fiber count for asbestos fibers and bundles longer than 5 microns was found to be more than 0.1 fibers per square millimeter, then the media lot would have been rejected. No asbestos fibers were detected on the media or field blank samples.

#### **4.4.2.2 Laboratory Quality Control**

EMSL Analytical, Inc., the laboratory chosen to analyze all asbestos samples, participates in the National Voluntary Laboratory Accreditation Program (NVLAP). Participation in this national program includes quarterly round-robin samples for analytical asbestos detection. These prepared samples include a known concentration of asbestos; when the laboratory performs analysis of these “spiked” samples their analysts must fall within the allowable standard deviation for the specific sample analyzed. Participation in this program ensures both precision and accuracy of both the equipment used in the analysis and the analyst's themselves. By subcontracting a laboratory participating in NVLAP, Tetra Tech ensured analytical results are both precise and accurate.

#### **4.4.2.3 Equipment Operation and Calibration**

All field and laboratory equipment was operated, maintained, and calibrated in accordance with applicable methodologies while using the manufacturer's recommended procedures. Section 2.2 of the DEQ-approved SI Work Plan (Tetra Tech, 2007a) details the analytical methods,



which in turn specify the laboratory equipment operation, maintenance, and calibration procedures.

#### **4.4.2.4 Data Management**

The Tetra Tech project manager was responsible for ensuring that project personnel have the most current version of this SI and other project planning documents. The Tetra Tech project manager maintained project files and project documents in Tetra Tech's Great Falls then Helena, Montana, office.

Analytical laboratory data as well as pertinent field notes/data was directly downloaded onto the Great Falls server. During report generation and throughout the project, the Great Falls server was backed up daily to prevent loss of data.

The SI report includes field notes, field logs, field forms, chain-of-custody records, evaluation of data quality, and analytical reports. Tetra Tech's project manager performed internal quality assurance audits to ensure data collection and data management, including data review, verification, and validation were performed in accordance with the SI objectives.



## 5.0 RECOMMENDATIONS AND CONCLUSIONS

Tetra Tech performed a Supplemental Investigation at the CMC Bozeman Facility in December 2007 in accordance with Tetra Tech's SI Work Plan. The SI focused on previously uninvestigated areas where asbestos impacted soil may be located, an evaluation of pavement condition of areas known or suspected of containing asbestos, and, an investigation of potential airborne and settled dust concentrations of asbestos within the former ore storage/mill building and attached building addition. Our recommendations and conclusions are summarized below.

### 5.1 PAVEMENT ASSESSMENT

Using pavement assessment as a tool in the evaluation of the overall assessed area included in the Facility, our recommendations relative to pavement that may be covering asbestos are as follows:

- All areas of asphalt and Portland cement concrete rated High to Moderate for deterioration (**Figure 4**) should be replaced or repaired using similar construction materials;
- Contractors involved in pavement replacement or repair should be knowledgeable about the identification and hazards associated with asbestos and the Facility-specific asbestos, as included in an addendum to the 2002 VCP;
- All areas ranked as Low deterioration should be addressed using institutional controls and a City O&M Plan which would allow the City to inspect these areas for deterioration on a regular basis; and,
- The institutional control measures and O&M Plan should be incorporated into an addendum to the 2002 VCP.

These areas should be addressed as a preventative O&M measure and included in a preventative O&M program using a modified O&M approach as noted in EPA's "Purple Book," EPA Document No. 560/5-85-024 to prevent the release of asbestos fibers. Additionally, until all asbestos containing soils within South Wallace Avenue and the right-of-way have been replaced, a yearly pavement inspection of the entire South Wallace Avenue area included in this SI, should be included in the O&M program until replacement of all the included area occurs.

Due to the possibility that asbestos materials may be encountered in utility corridors during the excavation/utility repair work along South Wallace Avenue, Tetra Tech recommends addressing future work efforts in an addendum to the 2002 VCP to protect the health and safety of utility workers and the community.

### 5.2 SOIL

Based on Tetra Tech's analysis of the data collected during this investigation, it is Tetra Tech's opinion that the public has direct access to asbestos laden soils east of the SHB, south of the SHB along the Story Distributing Property, and in the alley behind Heeb's. Therefore, these areas should be remediated and/or addressed in accordance with an addendum to the 2002 VCP.

To prevent exposure to soils that contain visible asbestos along the eastside of the SHB, Story Distributing property, and Heeb's alley, Tetra Tech recommends that these asbestos



contaminated soils be excavated, transported, and disposed of by a contractor that has completed similar asbestos excavation remediation work, that employs DEQ-licensed Asbestos Contractor/Supervisors, and that employs 40-hr HAZWOPER OSHA trained individuals in accordance with all federal, state, and local regulations. Additionally, Tetra Tech recommends that all asbestos soils be removed in these areas to an over-excavation of approximately 0.5-feet to ensure that the soil contaminated with asbestos is removed. Confirmation samples should be collected to evaluate whether all of the asbestos materials have been removed. We estimate the following approximate soil volumes will require excavation and disposal; 104 yd<sup>3</sup> at the SHB, 101yd<sup>3</sup> at the Heeb's property, and 295 yd<sup>3</sup> at the Story Distributing Property; for a total of 500 cubic yards.

Tetra Tech recommends that specific areas where soils containing asbestos are known or likely to be present be addressed through an addendum to the 2002 VCP. An addendum to the 2002 VCP should evaluate the following:

- Excavation and/or encapsulation in the South Wallace Avenue utility corridor;
- Removal of asbestos contamination beneath South Wallace Avenue;
- Removal of asbestos contamination in areas adjacent to the SHB addition;
- Removal of accessible asbestos contamination on Story Distributing, Inc. property, EBM property, and, the alley south of Heeb's; and,
- Any required confirmation sampling.

The addendum should also address any remaining areas of contamination at the Facility through the analysis and selection of appropriate remedial alternatives. Those alternatives considered for selection should include no action, removal, and institutional controls (deed restrictions, City ordinance, etc.) for soils containing, or potentially containing asbestos, in the following inaccessible areas:

- Beneath buildings on the Harrington and Empire Building Materials property;
- South Wallace Avenue (between Main Street and Curtiss Street) and associated South Wallace Avenue right-of-ways and perpendicular street aprons (Babcock, Olive and Curtiss);
- Paved parking areas at Heeb's Grocery and the Harrington buildings;
- Loading docks, ramps and/or other structures on Empire Building Materials and Harrington properties; and,
- Sidewalks and other paved surfaces.

### 5.3 AIR AND DUST

Analysis of the dust and air samples did not indicate the presence of discernable quantities of asbestos surficial or airborne particulate inside the NHB or SHB; therefore these areas – in accordance with sampling methodologies as defined herein – should be considered free from quantifiable asbestos.



## 6.0 REFERENCES

Resource Technologies, Inc. (RTI) 2002a. Voluntary Cleanup Plan for the CMC East Main Depot Bozeman, Montana, Revision 2. Prepared for the City of Bozeman. October 2002.

\_\_\_\_\_ 2002b. Heath and Safety Plan for the CMC East Main Depot Site Voluntary Cleanup Bozeman, Montana. Prepared for the City of Bozeman. September 4, 2002.

\_\_\_\_\_ 2003. Addendum to the Voluntary Cleanup Plan for the CMC East Main Depot Facility, Bozeman, Montana. Prepared for the City of Bozeman.

\_\_\_\_\_ 2004. Voluntary Cleanup and Redevelopment Act Voluntary Cleanup Completion Report, Revision 1, CMC East Main Depot Site the Primary Portion of the CMC Asbestos Bozeman Facility Bozeman, Montana. Prepared for the City of Bozeman. August 2004.

Tetra Tech, Inc. 2007a. Final Revision – CMC Bozeman Facility Supplemental Investigation. Prepared for the City of Bozeman. November, 2007.

\_\_\_\_\_ 2007b. Limited Soil Investigation Results Report for the Nash-Finch/Bozeman Public Library. Prepared for the City of Bozeman. July 5, 2007.

\_\_\_\_\_ 2008. CMC Bozeman Facility: Revised Pavement Assessment. Prepared for the City of Bozeman. June 16, 2008.



## **APPENDIX A**

### **Figures**



G:\phase1\bozeman\arcmap\app\_a\_loc.mxd



2005 Montana NAIP Aerial Photograph




7720035.200

- Approximate Previously Assessed Area
- Approximate Area Included in SI

CMC Bozeman Facility  
Bozeman, Montana  
Figure 1



G:\phase1\bozeman\cadpro\site.dwg    SAVED: 6/19/08    PRINTED: 12/30/08    BY: MARY.BELL



7720035.200

- Interior Area included in SI
- Exterior Area included in SI
- x — Fence
- Previously Assessed Area
- Pavement Assessment Area

CMC Bozeman Facility  
Bozeman, Montana  
FIGURE 2






Pavement Cracking

- L** - Low  
**M** - Medium  
**H** - High






Asphalt Pavement Condition  
Areas of Suspected Asbestos Ore  
CMC Bozeman Facility  
Bozeman, Montana  
FIGURE 3



G:\phases1\bozeman\cadpro\asphalt\_pavement\_rev2.dwg    SAVED:12/31/08    PRINTED:12/31/08    BY:MARY BELL



7720035.200

Asphalt Distress Type:		Severity Level:	 Pavement Cracking
 Previously Assessed Area	1 - Alligator Cracking	M - Medium	
 Proposed Pavement Assessment Area	3 - Block Cracking	H - High	
 Asphalt to be Remove/Replaced	8 - Patching		
 Asphalt to be Repaired	14 - Swell		
	5 - Depression		
	6 - Longitudinal & Transverse Cracking		
	10 - Ravelling & Weathering		



Asphalt Pavement Removal and  
Repair Recommendations  
CMC Bozeman Facility  
Bozeman, Montana  
FIGURE 4







G:\phase1\bozeman\cadpro\3d test pits.dwg  
 PRINTED: 12/31/08  
 BY: MARY.BELL



NOT TO SCALE

July 2007

SI - SHB Assessment Area





7720035.200

SHB - Test Pit Diagram  
 CMC Bozeman Facility  
 Bozeman, Montana  
 FIGURE 6



G:\phase1\bozeman\cadpro\3d test pits.dwg    SAVED:12/30/08    PRINTED:12/31/08    BY:MARY.BELL



NOT TO SCALE

July 2007



SI - Heeb's Assessment Area



7720035.200

Heeb's - Test Pit Diagram  
CMC Bozeman Facility  
Bozeman, Montana  
FIGURE 7





NOT TO SCALE

July 2007

SI - Story Assessment Area




7720035.200

Story - Test Pit Diagram  
CMC Bozeman Facility  
Bozeman, Montana  
FIGURE 8



C:\phases1\bozeman\cadpro\JULY\VOP Figures\_rev8.dwg    SAVED:12/10/08    PRINTED:12/30/08    BY:MARY.BELL



- Facility
- Previously Assessed Area (RTI 2002)
- Right of Way Boundary
- Sewer Main - PVC/Clay Pipe
- Water Main - Cast Iron/Ductile Pipe

- Observed Asbestos Ore Area
- Potential Asbestos Ore Area
- Potential No Asbestos Ore Area
- Previously Remediation Area (RTI 2003)




7720035.300

Observed & Potential Asbestos Ore  
CMC Bozeman Facility  
Bozeman, Montana  
FIGURE 9




G:\phase1\bozeman\cadpro\harringtons.dwg    SAVED: 12/30/08    PRINTED: 12/30/08    BY: MARY.BELL



SCALE IN FEET  
0 15

October 2007

**Legend**



NHB North Harrington Building  
SHB South Harrington Building  
  
P Porous  
NP Non-Porous  
SP Semi-Porous




7720035.200

NHB - Attic Level  
CMC Facility - SI  
Bozeman, Montana  
**FIGURE 10**



G:\phase1\bozeman\cadpro\harringtons.dwg    SAVED: 12/30/08    PRINTED: 12/30/08    BY: MARY.BELL



#### Legend

NHB - 10 - 1 - P  
 Building    Sample    Aliquot    Sample    Surface    Type

NHB North Harrington Building  
 SHB South Harrington Building  
 P Porous  
 NP Non-Porous  
 SP Semi-Porous



NHB - Main Level  
 CMC Facility - SI  
 Bozeman, Montana  
 FIGURE 11



7720035.200



G:\phase1\bozeman\cadpro\harringtons.dwg    SAVED: 12/30/08    PRINTED: 12/30/08    BY: MARY.BELL



**Legend**

NHB - 10 - 1 - P  
Building    Sample    Aliquot Sample    Surface Type

NHB North Harrington Building  
SHB South Harrington Building  
  
P Porous  
NP Non-Porous  
SP Semi-Porous

NHB - Third Level  
CMC Facility - SI  
Bozeman, Montana  
**FIGURE 12**



7720035.200



The diagram is a floor plan of a building with several rooms and labeled points of interest. The rooms are: Vault, Shop, Office, Cleaning Area, and HVAC Room. The plan is marked with numerous points labeled with codes like NHB-9-10-NP, NHB-9-8-NP, NHB-9-6-SP, NHB-9-2-P, NHB-7-10-SP, NHB-9-7-SP, NHB-9-5-SP, NHB-9-3-P, NHB-9-9-NP, NHB-7-1-SP, NHB-9-4-SP, NHB-8-3-SP, NHB-8-4-SP, NHB-8-5-NP, NHB-8-10-SP, NHB-7-4-SP, NHB-7-2-P, NHB-7-5-P, NHB-7-6-SP, NHB-8-1-SP, NHB-8-6-NP, NHB-8-8-NP, NHB-7-9-SP, NHB-8-2-SP, NHB-8-7-NP, NHB-7-9-NP, NHB-7-8-NP, NHB-7-7-P, and NHB-9-1-P. The plan also shows an Elevator and a set of stairs.



A horizontal number line with tick marks at every integer from 0 to 15. The numbers 0 and 15 are labeled at the ends of the line.

Diagram illustrating the hierarchical structure of the NHB-1-P dataset. The hierarchy is shown as a sequence of nodes: NHB, 10, 1, and P. Brackets connect these nodes to labels: 'Building' for NHB, 'Sample' for 10, 'Aliquot Sample' for 1, and 'Surface Type' for P.


NHB - Lower Level  
CMC Facility - SI  
Bozeman, Montana  
FIGURE 13



7720035.200



G:\phase1\bozeman\cadpro\harringtons.dwg SAVED: 12/30/08 PRINTED: 12/30/08 BY: MARY.BELL



#### Legend

NHB	North Harrington Building
SHB	South Harrington Building
P	Porous
NP	Non-Porous
SP	Semi-Porous

SHB - Salvation Army  
CMC Facility - SI  
Bozeman, Montana  
FIGURE 14



7720035.200



## **APPENDIX B**

### **Site Specific CMC Bozeman Facility SI Work Plan - HASP**





Safety Excellence

## HEALTH AND SAFETY PLAN (HASP)

CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street

Prepared By: Scott Vosen  
Great Falls, Montana

Date: December 14, 2007

Tetra Tech Project No.: 1157720035.200

### Project Identification:

Service Type: Industrial Hygiene

Site Name: CMC Bozeman Facility

Client Name: Montana Department of Transportation

Site Location: Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street

Client Contact: Mr. Tim Cooper

Client Phone No: (406) 582-2303

### Site History:

Previous assessments have been completed for properties to the east of Wallace Avenue between East Main Street and Curtiss Street. Areas of known asbestos ore contamination in soil have been identified, and excavated in some areas, at the site.

### Scope of Work:

The current phase of work at the site will include assessment of pavement conditions and investigation of potential asbestos ore contamination is soil.

### Site Regulatory Status:

CERCLA/SARA	RCRA	OSHA	OTHER FEDERAL
US EPA: No	US EPA: No	1910: Yes	DOE: No
State: Yes	state: No	1926: Yes	USATHAMA: No
NPL site: No	NRC	state: Yes	Air Force: No
	10CFR20: No		

### Review and Approval Documentation

#### Reviewed By:

A. Project Manager: Keith Cron

Date: 12-17-07

B. Site H & S Coordinator: Nathan Shumate

Date: 12-17-07

#### Approved By:

Date: 12-17-07

Approval signature also certifies that the PPE selected for this project was based on a hazard assessment and selected according to the requirements established by OSHA in 29 CFR 1910.132 (d).

### Project Dates

### Amendment Dates:

Project Start Date: December 17, 2007

Project End Date: unknown

This site HASP must be reissued/reapproved for

activities conducted after: December 31, 2008

1

2

3

4



**City of Bozeman - CMC Bozeman Facility  
HEALTH AND SAFETY PLAN (HASP)**

**TABLE OF CONTENTS**

<b>SECTION DESCRIPTION</b>	<b>PAGE NUMBER</b>
Project Identification	1
Site Regulatory Status	1
Review and Approval Documentation	1
Project Dates	1
Tetra Tech Representatives/Responsibilities	1
Tetra Tech Subcontractors	2
Client / Tetra Tech / Subcontractor H&S Program & Policy Bridging Section	2
Site Specific Health and Safety Personnel	3
Tasks Covered Under the Plan	3
Types and Sources of Hazards	4
Chemicals of Concern	4
Hazard Evaluation of Chemicals of Concern	5
Chemicals of Concern/Precautions	6
Physical/Construction Hazards of Concern	7
Task Based Risk Analysis and Protection Plan	8
Personal Protective Equipment Level Definitions	9
Cartridge Changeout Schedule	13
Decontamination Plan	13
Contingency Plan	14
Response Plans - Medical, Fire, Spill, Security, Weather and Disaster	15
Site Control Measures	19
Site Personnel and Certification Status	20
Training and Briefing Topics	22
Intrusive Activities Checklist	23
Procedures for Ensuring Unknown Subsurface Structures Identified	24
Required PPE and Equipment Checklist	25
Field Audits	26
Tetra Tech Approval/Signoff Form	27
Subcontractor Approval/Signoff Form	28
	29

Note: The sections highlighted in yellow are required for all health and safety plans with the other sections optional depending on the project, tasks and associated hazards. If this template is used for sites without chemical hazards, the following sections may be eliminated as well; H&S Evaluation Chemicals of Concern, Hazard Evaluation of Chemicals of Concern and Precautions for Chemicals of Concern; and Decontamination Plan.

**Forms Attached**

Worker / Visitor Sign-In Form  
Daily Tailgate Meeting Form  
Field Audit Form

√  
√  
√



## HEALTH AND SAFETY PLAN (HASP)

CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street

### Tetra Tech Representatives

Branch Address and Phone	Name/Title	Role and Responsibilities
Tetra Tech (406) 443-5210 303 Irene Street Helena, Montana 59601	Jess Whitford	Pavement Assessment
Tetra Tech (406) 453-1641 1601 2nd Avenue North, Suite 116 Great Falls, Montana	Keith Cron Nathan Shumate	Project Management & Oversight Site Characterization

### Tetra Tech Subcontractors

Organization/Address and Phone	Name/Title	Role and Responsibilities
Abatement Contractors of Montana 406-549-8489 861 Dakota Ave. Missoula, MT 59802	Mike Foust	Test pit excavation

**Scope of Work** Excavate test pits at the direction of Tetra Tech.

Organization/Address and Phone	Name/Title	Role and Responsibilities
<b>Scope of Work</b>		

Organization/Address and Phone	Name/Title	Role and Responsibilities
<b>Scope of Work</b>		





Safety Excellence

## HEALTH AND SAFETY PLAN (HASP)

CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street

### Client / Tetra Tech / Subcontractor H&S Program & Policy Bridging Section

Identify which specific H&S programs will be followed for the designated scope of work.

H&S Program	Specify Program To Be Used	Comments
Emergency Evacuation Procedures	<input type="checkbox"/> Client <input checked="" type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other	Evacuation routes will be established by Tetra Tech's site health and safety coordinator during daily safety meetings.
Drilling and subsurface structure locates	<i>Heaps 7443900</i> <input type="checkbox"/> Client <input checked="" type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other <i>Hamingtons 7443904</i>	Tetra Tech will submit a request to the UULC for location and surface-marking of underground utilities.
Permit Required Confined Space Entry	<input type="checkbox"/> Client <input type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other	Not applicable; no confined space entries will be performed during this project.
Lockout / Tagout	<input type="checkbox"/> Client <input type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other	Not applicable
Other	<input type="checkbox"/> Client <input type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other	
Other	<input type="checkbox"/> Client <input type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other	
Other	<input type="checkbox"/> Client <input type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other	
Other	<input type="checkbox"/> Client <input type="checkbox"/> Tetra Tech <input type="checkbox"/> Sub <input type="checkbox"/> Other	

Tetra Tech's policy is to provide a safe working environment for all employees and contractors so that work may be conducted in a safe and efficient manner.

Tetra Tech employees and subcontractor employees working at the specific project covered by this HASP shall adopt and adhere to this HASP and the above referenced programs/policies by following all requirements stated in the safe work practices applicable to their work. No work is so urgent or important that we cannot take the time to do it safely. **ALL** personnel on site including subcontractor's have the right and responsibility to stop the work if they feel a safety protocol is not being followed or if they feel an unsafe condition exists.

**Nathan Shumate** has been designated **Site Health and Safety Coordinator (SHSC)**

for activities to be conducted at this site. The SHSC has total responsibility for ensuring that the provisions of this HASP are adequate and implemented in the field. Changing field conditions may require decisions to be made concerning adequate protection programs. Therefore, the personnel assigned as SHSCs are experienced and meet the additional training requirements specified by OSHA in 29 CFR 1910.120.

**Keith Cron** has (have) been designated as the **alternate SHSC(s)**.



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Activities Covered Under This Plan

<b>Task</b>	<b>1</b>	<b>Schedule:</b> December 17, 2007 - ??
<b>Pavement Assessment</b>	Tetra Tech will visually assess the condition of paving throughout the project corridor.	
<b>Task</b>	<b>2</b>	<b>Schedule:</b> December 17, 2007 - ?? <i>12/19/07 -</i>
<b>Exterior Asbestos-in-Soil Assessment</b>	Tetra Tech will visually assess soil for the presence of asbestos ore. Assessment locations will coincide with test pit locations. Test pits will be excavated with a backhoe and visually assessed to determine vertical extent of asbestos contamination. Soil samples will be collected at six-inch intervals to depth in each test pit location. Test pits will be excavated south of Heeb's Market and south and east of the Harrington building. Based on previous data collected at and proximate to the site, Tetra Tech anticipates the excavations will not exceed 4 feet in depth.	
<b>Task</b>	<b>3</b>	<b>Schedule:</b> December 17, 2007 - ??
<b>Indoor Asbestos-in-Air Assessment</b>	The interior of the Harrington building will be assessed for the presence of asbestos. This task will include horizontal surface dust sampling with a microvac apparatus and personal air monitoring of Harrington and/or Tetra Tech employees during typical daily activities for Harrington employees.	
<b>Task</b>	<b>4</b>	<b>Schedule:</b>

### Types and Sources of Hazards

Physiochemical	Radiation	Chemically Toxic
<b>Flammable:</b> No	<b>Ionizing:</b> No	<b>Inhalation:</b> No
<b>Explosive:</b> No	<b>Non-Ionizing:</b> No	<b>Ingestion:</b> No
<b>Corrosive:</b> No	<b>Other</b>	<b>Absorption:</b> No
<b>Reactive:</b> No	<b>Physical Hazards:</b> Yes	<b>Carcinogen:</b> No
<b>O2 Rich:</b> No	<b>Construction Activities:</b> Yes	<b>Mutagen:</b> No
<b>O2 Deficient:</b> No		<b>Teratogen:</b> No
<b>Biological</b>		<b>OSHA listed:</b> No
<b>Etiological Agent:</b> No	<b>Specific OSHA Standards:</b> 29 CFR 1910.120, 29 CFR 1910.132, 29 CFR 1910.134	
<b>Other:</b> No	29 CFR 1926.1101	
(plant, insect, animal)		

Direct Sources of Hazards	Indirect Sources (Describe)
<b>Air:</b> Yes <b>Other:</b> Dust  <b>Groundwater:</b> No  <b>Soil:</b> Yes  <b>Surface Water:</b> No	NA



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

Health and Safety Evaluation - Chemicals of Concern				
Chemical Name	Entry Route	Carc*	Symptoms	Target Organs



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Health and Safety Evaluation - Hazard Evaluation of Chemicals of Concern

Chemical Name	LEL/UEL (%)	Flam	OT (ppm)	IDLH	Exposure Limits



**HEALTH AND SAFETY PLAN (HASP)****CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street****Health and Safety Evaluation - Chemicals of Concern / Precautions****PRECAUTIONS**

**INGESTION:** All listed chemicals have the potential for accidental ingestion, however in work place settings it is not considered a primary route of entry. All accidental ingestions should be addressed by referring to the MSDS and seeking immediate medical attention.

**INHALATION:** Listed chemicals capable of inhalation routes of entry should be maintained below the established exposure limits. If there is indication that the exposure limits are being exceeded, appropriate respiratory protection should be used. If appropriate PPE has not been planned for, work should cease and the SHSC should be contacted.

**ABSORBANCE/CONTACT:** Listed chemicals presenting an absorbance or contact hazards should be handled only with the use of appropriate PPE.

**NOTE:** Overexposure to any chemical via any route of entry should be addressed by referring to the MSDS and seeking immediate medical attention. Avoid contact with all chemical hazards when possible and consult MSDS before any exposure may occur.

**OTHER PRECAUTIONS**

There are no chemicals of concern associated with the tasks listed above.

**ABBREVIATIONS**

LEL= Lower Explosive Limit

UEL = Upper Explosive Limit

ppm = parts per million

mg/m<sup>3</sup> = milligram per cubic meter

TWA = Time Weighted Average

STEL = Short Term Exposure Limit

Flam = Flammable

IDLH = Immediately Dangerous to Life and Health

OT = Odor Threshold

NOTE: Odor Thresholds were obtained from the American Industrial Hygiene Association's (AIHA) publication on Odor Thresholds. The listed thresholds are best estimates based on existing experimental data. (d) indicates the threshold for detection and (r) indicates the threshold for recognition.

NOTE: \* In 1989, OSHA published new exposure limits (in most cases lower) for some chemical compounds. However, in 1993, under a court decision, these newly established limits were vacated and reverted back to the previous limit or to none if a limit was not previously established for the chemical compound. The limits listed in the table are the older, enforceable OSHA limits. It is recommended that the most conservative exposure limit listed be used in assessing exposures and determining controls and safety measures.



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Health and Safety Evaluation - Physical / Construction Hazards of Concern

For the hazards that apply to this site, indicate the task(s) to which each particular hazard applies. For the hazards that do not apply to this site, delete the "1" in the Task No(s) column.

HAZARD	Task No(s)	Protection Procedure
Noise	All	Hearing protection should be worn if potential of >85 dB
Cold	All	Warm clothing; if symptoms develop - go to warm area
Rain	All	Wear rain gear; watch footing on wet surfaces
Snow	All	Warm clothing - watch footing on slippery surfaces
Electrical Storms	1,2	Discontinue operations
Confined Space Entry	2,3	Follow confined space permitting and entry procedures
Heavy Lifting / Moving	2,3	Utilize proper lifting techniques
Rough Terrain	1,2	Watch footing
Housekeeping	2,3	Maintain order
Neighborhood	All	Awareness of area; comply with contingency / ER plans
Traffic	1,2	Obey all traffic regulations; maintain awareness
Heavy Equipment Operation	2	Only qualified operators; inspections and back-up alarms
Lifting Equipment Operation	2	Only licensed operators; equipment inspections required
Excavating / Trenching	2	See Tt H&S Manual; Comply with OSHA regulations
Utilities - Underground	2	Have located before any work commences
Utilities - Overhead	2	Keep objects more than 20 feet from power lines
Electrical - General	2	See Tt H&S Manual; Comply with OSHA regulations
Hand Tools	All	Use appropriate tools for the task
High Pressure Water	2	Follow operating instructions
Other:		
Other:		
Other:		



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Task Based Risk Analysis and Protection Plan

The preceding tables have identified the known and suspected hazards to be present in performing the tasks required to complete this project. Below is a breakdown by task of the hazards, likelihood of exposures, and protective protocols to be used to minimize risk.

<b>Associated Hazards:</b>	<b>CHEMICAL</b>	There are no anticipated chemical exposures associated with this task.
	<b>PHYSICAL</b>	Traffic, uneven terrain, slips/trips/falls, weather.
	<b>BIOLOGICAL</b>	There are no anticipated biological hazards associated with this task.
	<b>OTHER</b>	Asbestos fiber inhalation
<b>Exposure Potential:</b>	<b>CHEMICAL</b>	NA
	<b>PHYSICAL</b>	Likely
	<b>BIOLOGICAL</b>	NA
	<b>OTHER</b>	Not Likely
<b>PPE:</b>	Level D	PPE for this task should include long pant, leather boots, and appropriate clothing for weather conditions (e.g. gloves, coat, hat, rain gear, etc.).
<b>Air Monitoring Plan</b>	There are no air monitoring requirements associated with this task.	
<b>Air Monitoring Equipment</b>	NA	
<b>Precautions:</b>	<b>CHEMICAL</b>	NA
	<b>PHYSICAL</b>	Be mindful of traffic, use caution to avoid slip/trip/fall hazards (e.g. puddles, curbs, pot holes, ice, etc.), wear appropriate clothing for weather conditions.
	<b>BIOLOGICAL</b>	NA
	<b>OTHER</b>	Potential asbestos exposure is related to the nature of the project (i.e. potential asbestos ore contamination of soil). Avoid obvious asbestos ore contamination. If dry, windy conditions exist, avoid dust as appropriate (e.g. leave site, move upwind, etc.) until conditions become favorable.



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Task Based Risk Analysis and Protection Plan

The preceding tables have identified the known and suspected hazards to be present in performing the tasks required to complete this project. Below is a breakdown by task of the hazards, likelihood of exposures, and protective protocols to be used to minimize risk.

TEST PITS		
<b>Associated Hazards:</b>	<b>CHEMICAL</b>	There are no anticipated chemical exposures associated with this task.
	<b>PHYSICAL</b>	Heavy equipment (backhoe), excavation hazards (utilities, sidewall collapse, etc.), traffic, strains, slips/trips/falls, weather.
	<b>BIOLOGICAL</b>	There are no anticipated biological hazards associated with this task.
	<b>OTHER</b>	Asbestos fiber inhalation
<b>Exposure Potential:</b>	<b>CHEMICAL</b>	NA
	<b>PHYSICAL</b>	Likely
	<b>BIOLOGICAL</b>	NA
	<b>OTHER</b>	Somewhat likely
<b>PPE:</b>	Level C	PPE for this task should include steel-toe leather boots, long pants, hard hat, safety glasses, tyvek suits, air-purifying respirator (HEPA-filtered), and gloves (latex/nitrile and/or cloth/leather), as appropriate.
<b>Air Monitoring Plan</b>	Ambient, down-wind air monitoring will be conducted during test pit excavation activities. Sampling will be conducted in accordance with the NIOSH 7400 Method for PCM. One sample will be collected while working in each of the following three areas (three total samples): 1) east of the Harrington building; 2) south of the Harrington building; and, 3) south of Heeb's Market.	
<b>Air Monitoring Equipment</b>	Vacuum pump, stand, PCM cassettes, and calibration device (primary or secondary).	
<b>Precautions:</b>	<b>CHEMICAL</b>	NA
	<b>PHYSICAL</b>	Use caution while near heavy equipment, maintain eye contact with operators, do not enter excavations greater than 4 feet deep without proper shoring and/or sloping (1:1), ensure underground utilities have been surface-marked prior to excavation, be mindful of traffic and use traffic control (e.g. signage, cones/candles, barricades) as appropriate, use proper lifting techniques (e.g. legs, not back, no twisting), use caution to avoid slips/trips/falls, wear proper clothing for weather conditions.
	<b>BIOLOGICAL</b>	NA
	<b>OTHER</b>	If asbestos ore is observed, don air-purifying respirator (HEPA-filtered). Properly decontaminate reusable equipment and supplies. Discard disposable equipment and supplies.



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Task Based Risk Analysis and Protection Plan

The preceding tables have identified the known and suspected hazards to be present in performing the tasks required to complete this project. Below is a breakdown by task of the hazards, likelihood of exposures, and protective protocols to be used to minimize risk.

Personnel monitoring		
<b>Associated Hazards:</b>	<b>CHEMICAL</b>	There are no anticipated chemical exposures associated with this task.
	<b>PHYSICAL</b>	Strains, slips/trips/falls
	<b>BIOLOGICAL</b>	There are no anticipated biological hazards associated with this task.
	<b>OTHER</b>	Asbestos fiber inhalation
<b>Exposure Potential:</b>	<b>CHEMICAL</b>	NA
	<b>PHYSICAL</b>	Somewhat likely
	<b>BIOLOGICAL</b>	NA
	<b>OTHER</b>	Unlikely
<b>PPE:</b>	Level D	PPE for this task should include long pants, leather boots, gloves (latex/nitrile or cloth/leather).
<b>Air Monitoring Plan</b>	<div style="text-align: right; font-weight: bold;">JEFF HARRINGTON air</div> Personnel air monitoring will be performed on two individuals during this task (Harrington and/or Tetra Tech employees). Samples will consist of 8-hour TWA samples to be analyzed by the PCM method.	
<b>Air Monitoring Equipment</b>	Low-flow, personal sampling pumps, PCM cassetts, and calibration standard (primary or secondary).	
<b>Precautions:</b>	<b>CHEMICAL</b>	NA
	<b>PHYSICAL</b>	Use caution to avoid slips/trips/falls, use proper lifting techniques (legs not back, no twisting).
	<b>BIOLOGICAL</b>	NA
	<b>OTHER</b>	Avoid raising dust where possible. If conditions warrant, don half-face respirator (HEPA filtered) and/or cease work.



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Task Based Risk Analysis and Protection Plan

The preceding tables have identified the known and suspected hazards to be present in performing the tasks required to complete this project. Below is a breakdown by task of the hazards, likelihood of exposures, and protective protocols to be used to minimize risk.

<b>Associated Hazards:</b>	<b>CHEMICAL</b>	
	<b>PHYSICAL</b>	
	<b>BIOLOGICAL</b>	
	<b>OTHER</b>	
<b>Exposure Potential:</b>	<b>CHEMICAL</b>	
	<b>PHYSICAL</b>	
	<b>BIOLOGICAL</b>	
	<b>OTHER</b>	
<b>PPE:</b>	Level	
<b>Air Monitoring Plan</b>		
<b>Air Monitoring Equipment</b>		
<b>Precautions:</b>	<b>CHEMICAL</b>	
	<b>PHYSICAL</b>	
	<b>BIOLOGICAL</b>	
	<b>OTHER</b>	



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Personal Protective Equipment Level Definitions

#### Level D

Level D protection is assigned when minimal protection is warranted. Level D offers protection from nuisance contamination only and is made up of a typical work uniform for the work to be performed. Level D protection includes the following:

**Hard hat, safety glasses, hearing protection (as required), gloves, and steel toe boots.**

#### Level C

Level C protection is assigned when the type(s) and concentration(s) of contaminants is known and the criteria for using an air-purifying respirator are met. Level C is an upgrade from level D and in addition to the requirements of level D, the following requirements must be met:

**Level D plus Full-face or half-mask air purifying canister/cartridge equipped respirator, hooded chemical resistant clothing, and inner and outer chemical resistant gloves.**

#### Level B

Level B protection is assigned when the type(s) and concentration(s) of contaminants is unknown or is known and warrants the highest level of respiratory protection with a lesser level of skin protection. Level B is an upgrade from level C and in addition to level C requirements, the following requirements must be met:

**Level C plus pressure-demand full-face SCBA or pressure demand supplied air respirator with escape SCBA.**

#### Level A

Level A protection is assigned when the atmosphere is IDLH (Immediately Dangerous to Life and Health) and warrants the highest degree of respiratory protection and skin protection. Level A is an upgrade from level B and in addition to level B requirements, the following requirements must be met:

**Level B plus totally encapsulating chemical-protective suit.**

### CARTRIDGE CHANGEOUT SCHEDULE

#### Cartridge Changeout Schedule:

Cartridges will be changed per manufacturer recommendations or as loading occurs creating difficult breathing. Manufacturer recommends single use for disposable cartridges.

#### Method Used to Determine Schedule:

Difficulty breathing through respirator. Adjusted based on activity and site conditions.



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Decontamination Plan

#### Personal Decontamination

The section outlining task by task risk assessment and protection plan specifies the level of protection required for each task. Consistent with the level of protection required, step by step procedures for decontamination for each level of protection are given below.

Disposable PPE (e.g. tyvek suites, latex/nitrile gloves) will be removed following completion of each test pit excavation. Reusable equipment will be decontaminated with water following each test pit excavation. Employees will self-decontaminate.

#### Levels of Protection Required for Decontamination Personnel

**The level of protection required for a person assisting with decontamination is:**

LEVEL: D

**Modification: (upgrade or downgrade) will be made under the following conditions:**

No decontamination personnel will be utilized for this project.

#### Disposition of Contaminated Wastes

**The following outlines the protocol to be followed for contaminated wastes that are encountered:**

Anticipated contaminated wastes will be limited to asbestos ore impacted soils and dust. Impacted soil and asbestos ore will be returned to the test pit excavations from which they originated. Decontamination fluids will also be disposed in the test pit excavations.

#### Sampling Equipment Decontamination

**The following outlines the protocol to be followed for decontamination of sampling equipment:**

Sampling equipment will be decontaminated with water; water will be disposed in test pit excavations.

#### Non-Sampling Equipment Decontamination

**The following outlines the protocol to be followed for decontamination of non-sampling equipment:**

Equipment will be decontaminated with water; water will be disposed in the test pit excavations.



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

Contingencies			
Emergency Contacts and Phone Numbers			
Agency	Contact		Phone Number
Tt Emergency Contact for the Project	Keith Cron		(406) 788-5318 cell
<b>24 Ambulance Service</b>	911		911
<b>Fire Department</b>	Local		911
<b>Police Department</b>	Local		911
<b>Onsite Coordinator</b>	Keith Cron		406-788-5318
<b>Site Telephone</b>	Mobile		406-788-5318
<b>Nearest Telephone</b>			
In the event of an incident, the TT-MM reporting protocol requires that a corporate contact be notified as soon as possible.	Yvonne Freix	Office: 715-845-4100    Mobile: 800-976-2524    Home: 715-355-4193	
	Stacy Meacham	Office: 402-933-1345    Mobile: 402-651-6675    Home: 402-933-7763	
	Anita Carrico	Office: 214-953-3111 (285)    Mobile: 469-585-8931	
	Tory Fravel	Office: 970-223-9600    Mobile: 970-481-0883    Home: 970-266-9409	
Local Medical Emergency Facility(s)			
<b>Name of Hospital:</b>	Bozeman Deconess Hospital		<b>Distance:</b> 1.4 miles
<b>Address:</b>	915 Highland Blvd		<b>Time:</b> 5 minutes
<b>Type of Service:</b>	ER, 24 hr, trauma, burn center, chemical exposures etc.		
<b>Route:</b>	SEE ATTACHED DIAGRAM      Head north on South Wallace Avenue, toward East Olive Street (0.2 miles); Turn right at East Main Street (0.5 miles); Turn right at Highland Boulevard (0.6 miles); Turn right (338 ft).		
<p><small>In the case of a <b>SERIOUS OR LIFE-THREATENING EVENT</b> (any injury, accident or near-miss event):</small></p> <ol style="list-style-type: none"> <li><small>1. Seek emergency medical treatment immediately</small></li> <li><small>2. Once the injured person(s) is appropriately cared for, call a corporate contact listed on the emergency wallet card and update the employee's supervisor and project manager as soon as possible.</small></li> </ol>			





## Safety Excellence

Page 16

CMC - Bozeman Facility HASP





TETRA TECH

*Safety Excellence*

## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Secondary Provider (Occupational Health Clinic)

<b>Name of Occ Clinic:</b>	Gallatin Community Clinic	<b>Distance:</b>	0.5 miles
<b>Address:</b>	214 E. Mendenhall Street	<b>Time:</b>	3 minutes
<b>Type of Service:</b>	General		

**Route:** See Attached Map: Head north on South Wallace Avenue toward East Olive Street (0.3 miles); Turn left at East Mendenhall Street (0.3 miles).


In the case of a **NON-EMERGENCY/NON-LIFE THREATENING INCIDENT** (any injury, accident or near-miss event) call one of the corporate contacts listed on the wallet card (and above) prior to an Employee visiting a physician and implementing the following procedure:

1. Administer first aid immediately.
2. Tetra Tech employees call WorkCare (Tetra Tech contracted physicians) at 1-800-455-6155 for a triage call/discussion with an Occupational Health Nurse (OHN).
3. Mention that this is regarding an injury. At this point the nurse/physician will assist the employee/supervisor/H&S Coordinator to determine the best treatment plan. For example, he/she will recommend first aid or urgent care.
4. WorkCare will require the following information when a call is placed: Name of person calling, phone number, location, name of person injured, Social Security number, date and type of injury.



## HEALTH AND SAFETY PLAN (HASP)

CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street





## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

Response Plans	
Medical - General	
<b>First Aid Kit:</b>   <b>Eye Wash:</b>  <b>Safety Shower:</b>  <b>Special Procedures:</b>	<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p><b>Type:</b> Portable</p> <p><b>Location:</b> Vehicle</p> <p><b>Required?:</b> Yes</p> <p><b>Location:</b> Vehicle</p> <p><b>Required?:</b> No</p> <p><b>Location:</b> NA</p> </div> <div style="width: 45%;"> <p><b>Special First Aid Precautions:</b></p> <p><b>Hydrofluoride on Site:</b> No</p> <p><b>Cyanides on Site:</b> No</p> <p><b>Other:</b></p> <p>NA</p> </div> </div> <p>Consult MSDS for appropriate first aid measures related to chemical exposures. Seek immediate medical attention when incidents warrant anything beyond minor first aid response.</p> <p>The buddy system will be required and a trained CPR/First Aid person will be on-site.</p>
Fire/Explosion	
<b>Special Procedures:</b>   <b>Fire Extinguisher:</b>	<p>Fire extinguishers will be used to extinguish small fires. For any fire beyond the control of a portable fire extinguisher contact the local firefighting authorities as listed in the emergency contact section of this plan.</p> <p><b>Type:</b> ABC</p> <p><b>Location:</b> Vehicles</p>
Spill Response	
<b>Special Procedures:</b>   <b>Special Gear:</b>	<p>In the event of a spill from a vehicle or site discovery, a dirt barrier will be established with sorbant pads. All contaminated solid will be placed into properly labeled containment vessels.</p> <p><b>Type:</b></p> <p><b>Location:</b></p>
Weather/Natural Disaster Emergency	
<b>Special Procedures:</b>	<p>Cease work immediately and head for the agreed meet location (established in daily safety meetings). If travel is not possible seek immediate shelter as available.</p>



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**


Site Control Measures		
Work Zones		
<b>Exclusion Zone:</b>	NA	
<b>Decon Zone:</b>	NA	
<b>Support Zone:</b>	NA	
<b>Other Zones:</b>	NA	
Methods for Delineating Zones		
<b>Work Zone Delineation Plan</b>	NA	
<b>Delineation Equipment</b>	NA	
Security Measures		
No specific security measures will be employed. At the end of each day, the containation zone will be depicted		
Security Related Contacts		
Agency	Contact Name	Phone Number



# HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

**Site Map**



7720035.100

- - - Interior Area to be Included In SI
- - - Exterior Area to be Included In SI
- x - Fence
- - - Previously Assessed Area
- - - Proposed Pavement Assessment Area

**Appendix A**  
**CMC Bozeman Facility**  
**Bozeman, Montana**  
**FIGURE 2**



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

Site Personnel and Certification Status		
<b>Name:</b>	Keith Cron	<b>Medical Current:</b> Yes
<b>Title:</b>	On-site project coordinator	<b>HAZWOPER Current:</b> Yes
<b>Task(s):</b>	all	<b>Fit Test Current:</b> Yes
<b>CPR/First Aid:</b>	Adult CPR 2004	
<b>Other:</b>	40-HAZWOPR, Asbestos Building Inspector, Asbestos Contractor/Supervisor	
<b>Name:</b>	Nathan Shumate	<b>Medical Current:</b> Yes
<b>Title:</b>	SHSC	<b>HAZWOPER Current:</b> Yes
<b>Task(s):</b>	2,3	<b>Fit Test Current:</b> Yes
<b>CPR/First Aid:</b>	NA	
<b>Other:</b>	40-HAZWOPR, Asbestos Building Inspector, Asbestos Contractor/Supervisor	
<b>Name:</b>	Jesse Whitford	<b>Medical Current:</b> Yes
<b>Title:</b>	Technician	<b>HAZWOPER Current:</b> Yes
<b>Task(s):</b>	1	<b>Fit Test Current:</b> NA
<b>CPR/First Aid:</b>	NA	
<b>Other:</b>	40-HAZWOPR	
<b>Name:</b>	Mike Foust	<b>Medical Current:</b> Yes
<b>Title:</b>	Excavation Contractor	<b>HAZWOPER Current:</b> Yes
<b>Task(s):</b>	4	<b>Fit Test Current:</b> Yes
<b>CPR/First Aid:</b>		
<b>Other:</b>	40-HAZWOPR, Asbestos Building Inspector, Asbestos Contractor/Supervisor	
<b>Name:</b>		<b>Medical Current:</b>
<b>Title:</b>		<b>HAZWOPER Current:</b>
<b>Task(s):</b>		<b>Fit Test Current:</b>
<b>CPR/First Aid:</b>		
<b>Other:</b>		
<b>Medical Current:</b>	All personnel, including visitors entering the Task 2 work areas must be certified as medically fit to work and to wear a respirator if appropriate.	
<b>Training Current:</b>	All personnel, including visitors entering the Task 2 work areas must have certifications of completion of training in accordance with OSHA 29 CFR 1910.120.	
<b>Fit Test Current:</b>	All on-site personnel for Tasks 2 and 3, including visitors entering any area requiring the use or potential use of any negative pressure respirator must have at a minimum, a qualitative fit test administered in accordance with OSHA 29 CFR 1910.134 or ANSI within the last 12 months. If site conditions require the use of a full face negative pressure air purifying respirator for protection against asbestos or lead, employees must have a qualitative fit test in accordance with OSHA 20 CFR 1910.1002 or 1025 within the last 6 months. * Bearded workers, who can not be fit-tested for a tight face fitting respirator, are required to wear a powered air purifying respirator (PAPR).	
<b>Note:</b>	These requirements should be verified for any subcontractor personnel assigned to the site.	



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Training and Briefing Topics

**Note:** The following topics will be covered as indicated (i.e., the initial site training, daily, monthly or periodically). Delete the X's corresponding to the topics that do not apply to this site. Indicate the frequency for the topics that do apply.

Site characterization and analysis (29 CFR 1910.120 i)	X	daily
Physical Hazards	X	daily
Site Control (29 CFR 1910.120 d)	X	daily
Engineering Controls and Work Practices (29 CFR 1910.120 g)	X	daily
Heavy Machinery	X	daily
Backhoe	X	daily
Equipment	X	daily
Tools	X	daily
Ladders (29 CFR 1910.27 d)	X	initial
Overhead and Underground Utilities	X	daily
PPE (29 CFR 1910.120 g; and 1910.134)	X	daily
Respiratory Protection (29 CFR 1910.120 g; and 1910.134)	X	initial
Level C - Personal Protective Equipment	X	initial
Level D - Personal Protective Equipment	X	initial
Air Monitoring (29 CFR 1910.120 h)	X	initial
Decontamination (29 CFR 1910.120 k)	X	initial
Emergency Response (29 CFR 1910.120 l)	X	daily
Sanitation (29 CFR 1910.120 n)	X	daily
Other:		



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Intrusive Activities Checklist

Will intrusive activities be performed for work under this HASP? Yes

If yes, describe the type(s) of intrusive activity. Test pit excavation (backhoe)

#### Subsurface Structures Present

Type	Present?	Located ?	Method Used/To Be Used for Locating
Electrical	Yes	Overhead (potential underground)	811 utilities locate
Gas	Yes	Prior to project	811 utilities locate
Water/Sewer	Yes	Prior to project	811 utilities locate
Product Line	No		
Product Tank			
Other			

#### Shut-Offs Located

Type	Location of Shut-Off
Electrical	Unknown
Gas	Unknown
Water/Sewer	Unknown
Product	NA
Other	

#### Emergency Contacts for Subsurface Structure Repair

Type	Appropriate Contact for Emergency Repair of Specific Subsurface Structure Type/Material
Electrical	Northwestern Energy - (888) 467-2353
Gas	Northwestern Energy - (888) 467-2353
Water/Sewer	City of Bozemen - (406) 582-2300
Product	NA
Other	



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### Procedure for Ensuring Unknown Substructures Identified

Although potential known and unknown subsurface structures are identified per the above sections, there is always the potential for unknown subsurface structures to be encountered during intrusive activities. Therefore, a protocol needs to be established for each particular site. For this site, the following procedures will be followed for the intrusive activities identified above: (Delete the X's in front of the procedure(s) that do not apply to this site.)

X "One Call" or equivalent utility locate per the local system for the site will be made (this is mandatory on all sites)

X Follow up with one-calls (on-site meeting requested during initial locate request)

**Other Specific Subsurface Identification Requirements for this Site**



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

Required PPE and Equipment Checklist		
Delete the X's corresponding to the PPE/Equipment that does not apply to this site.		
HEALTH AND SAFETY BINDER / HASP, SITE CHECK IN/OUT PROCEDURES, ETC.		X
SAFETY GLASSES WITH SIDE SHIELDS		X
HARD HAT		X
STEEL-TOED BOOTS		X
GLOVES	TYPE: latex/nitrile/cloth/leather	X
RESPIRATOR	TYPE: Air-purifying (HEPA-filtered)	X
RESPIRATOR CARTRIDGES	TYPE: HEPA	X
HEARING PROTECTION	TYPE:	X
FIRE EXTINGUISHER		X
EYE WASH BOTTLE		X
FIRST AID KIT		X
DRINKING WATER	AMOUNT:	X
WASH WATER		X
UV PROTECTION		X



## HEALTH AND SAFETY PLAN (HASP)

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street**

### FIELD AUDITS

A field auditing program should be determined for the project based on the scope of work, duration of the project and degree of hazards associated with the tasks involved.

During the course of this project a minimum number of field audits will be conducted as follows: 1

The following person is responsible for ensuring the audits and associated corrective actions are completed: Keith Cron

Will known or suspect hazardous materials / dangerous goods be packaged and shipped? No

If shipping materials classified or suspected as hazardous materials or dangerous goods attach and follow Company Field Guidelines entitled "HAZARDOUS MATERIALS / DANGEROUS GOOD PACKAGING AND SHIPPING GUIDELINES".

Are there any identified or potential confined spaces associated with the project? Y

Will the project involve any confined space entry? No

Potential confined spaces include excavations greater than 4 feet deep. Tetra Tech does not anticipate the excavations will be more than 4 feet deep. No site personnel will enter excavations greater than 4 feet deep.

Will Tetra Tech employees or subcontractor employees be required to or have the potential to work alone? No

For which task(s) will a site worker be or have the potential to be working alone?

List the type of employees that will be permitted to work alone and under what conditions:

**Note:** Personnel should not be allowed to work alone if there is high hazard potential associated with the site and/or task they will be performing, including but not limited to high physical hazard potential (such as heavy equipment operation, high voltage, intrusive activities, etc.), potential for extreme acute chemical exposure, high crime areas, remote sites, etc.

### Lone Worker Check-In Procedure

Detail a daily check-in procedure for all site personnel who will be working alone. Note: There may be a need to detail different check-in procedures for different tasks, personnel etc.

Form of communication to be used for check-in:

Primary check-in person:

Alternate check-in person:

#### Check-In Schedule

Initial Check-In:

Periodic Check-In:

Final Check-Out:





TETRA TECH

Safety Excellence

## HEALTH AND SAFETY PLAN (HASP)

CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected Adjoining Properties, South of East Main Street, Extending Past Curtis Street



### Tetra Tech Compliance Agreement Form

**PROJECT SCOPE:** The current phase of work at the site will include assessment of pavement conditions and investigation of potential asbestos ore contamination in soil.

**PROJECT NUMBER:**

Tetra Tech Project No.:  
1157720035.200

I have read, understood, and agree with the information set forth in this Health and Safety Plan along with any related attachments and discussed in the Personnel Health and Safety briefing.

NAME	SIGNATURE	DATE
Nathan Shumate	Nathan Shumate	12/17/07
Keith Con		12/17/07
Jesse Whitford		12/18/07
Nathan Shumate	Nathan Shumate	12.18.07
NATHAN Shumate	NATHAN Shumate	12.19.07
NATHAN Shumate	Nathan Shumate	12.20.07
Emily Engle	Emily Engle	12/20/07





## Safety Excellence

## Subcontractor Notification of Hazards Acknowledgement Form

I am aware that Tetra Tech has provided this Health and Safety Plan for my review to inform me of the hazards identified with the project site and tasks that Tetra Tech will perform. I understand that this Health and Safety Plan does not fulfill requirements for subcontractor health and safety plans related to the tasks which they will perform.

[illegible]



**Worker / Visitor Log**

**PROJECT SCOPE:**

The current phase of work at the site will include assessment of  
pavement conditions and investigation of potential asbestos ore  
contamination in soil.

Tetra Tech Project No.:  
1157720035.200

Name	Company / Organization	Date	Time In	Time Out
Nathan Shumate	T TECH	12.17.07	8:00	12:00
Nathan Shumate	T TECH	12.17.07	13:00	17:45
Keith Cron	T+	12/17/07	0800	1200
Keith Cron	T+	12/17/07	1300	1745
Nathan Shumate	T TECH	12.18.07	8:00	12:30
Keith Cron	T+	12/18/07	0800	12:30
Colleen Owen	DEQ	12/18/07	1045	?
Nathan Shumate	T TECH	12/18/07	13:30	17:45
Jesse Whitford	T+	12/18/07	0800	1700
Jesse Whitford	T+	12/19/07	0800	1355
Mike Frost	RCM	12-19-07	930	1620
R NAVARRO	ACM	12-19-07	9:30	1620
Nathan Shumate	T+	12.19.07	0800	1800
<del>Mike Frost</del>	T+	12.19.07	0800	1800
Mike Frost	RCM	12-20-07	8:30 AM	1500
Rivera Navarro	ACM	12.20.07	8:50	1500
Nathan Shumate	T TECH	12.20.07	0800	1545
Colleen Owen	DEQ	12.20.07	1330	1520
<del>Mike Frost</del>	T+	12.20.07	0800	1545
<del>Mike Frost</del>	T+	12/20/07	0745	
Ronald W. English	T+	12/20/07	8:00	
Mike Frost	RCM	12-28-07	8 AM	

Colleen Owen DEQ

12-28-07 0930





**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected  
Adjoining Properties, South of East Main Street, Extending Past Curtis  
Street**

**PROJECT SCOPE:**

**Tetra Tech Project No.:**  
**1157720035.200**

## Meeting Facilitator

Nathan Shumate

9:10 ON 12.18.07

## Name

**Company / Organization**

Tetra Tech

---

12



## Daily Tailgate Meeting Form

**PROJECT SCOPE:**

The current phase of work at the site will include assessment of pavement conditions and investigation of potential asbestos ore contamination in soil.

**Tetra Tech Project No.:**  
**1157720035.200**

## Topics Discussed

- LADDER SAFETY
- STRAINS
- SLIPS / TRIPS / FALLS

## Meeting Facilitator

Nathaw Shumath

**Meeting Date / Time**

12.17.07 / 0800

## MEETING ATTENDEES

[illegible]





TETRA TECH

Safety Excellence

**CMC Bozeman Facility AT Wallace Avenue Right-of-Way and Selected  
Adjoining Properties, South of East Main Street, Extending Past Curtis  
Street**

**Daily Tailgate Meeting Form**

**PROJECT SCOPE:**

The current phase of work at the site will include assessment of pavement conditions and investigation of potential asbestos ore contamination in soil.

Tetra Tech Project No.:  
1157720035.200

**Topics Discussed**

- COLD STRESS
- SAFETY around big EQUIPMENT
- TRENCH SAFETY (SIDEWALL COLLAPSE)

**Meeting Facilitator**

NATHAN Shumate

**Meeting Date / Time**

12.19.07 / ~ 0845

**MEETING ATTENDEES****Name****Signature****Company / Organization**

Nathan Shumate

Nathan Shumate

TETRA TECH

Keith Cron

TI

NATHAN Shumate FOR:  
JESS Whitford

T+

Rubén S. NAWAKO

XCM

WHITFORD

PCN



**Daily Tailgate Meeting Form**

**PROJECT SCOPE:**

The current phase of work at the site will include assessment of  
pavement conditions and investigation of potential asbestos ore  
contamination in soil.

Tetra Tech Project No.:  
1157720035.200

**Topics Discussed**

- working around big EQUIPMENT &  
UTILITIES/ STRUCTURES (overhead power)
- PERSONNEL deCON
- BARRICADE TRAFFIC

**Meeting Facilitator**

*Nathan Shumate*

**Meeting Date / Time**

12.20.07 / 0845

**MEETING ATTENDEES**

**Name**

**Signature**

**Company / Organization**

NATHAN SHUMATE

*Nathan Shumate*

TETRA TECH

Keith Cron

*[Signature]*

T+

X RUBEN MARRASO

*[Signature]*

ACM

X M. FURER

*[Signature]*

Gen.





EMSL Analytical, Inc.

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4900 Fax: (856) 856-4960 Email: [westmontlab@EMSL.com](mailto:westmontlab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAXI56  
Customer PO:  
Received: 12/28/07 9:40 AM  
EMSL Order: 040731698

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: **CMC BOZEMAN-1157720035.200**

EMSL Proj:  
Analysis Date: 12/28/2007  
Report Date: 12/28/2007

### Fiber Count by Phase Contrast Microscopy (PCM), NIOSH 7400 Method, Revision 3, Issue 2, 8/15/94

Sample	Location	Sample Date	Volume	Fibers	Fields	LOD (fib/cc)	Fibers/ mm <sup>2</sup>	Fibers/ cc	Notes
39 040731698-0001	SHB- ENVIRONMENTAL WEST	12/19/2007	750.30	<5.5	100	0.004	<7.0	<0.004	
40 040731698-0002	SHB- ENVIRONMENTAL EAST	12/19/2007	758.30	<5.5	100	0.004	<7.0	<0.004	
41 040731698-0003	SHB-ALL TEST PIT LOCATIONS	12/19/2007	750.10	<5.5	100	0.004	<7.0	<0.004	
42 040731698-0004	HEEBS-ENVE WEST (UPWIND)	12/20/2007	699.40	<5.5	100	0.004	<7.0	<0.004	
43 040731698-0005	HEEBS-ENVE EAST (DOWNWIND)	12/20/2007	663.80	<5.5	100	0.004	<7.0	<0.004	
44 040731698-0006	HEEBS-ALL TEST PIT LOCATIONS	12/20/2007	682.70	<5.5	100	0.004	<7.0	<0.004	

No discernable field blanks submitted with this sample set.

Analyst(s)

Delores Beard (6)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

Limit of detection is 7 fibers/mm<sup>2</sup>. The laboratory is not responsible for data reported in fibers/cc, which is dependent on volume collected by non-laboratory personnel. This report relates only to the samples reported above. The test results contained within this report meet the requirements of NELAC unless otherwise noted. This report may not be reproduced, except in full, without written approval by EMSL. Results have been blank corrected as applicable. Samples received in good condition unless otherwise noted.

Analysis performed by EMSL Westmont (NY State ELAP #10872, AIHA #100194)





# Chain of Custody

## Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608

<http://www.emsl.com>

Please print all information legibly.

<b>Company:</b>	Tetra Tech	<b>Bill To:</b>	Tetra Tech
<b>Address1:</b>	1601 2nd Avenue North Suite 116	<b>Address1:</b>	1601 2nd Avenue North Suite 116
<b>Address2:</b>		<b>Address2:</b>	
<b>City, State:</b>	Great Falls, Montana	<b>City, State:</b>	Great Falls, Montana
<b>Zip/Post Code:</b>	59401	<b>Zip/Post Code:</b>	59401
<b>Country:</b>	U.S.A.	<b>Country:</b>	U.S.A.
<b>Contact Name:</b>	Keith Cron	<b>Attn:</b>	Keith Cron
<b>Phone:</b>	406.453.1641	<b>Phone:</b>	406.453.1641
<b>Fax:</b>	406.771.0743	<b>Fax:</b>	406.771.0743
<b>Email:</b>	Keith.Cron@Tetrattech.com	<b>Email:</b>	Keith.Cron@Tetrattech.com
<b>EMSL Rep:</b>		<b>P.O. Number:</b>	
<b>Project Name/Number:</b> CMC Bozeman - 1157720035.200			

MATRIX			TURNAROUND			
<input checked="" type="checkbox"/> Air	<input type="checkbox"/> Soil	<input type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours, Please call ahead to schedule. There is a premium charge for 3-hour tat, please call 1-800-220-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00a.m. Mon -Fri.), Please Refer to Price Quote

<b>PCM - Air</b> <input checked="" type="checkbox"/> NIOSH 7400(A) Issue 2: August 1994 <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input type="checkbox"/> ASTM D 5755-95 (quantitative method) <input type="checkbox"/> Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method fibers/gram	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500
<b>OTHER</b> <input type="checkbox"/>		

SAMPLES ACCEPTED  
FOR ANALYSIS BY  
EMSL ANALYTICAL INC.





## Chain of Custody

### Asbestos Lab Services

**EMSL Analytical, Inc.**  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608

<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) 39 - 44

**Total Samples #:** 6

Relinquished: NATHAN Shumate Date: 12-27-07

Time: P.M.

Received: KW TX Date: \_\_\_\_\_

Time: 790

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

[illegible]



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: [westmontasblab@EMSL.com](mailto:westmontasblab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAXI56  
Customer PO:  
Received: 01/09/08 9:15 AM  
EMSL Order: 040800463

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: **1157720035.200 CMC BOZEMAN FACILITY-SI**

EMSL Proj:  
Analysis Date: 1/9/2008  
Report Date: 1/9/2008

**Fiber Count by Phase Contrast Microscopy (PCM), NIOSH 7400 Method, Revision 3,  
Issue 2, 8/15/94**

Sample	Location	Sample Date	Volume	Fibers	Fields	LOD (fib/cc)	Fibers/ mm <sup>2</sup>	Fibers/ cc	Notes
1-122807 STORY ENV W 040800463-0001	UPWIND ACROSS WALLACE AVE	12/28/2007	1169.00	<5.5	100	0.002	<7.0	<0.002	
2-122807 STORY ENV E 040800463-0002	DOWNWIND @ LIBRARY PARKING LOT	12/28/2007	1165.00	<5.5	100	0.002	<7.0	<0.002	
3-122807 STORY TP 040800463-0003	@ TP LOCATION STORY TP-1- STORY-TP-7 THROUGHOUT DA	12/28/2007	1115.00	<5.5	100	0.002	<7.0	<0.002	

No discernable field blanks submitted with this sample set.

Analyst(s)

Delores Beard (3)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

Limit of detection is 7 fibers/mm<sup>2</sup>. The laboratory is not responsible for data reported in fibers/cc, which is dependent on volume collected by non-laboratory personnel. This report relates only to the samples reported above. The test results contained within this report meet the requirements of NELAC unless otherwise noted. This report may not be reproduced, except in full, without written approval by EMSL. Results have been blank corrected as applicable. Samples received in good condition unless otherwise noted.

Analysis performed by EMSL Westmont (NY State ELAP #10872, AIHA #100194)





# Chain of Custody

## Asbestos Lab Services

040800463

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800

Fax: (856) 858-4960

(856) 427-1608

<http://www.emsl.com>

Please print all information legibly.

<b>Company:</b>	Tetra Tech	<b>Bill To:</b>	Tetra Tech
<b>Address1:</b>	1601 2nd Avenue North	<b>Address1:</b>	1601 2nd Avenue North
<b>Address2:</b>	Suite 116	<b>Address2:</b>	Suite 116
<b>City, State:</b>	Great Falls, Montana	<b>City, State:</b>	Great Falls, Montana
<b>Zip/Post Code:</b>	59404	<b>Zip/Post Code:</b>	59404
<b>Country:</b>	USA	<b>Country:</b>	USA
<b>Contact Name:</b>	Keith Cron	<b>Attn:</b>	Keith Cron
<b>Phone:</b>	406.453.1641	<b>Phone:</b>	406.453.1641
<b>Fax:</b>	406.771.0743	<b>Fax:</b>	406.771.0743
<b>Email:</b>	Keith.Cron@tetrattech.com	<b>Email:</b>	Keith.Cron@tetrattech.com
<b>EMSL Rep:</b>	Stephen Siegel	<b>P.O. Number:</b>	
<b>Project Name/Number:</b> 1157720035.200 CMC Bozeman Facility - SI			

MATRIX			TURNAROUND			
<input checked="" type="checkbox"/> Air	<input type="checkbox"/> Soil	<input type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours, Please call ahead to schedule. There is a premium charge for 3-hour tat, please call 1-800-220-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00a.m. Mon -Fri.), Please Refer to Price Quote

<b>PCM - Air</b> <input checked="" type="checkbox"/> NIOSH 7400(A) Issue 2: August 1994 <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input type="checkbox"/> ASTM D 5755-95 (quantitative method) <input type="checkbox"/> Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method fibers/gram	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500  <b>OTHER</b> <input type="checkbox"/>

SAMPLES ACCEPTED FOR ANALYSIS BY EMSL ANALYTICAL INC.

Sent Fed Ex Via Tracking # 7983 4700 4364





# Chain of Custody

## Asbestos Lab Services

040800463

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608

<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) 1 - 3

Total Samples #: 3

Relinquished: [Signature] Date: 1/8/08

Time: P.M.

Received: DM-FX-915A Date: \_\_\_\_\_

Time: \_\_\_\_\_

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

	SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	VOLUME (if applicable)
1 -	122807 Story ENV W	Upwind across Wallace Ave.	1169 Liters
2 -	122807 Story ENV E	Downwind @ Library Parking Lot	1165 Liters
3 -	122807 Story TP	@ TP Locations Story TP-1 - Story TP-7 throughout Day	1115 Liters

SAMPLES ACCEPTED  
FOR ANALYSIS BY  
EMSL ANALYTICAL INC.



## **APPENDIX C**

### **Documentation of Accreditation**





organized to improve the practice of industrial hygiene  
proclaims that

*Keith C. Cron*

having met all requirements through  
education, experience and examination,  
is hereby certified in the

**COMPREHENSIVE PRACTICE  
of  
INDUSTRIAL HYGIENE**

and has the right to use the designations

**CERTIFIED INDUSTRIAL HYGIENIST**

**CIH**

Certificate Number: 9364 CP

Awarded: November 1, 2007

Expiration Date: June 1, 2013

*Barbara J. Dawson*  
Chair ABIH

*Lynn C. O'Connell*  
Executive Director ABIH



**KEITH C CRON**

has met the requirements of Title 17, Chapter 74.3,  
Subchapter 3, of the Administrative Rules of Montana  
for accreditation in the following asbestos-type  
occupation(s) as indicated by an expiration date(s).

**MTA-3043**

CS	MP	PD	IN
04/13/2008		01/24/2008	04/24/2008
WK			



**MT DEQ Asbestos Control Program**



## NATHAN W SHUMATE

has met the requirements of Title 17, Chapter 74.3,  
Subchapter 3, of the Administrative Rules of Montana  
for accreditation in the following asbestos-type  
occupation(s) as indicated by an expiration date(s).

MTA-3176

CS

04/13/2008

WK

MP

PD

IN

02/20/2008



MT DEQ Asbestos Control Program



## **APPENDIX D**

### **Tetra Tech 6-16-08 Pavement Condition Assessment**





June 16, 2008

Mr. Tim Cooper  
City of Bozeman  
P.O. Box 1230  
Bozeman, Montana 59771

**RE: CMC Bozeman Facility  
Revised Pavement Assessment  
Bozeman, Montana**

In accordance with Montana Department of Environmental Quality's (DEQ's) letter dated December 6, 2007, to the City of Bozeman (City) indicating approval of Tetra Tech's *Supplemental Investigation Workplan – Final Revision*, dated November, 2007, Tetra Tech determined the Pavement Condition Index (PCI), and overall pavement rating for Wallace Avenue from Curtiss Street to East Main Street. The initial pavement assessment was conducted on December 18 and 19, 2007 by Mr. Jess Whitford of Tetra Tech, and a follow-up assessment was conducted on June 12, 2008 by Mr. Marco Fellin of Tetra Tech to include areas that could not be assessed in 2007 due to snow and ice, and also to include several other areas of concern that were not addressed in the initial assessment.

The overall assessment was performed in general accordance with American Standard for Testing and Materials (ASTM) D5340-04, "Airport Pavement Condition Index Surveys," and was modified for the use of quantifying the pavement condition and rating of asphaltic concrete streets and parking areas, along with Portland Cement concrete sidewalks, curb, valley gutter and parking entrance aprons.

The PCI is a numerical rating of the pavement condition that ranges from 0 to 100, with 0 being the worst possible condition and 100 being the best possible condition. The pavement condition rating is a description of the pavement condition as a function of the PCI value that varies from "Failed" to "Excellent." The pavement distress is an external indicator of pavement deterioration caused by loading, environmental factors, construction deficiencies or a combination thereof. The PCI is not a measure of structural capacity, but provides an objective and rational basis for determining maintenance and repair needs and priorities. Typical distresses for asphalt pavement include cracking, rutting and weathering. Typical distresses for concrete are cracking, scaling and spalling. The severity levels of distress for both asphalt and concrete are low, medium and high.

The assessment area was designated by branch, section and sample unit. The branch assessed, as indicated above, was Wallace Avenue and portions of intersecting streets

**Tetra Tech**

2525 Palmer Street, Suite 2, Missoula, Montana 59808

Tel 406.543.3045 Fax 406.543.3088 [www.tetrattech.com](http://www.tetrattech.com)



from Curtiss Street to East Main Street. Boundaries of the assessment were limited to the right of way boundaries as shown in Figure 1. The sections assessed were broke down into areas within each block, such as intersecting streets, parking areas, loading docks, sidewalks, valley gutters, parking entrance aprons, and curbs. The sample units for each section are defined as asphalt pavement or Portland cement concrete. Types of distress observed for asphalt pavement include alligator cracking, block cracking, depression, longitudinal and transverse cracking, patching, raveling, weathering and swelling. Rutting of the asphalt pavement was not observed during the assessment. Slight rutting of the asphalt surface may become evident during the spring/early summer months in areas that are more heavily traveled, once frost is out of the ground, depending upon subgrade soil type, and condition and type of base course aggregate. Distress types encountered in concrete included longitudinal, transverse and diagonal cracking, patching/utility cut, scaling/crazing, settlement and spalling.

Each distress type and severity level were measured either in square feet or linear feet, depending on the type of distress. In general, the distress at each severity level were summed, and calculations performed in accordance with ASTM procedure D5340, to derive at the PCI value. The determination of severity level; low, medium or high, varies depending on the type of distress. A copy of the field notes, distress types observed, and deduct values is included in Attachment C. A brief description of distress types encountered, are explained as follows:

### **Asphalt Pavement Distress**

**Rutting:** This is a surface depression, typically in the wheel path. Rutting stems from permanent deformation in any of the pavement layers or subgrade, usually caused by lateral movement of the materials due to traffic loads.

**Alligator Cracking:** Typically referred to as fatigue cracking, is caused by repeated traffic loading, and are interconnecting cracks caused by fatigue failure. The cracks connect, forming many-sided, sharp angled pieces that develop a pattern resembling chicken wire. This type of distress is typically located only in traffic areas, such as wheel paths. As shown in figure 1, an increased quantity of alligator cracking is apparent with areas receiving a higher volume of traffic. During our assessment, the highest volume of traffic was observed to be from Babcock Street to East Main Street, with the next highest volume of traffic occurring between Olive Street and Babcock Street. The lowest volume of traffic was noted between Curtiss Street to Olive Street. Alligator cracking is considered a major structural distress, because the cracking is typically through out the full depth of the asphalt pavement thickness.

**Block Cracking:** Similar to alligator cracking, except that it occurs in larger rectangular portions of the pavement area, and may occur in non traffic areas.

**Depression:** A depression is a localized area in the pavement that has elevations slightly lower than those of the surrounding pavement. A severe case of a depression may be considered a pothole. In many instances, light depressions are not noticeable until after a rain, when ponding water creates “birdbath” areas.



**Longitudinal and Transverse Cracking:** Generally a longitudinal crack will appear parallel to centerline, or lay down direction, and transverse cracks extend across the pavement at approximately right angles. This type of distress is not generally related to repeated loading, but may be caused due to poor joint construction or shrinkage of the pavement surface.

**Patching:** A patch is considered a defect no matter how well it is performing. Patch work is typically performed as a surface repair or after accessing underground utilities.

**Raveling and Weathering:** Weathering is wearing of the surface to the dislodging of aggregates and loss of asphalt.

### **Portland Cement Concrete Distress**

**Longitudinal/Transverse and Diagonal Cracking:** These types of cracks divide the slab into two or three pieces, and are usually caused by the combination of repeated loading and shrinkage stresses.

**Scaling, Map Cracking and Crazing:** This refers to a network of shallow, fine cracks that extend only through the upper surface. This condition may be caused by over finishing of the concrete, resulting in scaling. This condition may also be caused by deicing chemicals, or continued freeze thaw cycles.

**Settlement:** This condition is a difference in elevation at a joint or crack, and is caused by upheaval or consolidation.

**Corner Spalling:** This is a raveling or breakdown of the concrete within approximately 2' of a corner.

**Patching/Utility Cut:** This is a simple patch that has occurred as a result of accessing underground utilities or other excavation work.

Attachment A contains a summary of each section assessed, type of sample unit, and PCI Value and Rating for each sample unit, including; listing of distress types, and severity and quantity of distress types observed for each sample unit. The seven additional pavement sections (three asphalt sections and four concrete sections) reviewed on June 12, 2008 are included at the end of the summary table. For purposes of suggested remediation for the various distress types, the priority of action is based on the low, medium, and high distress ratings listed in Attachment A. Immediate action is suggested for high distress ratings, which would include complete reconstruction of the pavement section. A medium distress rating also suggests that immediate action should be taken, which could include isolated repairs/patches, and preventative maintenance such as crack sealing or applying a seal coat. Pavement sections with low distress ratings suggest that no immediate action is required.





Attachment B contains a figurative representation of the asphalt pavement sections with either medium or high severity distress encountered during the field assessment. Immediate action should be taken on all of these sections. Due to the scale of Figure 1 in Appendix B, distress type and severity level of Portland Cement Concrete, including curb, sidewalk, parking entrance aprons and valley gutter, are not shown. Please refer to Attachment A for description and location of concrete distress types and quantities.

Sincerely,

Tetra Tech

Marco Fellin, P.E.  
Project Geotechnical Engineer

Attachment A: Tables of PCI Values with Ratings  
Attachment B: Figure 1. Distress Type and Severity Level  
Attachment C: Survey Data Sheets and Field Notes

cc w/attachments: Keith Cron, Tetra Tech, 1601 2<sup>nd</sup> Avenue North, Suite 116, Great Falls, Montana 59401





**ATTACHMENT A:**  
**Tables of PCI Values with Ratings**



**PCI ASSESSMENT SUMMARY**  
**Tetra Tech Project No. 1157720035.200**

**BRANCH: WALLACE STREET**

Section	Type of Sample Unit	PCI	Rating
Curtis Street to Wallace Street	Asphalt Pavement	65	Good
Curtiss Street to Olive Street	Asphalt Pavement	46	Fair
Parking at 212 S. Wallace	Asphalt Pavement	46	Fair
Loading Dock Entrance/Parking; N end of 212 Wallace Street	Asphalt Pavement	50	Fair
S edge of Olive Street to S edge of Babcock Street	Asphalt Pavement	44	Fair
Olive Street to Wallace Street	Asphalt Pavement	52	Fair
Babcock Street to Wallace Street	Asphalt Pavement	55	Fair
S edge of Babcock to East Main Street	Asphalt Pavement	26	Poor
Sidewalk; W side of Wallace Street, Curtiss Street to Olive Street	Portland Cement Concrete	82	Very Good
Curtiss Street Valley Gutter	Portland Cement Concrete	56	Fair
W side of Wallace Street between Curtiss Street and Olive Street; Parking Lot entrance Apron	Portland Cement Concrete	50	Fair
North and South Curb radius of Curtiss Street	Portland Cement Concrete	100	Excellent
Curb; W side of Wallace Street, 142' N of Curtiss Street to Parking Lot entrance apron	Portland Cement Concrete	50	Fair
Curb; W side of Wallace Street from Parking Lot entrance apron to Olive Street	Portland Cement Concrete	90	Excellent
SW Curb radius on Olive Street	Portland Cement Concrete	70	Good
NW Curb radius on Olive Street	Portland Cement Concrete	18	Very Poor
Curb; W side of Wallace Street, Olive street to Babcock Street	Portland Cement Concrete	44	Fair
Sidewalk: W side of Wallace street, First 22 section N of Olive Street	Portland Cement Concrete	55	Fair
Sidewalk: W side of Wallace street, Sections 23-38 N of Olive Street	Portland Cement Concrete	95	Excellent
Sidewalk: W side of Wallace street, Sections 39-46 N of Olive Street	Portland Cement Concrete	0	Failed
Sidewalk: W side of Wallace street, Sections 47-53 N of Olive Street	Portland Cement Concrete	95	Excellent
Sidewalk: W side of Wallace street, Sections 54-66 N of Olive Street	Portland Cement Concrete	66	Good
Sidewalk: W side of Wallace street, First 29 sections N of Babcock Street to SE corner of Heeb's Market	Portland Cement Concrete	70	Good
Sidewalk: W side of Wallace street, E end of Heeb's Market, (60' length)	Portland Cement Concrete	32	Poor
Sidewalk: W side of Wallace street from NE corner of Heeb's Market, to Parking Lot entrance apron	Portland Cement Concrete	42	Fair
Parking Lot entrance apron to Heeb's Market	Portland Cement Concrete	95	Excellent
Sidewalk: W side of Wallace street from N end of Heeb's Market Parking Lot entrance apron to East Main Street	Portland Cement Concrete	100	Excellent
Curb radius, N and S side of Babcock Street	Portland Cement Concrete	70	Good
Curb; W side of Wallace Street, 91' N of Babcock Street to garage entrance apron	Portland Cement Concrete	70	Good



**BRANCH: WALLACE STREET (continued)**

Residential entrance sidewalk: 7' length:			
Curb radius at East Main Street and W side of Wallace Street	Portland Cement Concrete	100	Excellent
107 Wallace Street	Portland Cement Concrete	70	Good
113 Wallace Street	Portland Cement Concrete	95	Excellent
115 Wallace Street	Portland Cement Concrete	70	Good
117 Wallace Street	Portland Cement Concrete	70	Good
121 Wallace Street	Portland Cement Concrete	70	Good
Business sidewalk entrance:			
Springer Group	Portland Cement Concrete	95	Excellent
Gallatin Valley Seed-Main Entrance	Portland Cement Concrete	95	Excellent
Gallatin Valley Seed-South Entrance	Portland Cement Concrete	95	Excellent
-----	-----	-----	
<b>Sections Below were Surveyed on June 12 - 2008</b>			
Eastern Parking area in Heeb's Market, just west of concrete sidewalk	Asphalt Pavement	80	Very Good
East end of Alley behind Heeb's Market.	Asphalt Pavement	100	Excellent
Entrance to Babcock apartments from alley behind Heeb's.	Asphalt Pavement	66	Good
4-foot wide concrete slab along entire south side of Heeb's Market.	Portland Cement Concrete	80	Very Good
Concrete curb west of Wallace Ave. extending between alley and entrance to Heeb's Market.	Portland Cement Concrete	92	Excellent
Residential Concrete Driveway south of alley behind Heeb's Market and west of Wallace Ave.	Portland Cement Concrete	30	Poor
Residential Concrete Driveway south of alley behind Heeb's Market, approximately 100 feet west of Wallace Ave.	Portland Cement Concrete	42	Fair

Please see the following pages for a detailed summary including assessment distress types encountered, severity and quantity, for each sample unit.



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location:** Curtiss Street to Wallace Street

**Number of Sample Units in Section:** 1

**Number of Sample Units Assessed:** 1

**Total Area Represented:** 350 sq. ft

Type of Distress Observed	Severity	Quantity
5	Medium	4 sq. ft.
3	Low	84 sq. ft.
6	Low	21 Lf
PCI = 65                      Rating: Good		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-10  
11-25  
26-40  
41-56  
57-70  
71-86  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
5. Depression  
6. Long. & Trans Cracking  
7. Oil Spillage

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving  
13. Slippage Cracking  
14. Swell



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location: Curtiss Street to Olive Street**

**Number of Sample Units in Section: 1**

**Number of Sample Units Assessed: 1**

**Total Area Represented: 11,310 sq. ft.**

Type of Distress Observed	Severity	Quantity
6	Low	282 Lf
1	Low	658 sq. ft.
1	Medium	56 sq. ft.
5	Low	269 sq. ft.
5	Medium	32 sq. ft.
5	High	5 sq. ft.
PCI = 46                      Rating: Fair		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-11  
11-25  
26-40  
41-56  
57-70  
71-87  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
5. Depression  
6. Long. & Trans Cracking  
7. Oil Spillage

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving  
13. Slippage Cracking  
14. Swell



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location:** Parking at 212 S Wallace Street

**Number of Sample Units in Section:** 1

**Number of Sample Units Assessed:** 1

**Total Area Represented:** 6955 sq. ft.

Type of Distress Observed	Severity	Quantity
1	Low	655 sq. ft.
5	Low	40 sq. ft.
6	Low	61 Lf.
6	Medium	16 Lf.
PCI = 46		Rating: Fair

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-12  
11-25  
26-40  
41-56  
57-70  
71-88  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
5. Depression  
6. Long. & Trans Cracking  
7. Oil Spillage

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving  
13. Slippage Cracking  
14. Swell



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location: Loading Dock Entrance/Parking**

**Number of Sample Units in Section: 1**

**Number of Sample Units Assessed: 1**

**Total Area Represented: 3306 sq. ft.**

Type of Distress Observed	Severity	Quantity
5	High	225 sq. ft.*
6	Low	40 Lf.
PCI = 50		Rating: Fair

\* Note: Depression appeared to be intentionally constructed to divert drainage away from adjacent window well.

<u>PCI</u>	<u>RATING SCALE</u>	<u>DISTRESS TYPES</u>	
0-13	Failed	1. Alligator Cracking	8. Patching
11-25	Very Poor	2. Bleeding	9. Polished Aggregate
26-40	Poor	3. Block Cracking	10. Raveling/Weathering
41-56	Fair	4. Corrugation	11. Rutting
57-70	Good	5. Depression	12. Shoving
71-89	Very Good	6. Long. & Trans Cracking	13. Slippage Cracking
87- 100	Excellent	7. Oil Spillage	14. Swell



## INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Total Area Represented: 10,710 sq. ft.**



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location: Olive Street to Wallace Street**

**Number of Sample Units in Section: 1**

**Number of Sample Units Assessed: 1**

**Total Area Represented: 450 sq. ft.**

Type of Distress Observed	Severity	Quantity
8	Low	30 sq. ft.
5	Medium	60 sq. ft.
PCI = 52                      Rating: Fair		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-15  
11-25  
26-40  
41-56  
57-70

Failed  
Very Poor  
Poor  
Fair  
Good

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
5. Depression

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location: Babcock Street to Wallace Street**

**Number of Sample Units in Section: 1**

**Number of Sample Units Assessed: 1**

**Total Area Represented: 450 sq. ft.**

Type of Distress Observed	Severity	Quantity
8	Low	210 sq. ft.
6	Medium	32 Lf.
PCI = 55                      Rating: Fair		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-16  
11-25  
26-40  
41-56  
57-70

Failed  
Very Poor  
Poor  
Fair  
Good

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
5. Depression

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location:** S edge of Babcock Street to East Main Street

**Number of Sample Units in Section:** 1

**Number of Sample Units Assessed:** 1

**Total Area Represented:** 10,688 sq. ft.

Type of Distress Observed	Severity	Quantity
1	Medium	570 sq. ft.
1	Low	755 sq. ft.
6	High	30 Lf.
6	Low	250 Lf.
8	Low	360 sq. ft.
8	Medium	47 Lf.
3	Low	250 sq. ft.
PCI = 26                      Rating: Poor		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-17  
11-25  
26-40  
41-56  
57-70

Failed  
Very Poor  
Poor  
Fair  
Good

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
5. Depression

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** W Sidewalk, Curtiss St. to Oliver  
**Number of Sample Units in Section:** 66  
**Number of Sample Units Assessed:** 66  
**Total Area Represented:** 66 (5'x5')

**Location:** Curtiss St. Valley Gutter  
**Number of Sample Units in Section:** 1  
**Number of Sample Units Assessed:** 1  
**Total Area Represented:** Entire Valley Gutter

Type of Distress Observed	Severity	Quantity
3	Low	2 slabs
3	Medium	1 slab
10	Low	3 slabs
11	Medium	6 slabs
PCI = 82                      Rating: Very Good		

Type of Distress Observed	Severity	Quantity
3	Medium	2 slabs
PCI = 56                      Rating: Fair		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-18  
 11-25  
 26-40  
 41-56  
 57-70  
 71-91  
 87- 100

Failed  
 Very Poor  
 Poor  
 Fair  
 Good  
 Very Good  
 Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints
	15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location: W Parking Entrance Apron  
Between Curtiss and Olive**

**Number of Sample Units in Section: 1**

**Number of Sample Units Assessed: 1**

**Total Area Represented: 2 slabs**

**Location: N & S Curb radius; Curtiss St.**

**Number of Sample Units in Section: 2**

**Number of Sample Units Assessed: 2**

**Total Area Represented: 2 curb radius**

Type of Distress Observed	Severity	Quantity
3	Medium	2 slabs
PCI = 50                      Rating: Fair		

Type of Distress Observed	Severity	Quantity
None		2 curb radius
PCI = 100                      Rating: Excellent		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-19  
11-25  
26-40  
41-56  
57-70  
71-92  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up  
2. Corner Break  
3. Long/Trans/Diagonal Crack  
4. Durability Crack  
5. Joint Seal Damage  
6. Patching  
7. Patching/Utility Cut  
8. Popouts  
9. Pumping  
10. Scaling/Map Cracking  
11. Settlement  
12. Shattered Slab  
13. Shrinkage Crack  
14. Spalling-Joints  
15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** W Curb, 142' N of Curtis  
to parking entrance  
**Number of Sample Units in Section:** 1  
**Number of Sample Units Assessed:** 1  
**Total Area Represented:** 142 Lf.

**Location:** W curb from parking entrance  
to Olive St.  
**Number of Sample Units in Section:** 1  
**Number of Sample Units Assessed:** 1  
**Total Area Represented:** 164 Lf.

Type of Distress Observed	Severity	Quantity
15	Medium	115 Lf.
PCI = 50                  Rating: Fair		

Type of Distress Observed	Severity	Quantity
15	Low	Minimal
PCI = 90                  Rating: Excellent		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-20  
11-25  
26-40  
41-56  
57-70  
71-93  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints
	15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location: SW curb radius on Olive St.**

**Location: NW curb radius on Olive St.**

**Number of Sample Units in Section: 1**

**Number of Sample Units in Section: 1**

**Number of Sample Units Assessed: 1**

**Number of Sample Units Assessed: 1**

**Total Area Represented: 1 Curb Radius**

**Total Area Represented: 1 Curb radius**

Type of Distress Observed	Severity	Quantity
15	Low	1 curb
PCI = 70                  Rating: Good		

Type of Distress Observed	Severity	Quantity
15	High	1 curb
PCI = 18                  Rating: Very Poor		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-21  
11-25  
26-40  
41-56  
57-70  
71-94  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints
	15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location: W Curb, Olive St. to Babcock St.**

**Number of Sample Units in Section: 1**

**Number of Sample Units Assessed: 1**

**Total Area Represented: 299 Lf.**

**Location: Sidewalk, W side of Wallace St.,  
1<sup>st</sup> 22 sections N of Olive St.**

**Number of Sample Units in Section: 22**

**Number of Sample Units Assessed: 22**

**Total Area Represented: 22 (5'x5')**

Type of Distress Observed	Severity	Quantity
10	Low	197Lf.
10	Medium	17 Lf.
10	High	19 Lf.
PCI = 44                      Rating: Fair		

Type of Distress Observed	Severity	Quantity
3	Low	4 slabs
10	Low	2 slabs
10	High	2 slabs
7	Low	1 slab
PCI = 55                      Rating: Fair		

Note: The first 31', and last 40' of curb was covered with snow and ice.

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-22  
11-25  
26-40  
41-56  
57-70  
71-95  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints
	15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location: Sidewalk, W side of Wallace St. ,  
Sections 23-38 N of Olive St.**

**Number of Sample Units in Section: 15  
Number of Sample Units Assessed: 15  
Total Area Represented: 15-(5'x5')**

**Location: Sidewalk, W side of Wallace St.,  
sections 39-46 N of Olive St  
(35' N of 107 Wallace St.)**

**Number of Sample Units in Section: 7  
Number of Sample Units Assessed: 7  
Total Area Represented: 7 (5'x5')**

Type of Distress Observed	Severity	Quantity
7	Low	1 slab
PCI = 95                  Rating: Excellent		

Type of Distress Observed	Severity	Quantity
10	High	7 slabs
PCI = 0                  Rating: Failed		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-23  
11-25  
26-40  
41-56  
57-70  
71-96  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints
	15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** Sidewalk, W side of Wallace St.  
**47-53 sections N of Olive St.**  
**Number of Sample Units in Section:** 6  
**Number of Sample Units Assessed:** 6  
**Total Area Represented:** 6-(5'x5')

**Location:** Sidewalk, W side of Wallace St.  
**54-66 sections N of Olive St.**  
**Number of Sample Units in Section:** 12  
**Number of Sample Units Assessed:** 12  
**Total Area Represented:** 12-(5'x5')

Type of Distress Observed	Severity	Quantity
None	Low	Minimal
PCI = 95                      Rating: Excellent		

Type of Distress Observed	Severity	Quantity
3	Low	2 slabs
10	Low	9 slabs
PCI = 66                      Rating: Good		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-24  
 11-25  
 26-40  
 41-56  
 57-70  
 71-97  
 87- 100

Failed  
 Very Poor  
 Poor  
 Fair  
 Good  
 Very Good  
 Excellent

- |                              |                          |
|------------------------------|--------------------------|
| 1. Blow Up                   | 8. Popouts               |
| 2. Corner Break              | 9. Pumping               |
| 3. Long/Trans/Diagonal Crack | 10. Scaling/Map Cracking |
| 4. Durability Crack          | 11. Settlement           |
| 5. Joint Seal Damage         | 12. Shattered Slab       |
| 6. Patching                  | 13. Shrinkage Crack      |
| 7. Patching/Utility Cut      | 14. Spalling-Joints      |
|                              | 15. Spalling-Corner      |



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** W sidewalk, N of Babcock  
to SE corner of Heeb's Market  
**Number of Sample Units in Section:** 29  
**Number of Sample Units Assessed:** 29  
**Total Area Represented:** 29-(5'x5')

**Location:** Sidewalk, E end of Heeb's  
60' length  
**Number of Sample Units in Section:** 3  
**Number of Sample Units Assessed:** 3  
**Total Area Represented:** 678 sq. ft.

Type of Distress Observed	Severity	Quantity
10	Low	19 slabs
3	Low	5 slabs
PCI = 70                  Rating: Good		

Type of Distress Observed	Severity	Quantity
7	Low	1 slab
11	High	1 slab
3	Medium	3 slabs
3	Low	3 slabs
PCI = 32                  Rating: Poor		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-25  
11-25  
26-40  
41-56  
57-70  
71-98  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up  
2. Corner Break  
3. Long/Trans/Diagonal Crack  
4. Durability Crack  
5. Joint Seal Damage  
6. Patching  
7. Patching/Utility Cut

8. Popouts  
9. Pumping  
10. Scaling/Map Cracking  
11. Settlement  
12. Shattered Slab  
13. Shrinkage Crack  
14. Spalling-Joints  
15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** Sidewalk, NE corner of Heeb's  
to parking entrance  
**Number of Sample Units in Section:** 1  
**Number of Sample Units Assessed:** 1  
**Total Area Represented:** 271 sq. ft.

**Location:** Sidewalk, Heeb's parking entrance  
to East Main St.  
**Number of Sample Units in Section:** 1  
**Number of Sample Units Assessed:** 1  
**Total Area Represented:** 339 sq. ft.

Type of Distress Observed	Severity	Quantity
3	Low	1 slab
PCI = 42                  Rating: Fair		

Type of Distress Observed	Severity	Quantity
None	Low	Minimal
PCI = 100                  Rating: Excellent		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-26  
11-25  
26-40  
41-56  
57-70  
71-99  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up  
2. Corner Break  
3. Long/Trans/Diagonal Crack  
4. Durability Crack  
5. Joint Seal Damage  
6. Patching  
7. Patching/Utility Cut  
8. Popouts  
9. Pumping  
10. Scaling/Map Cracking  
11. Settlement  
12. Shattered Slab  
13. Shrinkage Crack  
14. Spalling-Joints  
15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** Heeb's parking entrance

**Location:** Curb radius, N&S side of Babcock

**Number of Sample Units in Section:** 8

**Number of Sample Units in Section:** 2 curb radius

**Number of Sample Units Assessed:** 8

**Number of Sample Units Assessed:** 2 curb radius

**Total Area Represented:** 8- (5'x5')

**Total Area Represented:** N&S curb radius

Type of Distress Observed	Severity	Quantity
None	Low	Minimal
PCI =95                      Rating: Excellent		

Type of Distress Observed	Severity	Quantity
10	Low	2 curb radius
15	Low	2 curb radius
PCI = 70                      Rating: Good		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-27  
11-25  
26-40  
41-56  
57-70  
71-100  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints
	15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** W Curb, 91' N of Babcock  
to garage entrance  
**Number of Sample Units in Section:** 91 Lf  
**Number of Sample Units Assessed:** 91 Lf.  
**Total Area Represented:** 91 Lf.

**Location:** W Curb, SE corner of Heeb's parking  
to parking entrance  
**Number of Sample Units in Section:**  
**Number of Sample Units Assessed:**  
**Total Area Represented:**

Type of Distress Observed	Severity	Quantity
10	Low	91 Lf.
PCI = 70                      Rating: Good		

Type of Distress Observed	Severity	Quantity
NA*		
Covered with snow and ice in December 2007, rated on June 12, 2008, see below.		

\*Not Applicable

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-28  
11-25  
26-40  
41-56  
57-70  
71-101  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints
	15. Spalling-Corner



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** Curb radius at East Main  
And Wallace St.

**Number of Sample Units in Section:** 1  
**Number of Sample Units Assessed:** 1  
**Total Area Represented:** 1 curb radius

**Location:** Entrance sidewalks; Springer Group  
Gallatin Valley Seed, Main ent. and South ent.  
And 113 Wallace St.

**Number of Sample Units in Section:** 3  
**Number of Sample Units Assessed:** 3  
**Total Area Represented:** 3 Entrance sidewalks

Type of Distress Observed	Severity	Quantity
None	Low	Minimal
PCI = 100                  Rating: Excellent		

Type of Distress Observed	Severity	Quantity
None	Minimal	3
PCI = 95                  Rating: Excellent		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-29  
11-25  
26-40  
41-56  
57-70  
71-102  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** Residential entrance Sidewalks; 107, 115,  
117 and 121 Wallace St.

**Number of Sample Units in Section:** 4

**Number of Sample Units Assessed:** 4

**Total Area Represented:** 4 Entrance sidewalks

Type of Distress Observed	Severity	Quantity
10	Low	4 slabs
15	Low	4 slabs

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-30  
11-25  
26-40  
41-56  
57-70  
71-103  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up  
2. Corner Break  
3. Long/Trans/Diagonal Crack  
4. Durability Crack  
5. Joint Seal Damage  
6. Patching  
7. Patching/Utility Cut  
8. Popouts  
9. Pumping  
10. Scaling/Map Cracking  
11. Settlement  
12. Shattered Slab  
13. Shrinkage Crack  
14. Spalling-Joints



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location:** Eastern Parking area in Heeb's Market, just west of concrete sidewalk

**Number of Sample Units in Section:** 1

**Number of Sample Units Assessed:** 1

**Total Area Represented:** 1,260 sq. ft.

Type of Distress Observed	Severity	Quantity
8	Low	15
3	Low	4
6	Low	30 Lf.
PCI = 80                      Rating: Very Good		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-31  
11-25  
26-40  
41-56  
57-70

Failed  
Very Poor  
Poor  
Fair  
Good

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
6. Longitudinal/Transverse  
Cracking

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving



## INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Total Area Represented: 246.5 sq. ft.**

Type of Distress Observed	Severity	Quantity
None Observed		
PCI = 100 Rating: Excellent		

<u>PCI</u>	<u>RATING SCALE</u>	<u>DISTRESS TYPES</u>	
0-32	Failed	1. Alligator Cracking	8. Patching
11-25	Very Poor	2. Bleeding	9. Polished Aggregate
26-40	Poor	3. Block Cracking	10. Raveling/Weathering
41-56	Fair	4. Corrugation	11. Rutting
57-70	Good	5. Depression	12. Shoving



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR ASPHALT PAVEMENT

**Location:** Entrance to Babcock apartments from alley behind Heeb's.

**Number of Sample Units in Section:** 1

**Number of Sample Units Assessed:** 1

**Total Area Represented:** 405 sq. ft.

Type of Distress Observed	Severity	Quantity
10	Low	405 sq. ft.
6	Low	27 lin. Ft.
PCI = 66                      Rating: Good		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-33  
11-25  
26-40  
41-56  
57-70

Failed  
Very Poor  
Poor  
Fair  
Good

1. Alligator Cracking  
2. Bleeding  
3. Block Cracking  
4. Corrugation  
6. Longitudinal Cracking

8. Patching  
9. Polished Aggregate  
10. Raveling/Weathering  
11. Rutting  
12. Shoving



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location:** 4-foot wide concrete slab  
along entire south side of Heeb's.

**Location:** Concrete curb west of Wallace Ave.  
extending between alley and entrance to Heeb's.

**Number of Sample Units in Section:** 10  
**Number of Sample Units Assessed:** 10  
**Total Area Represented:** 680 sf

**Number of Sample Units in Section:** 7  
**Number of Sample Units Assessed:** 7  
**Total Area Represented:** 75.6 lineal feet of curb

Type of Distress Observed	Severity	Quantity
3	Low	41 lf
PCI = 80                      Rating: Very Good		

Type of Distress Observed	Severity	Quantity
14	Low	2 lengths
PCI = 92                      Rating: Excellent		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-34  
11-25  
26-40  
41-56  
57-70  
71-104  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints



## PCI ASSESSMENT SUMMARY

### INDIVIDUAL SAMPLE UNIT FOR PORTLAND CEMENT CONCRETE

**Location: Residential Concrete**  
**Driveway south of alley behind Heeb's**  
**Market and just west of Wallace Ave.**  
**Number of Sample Units in Section: 3**  
**Number of Sample Units Assessed: 3**  
**Total Area Represented: 540 sqft**

**Location: Residential Concrete Driveway south of alley**  
**behind Heeb's Market, approximately 100 feet west of**  
**Wallace Ave.**  
**Number of Sample Units in Section: 3**  
**Number of Sample Units Assessed: 3**  
**Total Area Represented: 3 Entrance sidewalks**

Type of Distress Observed	Severity	Quantity
5	Low	31lf
3	Low	34lf
3	Medium	48lf
PCI = 30                      Rating: Poor		

Type of Distress Observed	Severity	Quantity
3	Medium	50 lf
PCI = 42                      Rating: Fair		

#### PCI

#### RATING SCALE

#### DISTRESS TYPES

0-35  
11-25  
26-40  
41-56  
57-70  
71-105  
87- 100

Failed  
Very Poor  
Poor  
Fair  
Good  
Very Good  
Excellent

1. Blow Up	8. Popouts
2. Corner Break	9. Pumping
3. Long/Trans/Diagonal Crack	10. Scaling/Map Cracking
4. Durability Crack	11. Settlement
5. Joint Seal Damage	12. Shattered Slab
6. Patching	13. Shrinkage Crack
7. Patching/Utility Cut	14. Spalling-Joints



**ATTACHMENT B:**  
**Figure 1: Distress Type And Severity Level**









**ATTACHMENT C:**  
**Survey Data Sheets and Field Notes**



UNIT: Entrance to Balcon Apartments from Alley behind  
Heabs.



 D 5340 - 04<sup>01</sup>

FIG. X4.16 Corrected DVA for Jointed Rigid Airfield Pavements

## XS, BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

CDV

28 17  $\rightarrow q=2$  28

28 5 — 33  $q=1 \rightarrow 34$

PCI = 66 = Good Condition






FIG. X4.16 Corrected DVs for Jointed Rigid Airfield Pavements

## X5. BLANK FORMS

X5.1 See Fig. X5.1 and X5.2.

Unit - Asphalt Section at  
East End of Alley.


[illegible]

FIG. X6.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

No Distress Observed

$$PCI = 100$$





## X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

Parking Area in East Hecks Lot Adjacent to Wallace

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

total  $\rightarrow$   $\angle DV$

855-18 ① 20

PCI = 80 : Very Good



5 D 5340 - 04<sup>1</sup>




FIG. X4.15 Corrected DVs for Jointed Rigid Airfield Pavements

## X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

Tally Survey Data Sheet for Sample Unit				
Plot	1	2	3	4
9-2	40	17	57	410
52 9-1	40	5	45	42

PC = 100 - 40 = 57 = 57%

40 to 50: Fine



Agmatt

30' x 357'


12/10/7

21

12.2

19  
4.20  
296

154

 D 5340 - 04<sup>e1</sup>




FIG. X4.16 Corrected DVs for Jointed Rigid Airfield Pavements

## X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

Revised CDV

PCJ 100-5644 from

265	32	1	0	7	6	10	3.45	77	40
(4)	32	1	10	7	5	2.5	2	72.0	40
13	72	0	0	5	5	0	0	-10.0	44
ones authorized.									
	32	15	5	5	0	4.5	20	19.5	46
(1)	72	5	5	0	5	4.5	3.0	59.5	50



Park St. 212 S. Waller  
Harrington Papers

ASTM D 5340 - 04<sup>1</sup>




FIG. X4.16 Corrected DVs for Jointed Rigid Airfield Pavements

Low diversity = sensitive area

## X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

Q. 42.5 + 50 = 92.5 = 92.50  
Q. 43 = 54  
= FCI = 100 - 54 = 46 = Fair  
40 to 50 is Fair



Start 15' S of edge of  
Curb  
377' x 10' x 10' x 10'

Street  
2' curb in curb

to AC Planting  
2' x 10'




FIG. X4.15 Corrected DVs for Jointed Rigid Airfield Pavements

X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

AIRFIELD ASPHALT PAVEMENT CONDITION SURVEY DATA SHEET FOR SAMPLE UNIT										SKETCH:		
BRANCH <u>Waller Ave</u>		SECTION <u>12-18</u>		SAMPLE UNIT <u>AS</u>		SURVEYED BY <u>U.S.</u> DATE <u>12-18</u> SAMPLE AREA <u>110' x 100'</u>						
1. Alligator Cracking		5. Depression		9. Oil Spillage		13. Rutting						
2. Bleeding		6. Jet Blast		10. Patching		14. Shoving from PCC						
3. Block Cracking		7. Jt. Reflection (PCC)		11. Polished Aggregate		15. Slippage Cracking						
4. Corrugation		8. Long. & Trans. Cracking		12. Raveling/Weathering		16. Swell						
DISTRESS SEVERITY	QUANTITY								TOTAL	DENSITY %	DEDUCT VALUE	
SL	31	18"	27:2	10"	9.5	10	120	130	282.4	2.49	7.0	
SM	16											
SL	8	10										
SL	56	8	10	16	2	10	120	130	658.4	5.12	3.1	
SL	16	2	50	16	8		180	160	260.4	2.30	11.1	
SL	40	11							520.4	2.49	24.0	
SH	5								5.4	1.04	0.1	
SL	252								252.4	2.27	5.5	
SM	32.4								22.4	1.28	7.0	
SL	110.4								110.4	6.77	3.0	
											97.6	

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

PCP = 140-58-40  
4/6/10  
40 to 56 F



# PCI History

A.C. Phoenix

S. Side of Lincoln Street to S. End of Olive Street

8<sup>th</sup> 7<sup>th</sup> over 117.5 21.4

CON = 54

									OV	CON
9-74	38.0	25.0	24.0	11.0	7.0	7.0	5.0	0.1	$\frac{92.6}{117.5}$	54 46
9-60	38.0	25.0	24.0	11.0	7.0	7.0	5.0	0.1	117.5 21.4	54 46
9-64	38.0	25.0	24	11	7	5	5	0.1	117.5 21.4	54 46
9-47	38	25	24	11	5	5	5	0.1	117.5 21.4	54 52
9-25	38	25	24	5	5	5	5	0.1	117.5 21.4	54 52
9-21	38	25	5	5	5	5	5	0.1	117.5 21.4	54 58
9-7	38	5	5	5	5	5	5	0.1	117.5 21.4	54 58

$$PCI = 100 - 64 = 36$$

$$PCI = 100 - 58 = 42 \text{ Fair}$$

$$40.56 = \text{Fair}$$



CD # 7720035




FIG. X4.16 Corrected DVs for Jointed Rigid Airfield Pavements

ac Planning: 10' x 25' x 5' x 2'

Consent given: 5x3  
1750g

## X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

$$\max \text{COV} = 35$$

PCF-100-35-63

*Katany - 1301*

site 60 is 56-75



A.C. Paving

Intersect of 2 Center 12' to 1' wall base  
(12' of center 2 1' W edge of wall base)

Area = 15 x 25 = 525 sq ft

A.C. Paving = 10 x 35 = 350 sq ft

Concrete = 5 x 35 = 175 sq ft concrete

Pavement Condition Index (PCI) - Recommended Rating 0-100

Pavement Condition Rating - Ranges from "Failed" to "Excellent"

no. of  
units 2 ft  
square

$$N = \frac{\left(\frac{e^2}{4}\right)(10 - 1 + 5^2)}{}$$

2 = acceptable error (assuming 25 PCI points)

5 = Standard Deviation of the PCI, Taken 10 ft

AC and 15 for Concrete

N: Total number of single units

Calculating PCI for AC Pavement

Example of Center 2 Wall base (350 sq ft)

Disturb	Quantity	Total	Disturb %	Deduct Value
10	4 sq ft	4 sq ft	1.14 %	15.0 = 5.5
20	84 sq ft	84 sq ft	24.0 %	20.0 = 20.0
30	216 sq ft	216 sq ft	60.9 %	15.0 = 15.0
100	350 sq ft	350 sq ft	100 %	27.5 = 27.5

$$N = \frac{50}{7.92} = 6.3$$

$$m = 1.4 (9.145) (100 - 27.5) = 7.92$$

$$q = 4$$

PCI 56-70 is good  
Rating 6.5

q=4	COV = 40
q=3	COV = 30, 25
q=2	COV = 45, 20
q=1	COV = 30, 15

Max COV = 35  
Avg. 100 - 40 COV  
PCI 100 - 25 = 65  
Rating: Good



Asphalt

D 5340 - 04<sup>st</sup>




FIG. X4.16 Corrected DVs for Jointed Rigid Airfield Pavements

X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

AIRFIELD ASPHALT PAVEMENT CONDITION SURVEY DATA SHEET FOR SAMPLE UNIT					SKETCH:	
BRANCH _____		SECTION _____		SAMPLE UNIT _____		
SURVEYED BY _____		DATE _____		SAMPLE AREA _____		
1. Alligator Cracking		5. Depression		9. Oil Spillage		
2. Bleeding		6. Jet Blast		10. Patching		
3. Block Cracking		7. Jt. Reflection (PCC)		11. Polished Aggregate		
4. Corrugation		8. Long. & Trans. Cracking		12. Raveling/Weathering		
				13. Rutting		
				14. Shoving from PCC		
				15. Slippage Cracking		
				16. Swell		

DISTRESS SEVERITY	QUANTITY					TOTAL	DENSITY %	DEDUCT VALUE
10						10.00		
7A	450		120			570	5.3	46
11	30					30.0	0.7	1
12	28125	200				28000	2.3	7
10L	340	64	56			360	7.4	7
12	25	150	140	400		755	7.1	38
10L	15	32				47	0.4	2
12	250					250	2.7	9
								100

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

PCJ-10-74-26-100  
25-40-100

CDV  
9(1) 46 38 24 15 7 7 7 - 18  
16 14 12 10 9 7 5 - 12  
13 11 10 8 7 5 5 - 10  
14 12 10 8 7 5 5 - 10  
15 11 10 8 7 5 5 - 10  
16 12 10 8 7 5 5 - 10  
17 13 11 9 8 7 6 - 11  
18 14 12 10 9 8 7 - 12  
19 15 13 11 10 9 8 - 13  
20 16 14 12 11 10 9 - 14  
21 17 15 13 12 11 10 - 15  
22 18 16 14 13 12 11 - 16  
23 19 17 15 14 13 12 - 17  
24 20 18 16 15 14 13 - 18  
25 21 19 17 16 15 14 - 19  
26 22 20 18 17 16 15 - 20  
27 23 21 19 18 17 16 - 21  
28 24 22 20 19 18 17 - 22  
29 25 23 21 20 19 18 - 23  
30 26 24 22 21 20 19 - 24  
31 27 25 23 22 21 20 - 25  
32 28 26 24 23 22 21 - 26  
33 29 27 25 24 23 22 - 27  
34 30 28 26 25 24 23 - 28  
35 31 29 27 26 25 24 - 29  
36 32 30 28 27 26 25 - 30  
37 33 31 29 28 27 26 - 31  
38 34 32 30 29 28 27 - 32  
39 35 33 31 30 29 28 - 33  
40 36 34 32 31 30 29 - 34  
41 37 35 33 32 31 30 - 35  
42 38 36 34 33 32 31 - 36  
43 39 37 35 34 33 32 - 37  
44 40 38 36 35 34 33 - 38  
45 41 39 37 36 35 34 - 39  
46 42 40 38 37 36 35 - 40  
47 43 41 39 38 37 36 - 41  
48 44 42 40 39 38 37 - 42  
49 45 43 41 40 39 38 - 43  
50 46 44 42 41 40 39 - 44  
51 47 45 43 42 41 40 - 45  
52 48 46 44 43 42 41 - 46  
53 49 47 45 44 43 42 - 47  
54 50 48 46 45 44 43 - 48  
55 51 49 47 46 45 44 - 49  
56 52 50 48 47 46 45 - 50  
57 53 51 49 48 47 46 - 51  
58 54 52 50 49 48 47 - 52  
59 55 53 51 50 49 48 - 53  
60 56 54 52 51 50 49 - 54  
61 57 55 53 52 51 50 - 55  
62 58 56 54 53 52 51 - 56  
63 59 57 55 54 53 52 - 57  
64 60 58 56 55 54 53 - 58  
65 61 59 57 56 55 54 - 59  
66 62 60 58 57 56 55 - 60  
67 63 61 59 58 57 56 - 61  
68 64 62 60 59 58 57 - 62  
69 65 63 61 60 59 58 - 63  
70 66 64 62 61 60 59 - 64  
71 67 65 63 62 61 60 - 65  
72 68 66 64 63 62 61 - 66  
73 69 67 65 64 63 62 - 67  
74 70 68 66 65 64 63 - 68  
75 71 69 67 66 65 64 - 69  
76 72 70 68 67 66 65 - 70  
77 73 71 69 68 67 66 - 71  
78 74 72 70 69 68 67 - 72  
79 75 73 71 70 69 68 - 73  
80 76 74 72 71 70 69 - 74  
81 77 75 73 72 71 70 - 75  
82 78 76 74 73 72 71 - 76  
83 79 77 75 74 73 72 - 77  
84 80 78 76 75 74 73 - 78  
85 81 79 77 76 75 74 - 79  
86 82 80 78 77 76 75 - 80  
87 83 81 79 78 77 76 - 81  
88 84 82 80 79 78 77 - 82  
89 85 83 81 80 79 78 - 83  
90 86 84 82 81 80 79 - 84  
91 87 85 83 82 81 80 - 85  
92 88 86 84 83 82 81 - 86  
93 89 87 85 84 83 82 - 87  
94 90 88 86 85 84 83 - 88  
95 91 89 87 86 85 84 - 89  
96 92 90 88 87 86 85 - 90  
97 93 91 89 88 87 86 - 91  
98 94 92 90 89 88 87 - 92  
99 95 93 91 90 89 88 - 93  
100 96 94 92 91 90 89 - 94






FIG. X4.16 Corrected DVs for Jointed Rigid Airfield Pavements

## X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit

Extra Care Constructed w/ intentional depression to direct drainage from window well

$g=1$  44:  $\frac{50}{50}$

AK-1050-10-50-10-50

2-5



15 Section of ~~\_\_\_\_\_~~  
Wallace

4510 D 5340 - 04<sup>ci</sup>




FIG. X4.16 Corrected DVs for Jointed Rigid Airfield Pavements

## X5. BLANK FORMS

X5.1 See Figs. X5.1 and X5.2.

[illegible]

FIG. X5.1 Flexible Pavement Condition Survey Data Sheet for Sample Unit



AIRFIELD CONCRETE PAVEMENTS				
CONDITION SURVEY DATA SHEET FOR SAMPLE UNIT				
BRANCH	SECTION	DATE		SAMPLE UNIT
SURVEYED BY		DATE		SAMPLE AREA
<div style="display: flex; justify-content: space-between;"> <div> <p><b>DEFECTS INDEX</b></p> <p>1. Blow up 2. Cracks 3. Longitudinal 4. Transverse 5. Spalling 6. Surface 7. Potholes 8. Potholes</p> </div> <div> <p>9. Potholes 10. Surface 11. Surface 12. Surface 13. Surface 14. Surface 15. Surface 16. Surface 17. Surface</p> </div> </div>				
DEF	DEF	NO.	DEFECT	SCORE
1	1	1	1	1
2	2	2	2	2
3	3	3	3	3
4	4	4	4	4
5	5	5	5	5
6	6	6	6	6
7	7	7	7	7
8	8	8	8	8
9	9	9	9	9
10	10	10	10	10
11	11	11	11	11
12	12	12	12	12
13	13	13	13	13
14	14	14	14	14
15	15	15	15	15
16	16	16	16	16
17	17	17	17	17

4' x 170'  
Concrete Paved  
Section Along  
Backside (South)  
of Heels.  
Estimate 5 10 Slabs.

FIG. K5.2 Jointed Rigid Pavement Condition Survey Data Sheet for Sample Unit

# REFERENCES

- (1) Shuhin, M. Y., Durr, M. L., and Kohn, S. D., "Development of a Pavement Maintenance Management System, Vol. I, II, V," *Airfield Pavement Condition Rating*, US Air Force Civil Engineering Center, 1976.
- (2) Kohn, S. D., and Shuhin, M. Y., "Evolution of the Pavement Condition Index for Use on Porous Friction Surfaces," *Technical Report No. M-151*, US Army Construction Engineering Research Laboratory, Champaign, IL, 1984.
- (3) Air Force Regulation 93-3, *Airfield Pavement Evaluation Program*, Department of the Air Force, Headquarters US Air Force, Washington, D.C.
- (4) Advisory Circular No. 150/5380-6, *Guidelines and Procedures for Maintenance of Airport Pavements*, Federal Aviation Administration, US Department of Transportation.
- (5) U.S. Naval Facilities Engineering Command Military Handbook 1021/2, "General Concepts for Airfield Pavement Design," 1988.
- (6) *Pavement Condition Index (PCI) Field Manuals for Asphalt Surfaced Airfields*, American Public Works Association.
- (7) *Pavement Condition Index (PCI) Field Manuals for Concrete Surfaced Airfields*, American Public Works Association.
- (8) Green, W. H., and Schroe, R. A., "Airport Pavement Inspection by PCI," 2nd edition, Eckrose/Green Associates, Madison, WI, 1988.

Total

$$17 \times 1 \rightarrow CDV = 20$$

PCI = 80 = Very Good



















49 D 5340 - 04<sup>61</sup>

FIG. X5.2 Jointed Rigid Pavement Condition Survey Data Sheet for Sample Unit

- (1) Shahin, M. Y., Darter, M. I., and Kohn, S. D., "Development of a Pavement Maintenance Management System, Vol. I, II, V," *Airfield Pavements Condition Rating*, US Air Force Civil Engineering Center, 1976.
- (2) Kohn, S. D., and Shahin, M. Y., "Evolution of the Pavement Condition Index for Use on Porous Friction Surfaces," *Technical Report No. M-351*, US Army Construction Engineering Research Laboratory, Champaign, IL, 1984.
- (3) Air Force Regulation 93-5, *Airfield Pavement Evaluation Program*, Department of the Air Force, Headquarters US Air Force, Washington, D.C.

- (4) Advisory Circular No. 150/5380-6, *Guidelines and Procedures for Maintenance of Airport Pavements*, Federal Aviation Administration, US Department of Transportation.
- (5) U.S. Naval Facilities Engineering Command Military Handbook 1021/2, "General Concepts for Airfield Pavement Design," 1988.
- (6) *Pavement Condition Index (PCI) Field Manuals for Asphalt Surfaced Airfields*, American Public Works Association.
- (7) *Pavement Condition Index (PCI) Field Manuals for Concrete Surfaced Airfields*, American Public Works Association.
- (8) Green, W. H., and Eckroze, R. A., "Airport Pavement Inspection by PCI," 2nd edition, Eckroze/Green Associates, Madison, WI, 1988.

X Continued across to sheet: Partridge Lake: 95 5 miles  
 Littlemouth to NW end of Partridge - NW of Littlemouth across to Lake, 6.5 miles - K. M. B. 1917



[illegible]

FIG. X6.2 Jointed Rigid Pavement Condition Survey Data Sheet for Sample Unit

## REFERENCES

- (1) Shahin, M. Y., Darter, M. L., and Kohn, S. D., "Development of a Pavement Maintenance Management System, Vol. 1, II, V," *Airfield Pavement Condition Rating*, US Air Force Civil Engineering Center, 1976.
- (2) Kohn, S. D., and Shahin, M. Y., "Evolution of the Pavement Condition Index for Use on Porous Friction Surfaces," *Technical Report No. M-351*, US Army Construction Engineering Research Laboratory, Champaign, IL, 1984.
- (3) Air Force Regulation 93-5, *Airfield Pavements Evaluation Program*, Department of the Air Force, Headquarters US Air Force, Washington, D.C. *Y. H. Shahin*
- (4) Advisory Circular No. 150/5380-6, *Guidelines and Procedures for Maintenance of Airport Pavements*, Federal Aviation Administration, US Department of Transportation.
- (5) U.S. Naval Facilities Engineering Command Military Handbook 1021/2, "General Concepts for Airfield Pavement Design," 1988.
- (6) *Pavement Condition Index (PCI) Field Manuals for Asphalt Surfaced Airfields*, American Public Works Association.
- (7) *Pavement Condition Index (PCI) Field Manuals for Concrete Surfaced Airfields*, American Public Works Association.
- (8) Green, W. H., and Eckrope, R. A., "Airport Pavement Inspection by PCI," 2nd edition, Belcoro/Green Associates, Madison, WI, 1988.

D.C. ~~X~~ See Set of Wallace  
Cont: ~~X~~ Cont. Lapine N 75° side of Cont. Hill. PSI = 100 Excellent  
~~X~~ Cont: 145° N of Cont. 2 entrance gyps PSI = 50 Fair  
~~X~~ N side of gyps 20000 PSI 70 Excellent  
~~X~~ Gyps Cont. 20000 PSI 70 Good  
~~X~~ NW Cont. Lapine 20000 PSI 10 Very Poor  
~~X~~ Cont: 0100 to 0200 PSI 94 Fair



Cent: low Cent less than 2 1/2 by 2 1/2 in of  
 St. 200 of 1000 - Grand Max (100)

W side of wallace

Cent Radius of W side of Center: 100 (1000 ±) 100

Cent from the top 100 - 100 of center line

Assume 25 sections - 10 sections - 10 sections - 10 sections

Shilling level 115 = 5 sections 83% OV COV

10m = 5 83% 50 50

90 = 50

PCI = 100 - 50 = 50 Fair

Cent N side of Green 2 Olive: 1000 PCI 90

Cent: SW Radius of Olive 1000 OV 20 COV

\* PCI = 100 - 30 = 70 Good

Cent NW Radius of Olive - PCI = 100 - 82 = 18 Very Poor

10H

Olive to Backcast assume 12 sections

	Distance	OV	COV
10L 2	67	15	
10m 2	17	20	
10H 3	25	40	
		81	

90 46 20 15 81 50

21 46 20 5 71 46

10 46 5 5 56 56

PCI = 100 - 53 = 47 Fair







# Concrete

D 5340 - 04<sup>01</sup>

**AIRFIELD CONCRETE PAVEMENTS**  
**CONDITION SURVEY DATA SHEET FOR SAMPLE UNIT**

BRANCH: \_\_\_\_\_ SECTION: \_\_\_\_\_ SAMPLE UNIT: \_\_\_\_\_  
 SURVEYED BY: \_\_\_\_\_ DATE: \_\_\_\_\_ SAMPLE AREA: \_\_\_\_\_

DAMAGE TYPES					SKETCH:
1. Blow Up	8. Pothole				
2. Corner Break	9. Spalling				
3. Longitudinal Grooving	10. Rutting				
4. Transverse Grooving	11. Surface Cracks				
5. Joint Seal Damage	12. Shrinkage				
6. Patching, & R	13. Surface Discoloration				
7. Patching/Sealing Cut	14. Surface Erosion				
8. Pothole	15. Surface Damage				
9. Spalling	16. Surface Damage				
10. Rutting	17. Surface Damage				
11. Surface Cracks	18. Surface Damage				
12. Shrinkage	19. Surface Damage				
13. Surface Discoloration	20. Surface Damage				
14. Surface Erosion	21. Surface Damage				
15. Surface Damage	22. Surface Damage				

FIG. X5.2 Jointed Rigid Pavement Condition Survey Data Sheet for Sample Unit

## REFERENCES

- (1) Shuhin, M. Y., Darter, M. L., and Kohn, S. D., "Development of a Pavement Maintenance Management System, Vol. 1, II, V," *Airfield Pavement Condition Rating*, US Air Force Civil Engineering Center, 1975.
- (2) Kohn, S. D., and Shuhin, M. Y., "Evolution of the Pavement Condition Index for Use on Porous Friction Surfaces," *Technical Report No. M-351*, US Army Construction Engineering Research Laboratory, Champaign, IL, 1984.
- (3) Air Force Regulation 93-5, *Airfield Pavement Evaluation Program*, Department of the Air Force, Headquarters US Air Force, Washington, D.C.
- (4) Advisory Circular No. 150/5380-6, *Guidelines and Procedures for Maintenance of Airport Pavements*, Federal Aviation Administration, US Department of Transportation.
- (5) U.S. Naval Facilities Engineering Command Military Handbook 102.1/2, "General Concepts for Airfield Pavement Design," 1988.
- (6) *Pavement Condition Index (PCI) Field Manuals for Asphalt Surfaced Airfields*, American Public Works Association.
- (7) *Pavement Condition Index (PCI) Field Manuals for Concrete Surfaced Airfields*, American Public Works Association.
- (8) Green, W. H., and Eckrode, R. A., "Airport Pavement Inspection by PCI," 2nd edition, Eckrode/Green Associates, Madison, WI, 1988.

Side walk - W side - 17<sup>th</sup> 22 section of walk - N of Olive PCI: 55 Fair  
 Section 23-38  
 Section 39-49  
 Section 49-55  
 Section 56-67

157 section  
 PCI: 95 Excellent  
 PCI: 0 Failed  
 PCI: 100 Excellent  
 PCI: 66 Good



Olive to blackish

3L	111	3L	111	10.2	13
102	11	102	11	8	
7m	1	72	1	4.5	6
7L	1	10m	2	9.1	25

in 2nd 100 200 Indirect Section in 2nd, N from Olive  
Olive to blackish

3L	111	3L	111	10.2	13	OV	CBV
102	11	102	11	8		52	25
7m	1	72	1	4.5	6	51	34
7L	1	10m	2	9.1	25	48	25

✓ 100-23-34 over 2nd

7L 1 Density: 6.70% OV

~~PCF = 100 - 5 = 95~~ ~~F = 100~~

✓ 309-44  
Fossiliferous 2: 35' N Highly determined  
Fossiliferous 4: 10H Fossiliferous 0-10

~~PCF = 100~~

✓ 100-107 Gullies

~~41-50-5~~ ~~100-107~~

0% 0.0%

~~PCF = 100~~ ~~F = 100~~

26-100

127878

3L	111	3L	111	10.2	13	OV	CBV
102	11	102	11	8		52	25
7m	1	72	1	4.5	6	51	34
7L	1	10m	2	9.1	25	48	25

PCF = 100 - 34 = 66 Good



49 D 5340 - 04<sup>e1</sup>

FIG. X5.2 Jointed Rigid Pavement Condition Survey Data Sheet for Sample Unit

- (1) Shahin, M. Y., Darter, M. L., and Kohn, S. D., "Development of a Pavement Maintenance Management System, Vol. 1, II, V," *Airfield Pavement Condition Rating*, US Air Force Civil Engineering Center, 1976.
- (2) Kohn, S. D., and Shahin, M. Y., "Evolution of the Pavement Condition Index for Use on Porous Friction Surfaces," *Technical Report No. M-351*, US Army Construction Engineering Research Laboratory, Champaign, IL, 1986.
- (3) Air Force Regulation 93-5, *Airfield Pavement Evaluation Program*, Department of the Air Force, Headquarters US Air Force, Washington, D.C.
- (4) Advisory Circular No. 150/5380-6, *Guidelines and Procedures for Maintenance of Airport Pavements*, Federal Aviation Administration, US Department of Transportation.
- (5) U.S. Naval Facilities Engineering Command Military Handbook 1021/2, "General Concepts for Airfield Pavement Design," 1982.
- (6) *Pavement Condition Index (PCI) Field Manuals for Asphalt Surfaced Airfields*, American Public Works Association.
- (7) *Pavement Condition Index (PCI) Field Manuals for Concrete Surfaced Airfields*, American Public Works Association.
- (8) Green, W. H., and Eckroze, R. A., "Airport Pavement Inspection by PCI," 2nd edition, Eckroze/Green Associates, Madison, WI, 1985.

Asphalt: 2 questions; N of Lakeland to SE corner of Hwy 65 West  
PCI = 70 Good

Walk to E end of Heeb  $\checkmark$  Pct: 32 Post

Walt. N of Merri. NE corner of E. corner of section R2 = 42 Fair



2nd Section

~~W. end of 1st Alley (S. of Heck)~~

		Drain	OV	COV
10L	100	6.6	14	
3L	11H	17.2	13	
		9.7	14	15
		9.1	14	5
			19	22

2nd Total Section

~~PCI = 100 - 30 - 70 = 0~~

Schalt. E. end of Heck - Market (11.8' x 65')  
 (Column 3-20 sections)

		Drain	OV	COV
7L	1	333	15	
11H	1	333	20	
3M	3	100	<del>57</del>	
3L	3	100	22	
			110	

					OV	COV
904	57	22	20	15	110	54
(7)	57	22	20	5	100	56
(2)	53	22	5	5	85	58
(1)	53	5	5	5	68	68

~~PCI = 100 - 68 = 32~~

W. end of Heck to Entrance

(Column 1 section)

		Drain	OV	COV
3L	1	100	58	58

PCI = 100 - 58 = 42

E. end of Entrance to E. main - New Entrance  
 PCI 100



772035

30 North Street

Center Street (15' S. of Center 2nd & 3rd of Block)

15'  
25'  
32'

376' of AC Pavement X 35' wide

S. Side Obv 2 S. End of Section

25'  
15'  
27'  
92'

361' of AC Pavement X 35' wide

S. End of Sect. East to S. End of E. Main

35'  
143'  
16'  
60'  
24'  
21'

337' of AC Pavement



North (Sund)  
Cord - 10

Side wall W side of Center to Olive  
5' wide x 5' (50 Sections) Very good

3 in. wall  
at

Entrance Apron - 5 section S & S


4" x 5" Slot for 3" sand at Entrance Apron  
Edge count 1" Long - 1" wide  
6" Long with Ends

Entrance Apron

7' 6" x 10' long (2) S. Side at

N Side - Median Pav. Transverse Curb 7' Long

Entrance Apron



145

W side

Side wall from Entrance Apron to Olive

(29) Section S & S

Section 1 - Just W of Entrance apron - Very good

# 2 4' - 5' Cant Med.

3, 4, 5 Exposed (Polished) Med

Slab 5 to 6 E of 6, Slab 6 is 7/4" x 1" Higher

NO. 6 + 14 Very Good

NO 14 to 15 7/4" 15 14 Slab 15 is 7/4" x 1" Higher

NO. 16 Very Good

NO. 16 ± 17 - NO. 16 7/4" Higher


NO. 17 - 29 - Older Side wall but good condition

Remove 330' of side wall 5' x 5' section (60 sections)



West end Sidwell Olive to Balch

✓ Sect 1 4' x 6' 8" long Exposed. Partially High, Transverse Crack 4"



✓ Sect 2 Exposed Ar,

✓ No. 3 Long Crack 5'



✓ No. 4 5'

✓ No. 5 "

No. 5-18 Older but good condition

No. 19-117 Under


Partial



Good.

No. 20/21

~~No. 22~~



High Dev.

No. 22 Low severity partial

✓ No. 23-38 Very Good (25) - 100%

From Sect 20 to (34-10) 107 wallace

Sidwell totally deteriorated - High severity

No. 24 to End Sidwell

From 107 wallace Sect. 4' wide x 5'

39-45 Very Good

✓ 46, 47, 48 Older but good - low severity

✓ 49 5' Long Crack Low to mid

✓ No. 50 Transverse long Crack 4' Transverse, 1' Long

✓ 51, 52, 53 Older but good - low

54 Very Good

✓ 55, 56, 57 Older but good Low



W Side Ref-cock to E. Main


Side walk - Robert White Alley S. of Hatch - S.S. Section

- ✓ No. 1, 2 older East Gate
- 3, 4, 6 - very good 5' x 5'
- ✓ #7 3' x 5' older East gate low
- ✓ #8 older East gate 5' x 5'
- ✓ #9, 10, 11 older Exposure Polished Agg - NOT deformed
- ✓ #12 Low Corrosion East Terrace 5' Crack
- ✓ #13, 14, 15 Same - NO Cracks - Low
- ✓ #16-20 Older but good condition

Side walk at Entrance I Garage 7' section S.S.

- ✓ No. 21  3' Crack
- ✓ No. 22  3' Crack
- ✓ No. 23  5' Crack
- ✓ No. 24  2' Crack
- ✓ No. 25 OK
- ✓ No. 26 OK

Entrance App at same location - to Garage  
5' x 26' - 7"



- ✓ Section Side walk @ ally - 15' - 0" wide - Exposure Agg - NOT low or deformed
- ✗ Entrance gate @ ally 5' x 15' Exposure Agg. NOT deformed - 2" - 3" Crack 5' long at center of slab med. severity
- Side walk @ E. end of Hatch 11' - 4" wide x 60' long



Loch Cracks about 1" wide med. severity

46.80  
2910.02

med  
side  
walk 2'  
24.75



512 S. Wallace Ave

W. cut base of ... ..

X ... .. Photo ... 6' ...  
... ..  
... .. Photo ... 5' ...

... ..  
... .. addition 5' ...  
... ..  
... ..  
... ..

... ..  
... ..  
... ..  
... ..  
... ..  
... ..  
... ..

W. cut ... ..  
... ..  
... ..  
... ..  
... ..  
... ..

... ..  
... ..  
... ..  
... ..  
... ..







## **APPENDIX E**

### **Test Pit Excavation Logs**





JOB NO: 1157720035.200 PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/NS      TEST PIT NO.: Heebs TP-4

DESCRIPTIVE LOCATION: Approximately 80' from sidewalk, 15' from Heebs (LAT 45.6788514489° N, LON -111.029041031° E)

DATE STARTED: 12-20-07      DATE COMPLETED: 12-20-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 3'

REMARKS: Approximately 0-1.5' depth visible ore. North side sample location.

---

Excavation collected using wet methods

0081 Picture JPG

[illegible]





**TETRA TECH**

JOB NO: 1157720035

PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/NS      TEST PIT NO.: Heebs TP-1

DESCRIPTIVE LOCATION: SW corner of Heeb's building/NE corner (LAT 45.678866822° N, LON -111.028693326° E)

DATE STARTED: 12-20-07      DATE COMPLETED: 12-20-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 3.0'

REMARKS: Start 0900, sample collected 0930

Visible ore present

0079.jpg

[illegible]





**TETRA TECH**

PROJECT NAME: CMC Bozeman Facility

STATE: MT COUNTY: Gallatin LOGGED BY: KC/NS TEST PIT NO.: Heebs TP-2

DESCRIPTIVE LOCATION: 15' from South of Heebs building, approximately 45 feet from sidewalk crossing alley  
(LAT 45.6788373286° N, LON -111.02884293° E)

DATE STARTED: 12-20-07 DATE COMPLETED: 12-20-07 EXCAVATION COMPANY ACM

TOTAL DEPTH 3.0'

REMARKS: Start 1020. End of 1120 for dig. South side wall samples collected. No visible ore present throughout test pit. Test pit at beyond edge of gravel alleyway along the south side. 0080. JPG

[illegible]





## FIELD LOG OF EXPLORATION TEST PIT

JOB NO: 1157720035.200 PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/NS      TEST PIT NO.: Heebs TP-3

DESCRIPTIVE LOCATION: Approximately 60' from east sidewalk crossing alley (near Gas Main) and 3' from South side of Heebbs building (LAT 45.6788693656° N, LON -111.028928438° E)

DATE STARTED:	12-20-07	DATE COMPLETED:	12-20-07	EXCAVATION COMPANY	ACM
---------------	----------	-----------------	----------	--------------------	-----

TOTAL DEPTH 3.0'

REMARKS: Approximately 0 – 1.5' depth visible ore present. North side of test pit in alley way for sample collection  
0080.jpg

[illegible]





JOB NO: 1157720035.200 PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/NS      TEST PIT NO.: Heebs TP-5

DESCRIPTIVE LOCATION: Approximately 100' from side walk, 3' from Heebs South building  
(LAT 45.6788757327°N, LON-111.029192528° E)

DATE STARTED: 12-29-07      DATE COMPLETED: 12-29-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 3'

REMARKS:	0-1.5' depth visible ore.
	North side wall sample location.
	Collected using wet methods
	0082 Picture JPG

[illegible]





## FIELD LOG OF EXPLORATION TEST PIT

JOB NO: 1157720035 PROJECT NAME: CMC Bozeman Facility

STATE: MT COUNTY: Gallatin LOGGED BY: KC/NS TEST PIT NO.: SHB TP-1

DESCRIPTIVE LOCATION: SHB North Test Pit against NHB north dock wall (LAT 45.6770607°N, LON -111.02806788°E)

DATE STARTED: 12-19-07 DATE COMPLETED: 12-19-07 EXCAVATION COMPANY: ACM

TOTAL DEPTH 4'

REMARKS: 1000 – start, 1005 called/left message with Susan Swimley and Tim Cooper.  
\* Small hole made in building from contractor  
\* done at 11:10 , put surface asbestos ore in the hole and buried  
0084 Picture JPG

Depth (feet)	Classification and Description	Sample Depth (ft)	Headspace (ppm)
0 - .5	Poorly graded medium brown sand with gravels and cobble up to approximately 7"		
.5 – 1	Poorly graded medium brown sand with gravels and cobble up to approximately 7" with visible asbestos ore		
1 – 1.5	Poorly graded medium brown sand with gravels and cobble up to approximately 7" with visible asbestos ore		
1.5 – 2	Poorly graded medium brown sand with gravels and cobble up to approximately 7" with visible asbestos ore		
2 – 2.5	Poorly graded medium brown sand with gravels and cobble up to approximately 7" with visible asbestos ore		
2.5 – 3	Poorly graded medium brown sand with gravels and cobble up to approximately 7" with visible asbestos ore		
3.0 – 3.5	Poorly graded medium brown sand with gravels and cobble up to approximately 7" with visible asbestos ore		
3.5 – 4.0	Dark brown clayey silts (looks native) no/very little gravels		
	Dark brown clayey silts no/very little gravels (Base)	4.0	





## FIELD LOG OF EXPLORATION TEST PIT

JOB NO: 1157720035 PROJECT NAME: CMC Bozeman Facility

STATE: MT COUNTY: Gallatin LOGGED BY: KC/NS TEST PIT NO.: SHB TP-2

DESCRIPTIVE LOCATION: 20' South of SHB-TP1 (LAT 45.6769772981°N, LON -111.028038404°E)

DATE STARTED: 12-19-07 DATE COMPLETED: 12-19-07 EXCAVATION COMPANY: ACM

TOTAL DEPTH: \_\_\_\_\_

REMARKS: 11:15 1140 start testpit/backfilled  
visible evidence of asbestos ore in excavation  
Soil wet during excavation  
0074 Picture JPG

Depth (feet)	Classification and Description	Sample Depth (ft)	Headspace (ppm)
0 - .5	South side wall, 12" minus with sandy soil poorly graded sand with gravels non-native fill		
0.5 - 1	South side wall, 12" minus with sandy soil poorly graded sand with gravels non-native fill		
1 - 1.5	South side wall, 12" minus with sandy soil poorly graded sand with gravels non-native fill		
1.5 - 2.0	South side wall, 12" minus with sandy soil poorly graded sand with gravels non-native fill		
2.0 - 2.5	South side wall, 12" minus with sandy soil poorly graded sand with gravels non-native fill		
2.5 - 3.0	South side wall, 12" minus with sandy soil poorly graded sand with gravels non-native fill		
	Dark brown clayey silt (Base)	4	
	Composite	1 - 3	
	Duplicate of Composite	1 - 3	





**TETRA TECH**

JOB NO: 1157720035.200

PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/NS      TEST PIT NO.: SHB TP-3

DESCRIPTIVE LOCATION: Approximately 40' South from NHB East dock (LAT 45.6769331529°N, LON -111.02804898°E)

DATE STARTED: 12-19-07      DATE COMPLETED: 12-19-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 2.5'

REMARKS: Started 1315 Finished Excavation with Backfill 1345

### Wet Methods used during excavation

visible asbestos ore present 0-2.5'

0076 Picture JPG

[illegible]





**TETRA TECH**

JOB NO: 1157720035

PROJECT NAME: CMC Bozeman Facility

STATE: MT COUNTY: Gallatin LOGGED BY: KC/NS TEST PIT NO.: SHB – TP-4

DESCRIPTIVE LOCATION: 60' from South side of East NHB dock (towards City of Bozeman Library)  
(LAT 45.6769370071°N, LON -111.028059846°E)

DATE STARTED: 12-19-07      DATE COMPLETED: 12-19-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 4'

REMARKS: Start 1400, stop 1430 (backfill)  
South side wall samples  
0075 .jpg

[illegible]





JOB NO: 1157720035.200 PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/NS      TEST PIT NO.: SHB TP-5

DESCRIPTIVE LOCATION: 80' South of East NHB Dock (LAT 45.6768204384°N, LON -111.028062503°E)

DATE STARTED: 12-19-07      DATE COMPLETED: 12-19-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 2.5"

REMARKS: Start 1445, stop 1520 (backfill)

Asbestos ore noted in test pit debris pile and at top of concrete footing of building

.0077.JPG

[illegible]





JOB NO: 1157720035 PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/NS      TEST PIT NO.: SHB TP-6

DESCRIPTIVE LOCATION: SHB SE corner of building (LAT 45.6767885903°N, LON -111.02805648°E)

DATE STARTED: 12-19-07      DATE COMPLETED: 12-19-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 2.5"

REMARKS: Start 1530, stop 1600  
East side wall only 1' into boundary area visible ore present.

0078 Photo.JPG

[illegible]





**TETRA TECH**

JOB NO: 1157720035

PROJECT NAME: CMC Bozeman Facility

STATE: MT COUNTY: Gallatin LOGGED BY: KC/RWE TEST PIT NO.: Story TP-1

DESCRIPTIVE LOCATION: Approximately 15' south of SE SHB building corner (LAT 45.6767530036°N, LON -111.028076108°E)

DATE STARTED: 12-28-07 DATE COMPLETED: 12-28-07 EXCAVATION COMPANY ACM

TOTAL DEPTH 4'

REMARKS: 1145 Start 1200 – backfilled at 1230

0084 Picture JPG

[illegible]





JOB NO: 1157720035.200 PROJECT NAME: CMC Bozeman Facility

DESCRIPTIVE LOCATION: 20' from SE corner of Harrington S. Building., 15' S of SHB Building  
(LAT 45.6767876614°N, LON -111.028156459°E)

TOTAL DEPTH 4'

REMARKS: 1225 – 1245, 1300 backfill  
Excavation conducted using wet methods  
0086 Picture JPG

[illegible]





**TETRA TECH**

JOB NO: 1157720035.200

PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/RWE      TEST PIT NO.: Story TP-3

DESCRIPTIVE LOCATION: Approximately 40' W of SE corner of SHB (LAT 45.6767421395°N, LON -111.02823382°E)

DATE STARTED: 12-28-07      DATE COMPLETED: 12-28-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 3'

REMARKS: Start excavation 1200, 1215 excavation finished 1250 backfill  
Wet methods used during excavation  
Visual asbestos ore 0 - 1.5'  
0085 Picture JPG

[illegible]





**TETRA TECH**

## FIELD LOG OF EXPLORATION TEST PIT

JOB NO: 1157720035.200

PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/RWE      TEST PIT NO.: Story TP-4

DESCRIPTIVE LOCATION: Near power pole on SW corner of SHB (LAT 45.6767887945°N, LON -111.028311668°E)

DATE STARTED: 12-28-07      DATE COMPLETED: 12-28-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 3'

REMARKS: Started 1315, 1345 Stop.

No visible asbestos ore

---

Excavation conducted using wet methods

0087 Picture JPG

[illegible]





**TETRA TECH**

JOB NO: 1157720035.200

PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/RWE      TEST PIT NO.: Story TP-5

DESCRIPTIVE LOCATION: SW corner of SHB 15' from S and 20' W (LAT 45.6767546677°N, LON -111.028383626°E)

DATE STARTED: 12-28-07      DATE COMPLETED: 12-28-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 3'

REMARKS: Started 1700, finished 1725 Backfilled at 1820

No visible asbestos ore

Collected using wet methods

0089 Picture JPG

[illegible]





JOB NO: 1157720035.200 PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/RWE      TEST PIT NO.: Story TP-6

DESCRIPTIVE LOCATION: 15' S, 40' W of SE corner of SHB (LAT 45.6767632555°N, LON -111.028466803°E)

DATE STARTED: 12-28-07      DATE COMPLETED: 12-28-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH      Excavation to 1.5'

REMARKS: Engineered Road Bed in same locale as previous test pit exploration and soil removal with encapsulation. Colleen Owen indicated to previous data from past excavations in area coupled with onsite reference of new asphalt indicates previous excavation in area of test pit.

0070 Picture JPG

[illegible]





**TETRA TECH**

JOB NO: 1157720035.200

PROJECT NAME: CMC Bozeman Facility

STATE: MT      COUNTY: Gallatin      LOGGED BY: KC/RWE      TEST PIT NO.: Story TP-7

DESCRIPTIVE LOCATION: 40' W of SW corner of SHB (LAT 45.6767977942°N, LON -111.028452715°E)

DATE STARTED: 12-28-07      DATE COMPLETED: 12-28-07      EXCAVATION COMPANY    ACM

TOTAL DEPTH 3'

REMARKS: Start 1330. Finish 1630. No visible ore. Hard to dig into ground in this location as it had been compacted and frozen previously. Backhoe bucket could not scrap through. Rented Jackhammer, then rented bobcat with hydraulic jackhammer attachment to penetrate soil. Provided continuous wetting of soil throughout excavation.

0088 Picture JPG

[illegible]



## **APPENDIX F**

### **Test Pit Photo Log with Location Descriptions and GPS coordinates**



**APPENDIX F: TEST PIT PHOTO LOG WITH LOCATION DESCRIPTIONS  
CMC BOZEMAN FACILITY – SI WORKPLAN  
CITY OF BOZEMAN**



**PHOTOGRAPH 1** SHB TP-1: Located in NE corner of SHB along NHB east dock area south wall



**PHOTOGRAPH 2** SHB TP-2: Located 20 feet south of SHB TP-1 directly against east footing wall of SHB



**PHOTOGRAPH 3** SHB TP-3: Located 40 feet south of SHB TP-1 directly against east footing wall of SHB



**PHOTOGRAPH 4** SHB TP-5: Located 80 feet south of SHB TP-1 directly against east footing wall of SHB



**PHOTOGRAPH 5** SHB TP-6: Located 95-100 feet south of SHB TP-1 in middle of soil berm next to SE SHB



**PHOTOGRAPH 6** HEEBs TP-1: Located 4' south of Heebs and 12-14' from east alley sidewalk (past asphalt)



**APPENDIX F: TEST PIT PHOTO LOG WITH LOCATION DESCRIPTIONS  
CMC BOZEMAN FACILITY – SI WORKPLAN  
CITY OF BOZEMAN**



**PHOTOGRAPH 7** HEEBs TP-2: Located 15' south of Heebs and 45' from east alley sidewalk



**PHOTOGRAPH 8** HEEBs TP-3: Located 4' south of Heebs and 75' from east alley sidewalk



**PHOTOGRAPH 9** HEEBs TP-4: Located 15' south of Heebs and 120' from east alley sidewalk near lightpole



**PHOTOGRAPH 10** HEEBs TP-5: Located 4' south of Heebs and 160' from east alley sidewalk



**PHOTOGRAPH 11** Story TP-1: Located 15' directly south of the SE corner of SHB



**PHOTOGRAPH 12** Story TP-2: Located 20' directly west of the SE corner of SHB and adjacent to SHB



**APPENDIX F: TEST PIT PHOTO LOG WITH LOCATION DESCRIPTIONS  
CMC BOZEMAN FACILITY – SI WORKPLAN  
CITY OF BOZEMAN**



**PHOTOGRAPH 13** Story TP-4: Located east of the light pole near the SW corner of the SHB and adjacent to SHB



**PHOTOGRAPH 14** Story TP-5: Located 20' to the west of the SW corner of the SHB and 15' to the south of SHB



**PHOTOGRAPH 15** Story TP-6: Located 40' to the west of the SW corner of the SHB (east of asphalt pavement) and 15' to the south of SHB



**PHOTOGRAPH 16** SHB TP-7: Located 40' to the west of the SW corner of the SHB (east of the asphalt pavement)



## **APPENDIX G**

### **Asbestos Waste Volume Calculations**





TETRATECH

CLIENT City of BozemanDATE 6/11/08JOB TITLE CMC Bozeman Facility - SI WorkPlan JOB NUMBER 115 7720035.200SUBJECT South Harrington Building Actual Asbestos BY 3/11 SHEET 1 of 2  
Ore noted in Test Pits w/ columnsWaste Volume (Asbestos Ore) Calculations -

\* Estimate of Asbestos Ore based on 12/19/07 Test Pit visual data

\* Assume: 100 ft length x 7 ft width of Test Pit

\* From Test Pit Log Data:

TP1 = 3.5 ft depth visual asbestos ore

TP2 = No visible asbestos ore detected in Test Pit

TP3 = 1.5 ft depth visual asbestos ore

TP4 = 3.25 ft depth visual asbestos ore

TP5 = 2 ft depth @ top of S&amp;B Footing

TP6 = 2.5 ft depth

TP1 to TP2

$$3.5 \text{ ft depth} \times 7 \text{ ft width} \times 20 \text{ ft length} \times \frac{1}{2} \text{ (due to -0- depth @ TP2)}$$

$$= \boxed{245 \text{ ft}^3}$$

TP2 to TP3

$$(-0- \text{ depth @ TP2}) \frac{1}{2} \times 1.5 \text{ ft depth TP3} \times 7 \text{ ft width} \times 20 \text{ ft length}$$

$$= \boxed{105 \text{ ft}^3}$$

TP3 to TP4

$$1.5 \text{ ft depth @ TP3} \times 7 \text{ ft width} \times 20 \text{ ft length} + (3.25 \text{ depth @ TP4} - 1.5 \text{ depth @ TP3})$$

$$\times 7 \text{ ft width} \times 20 \text{ ft length} \times .5 \text{ (due to -0- depth shown visible ore part 1.5 ft)}$$

$$= \boxed{332.5 \text{ ft}^3}$$

TP4 to TP5

$$3.25 \text{ ft depth @ TP4} \times 7 \text{ ft width} \times 20 \text{ ft length} + (2.0 - 3.25 \text{ depth @ TP5} - \text{depth @ TP4})$$

$$\times 7 \text{ ft width} \times 20 \text{ ft length} \times .5 \text{ (due to -0- depth shown visible ore part 2.0 ft)}$$

$$= \boxed{367.5 \text{ ft}^3}$$

TP5 to TP6

$$2.0 \text{ ft depth @ TP5} \times 7 \text{ ft width} \times 20 \text{ ft length} + (2.5 - 2.0 \text{ depth @ TP6} - \text{depth @ TP5})$$

$$\times 7 \text{ ft width} \times 20 \text{ ft length} \times .5 \text{ (due to -0- depth shown visible ore part 2.5 depth)}$$

$$= \boxed{315 \text{ ft}^3} \quad \text{total} = 1365 \text{ ft}^3 = \boxed{50.5 \text{ yd}^3}$$





TETRA TECH

CLIENT City of BezeanDATE 6/11/08JOB TITLE CMC Bezean Facility - SI Work PlanJOB NUMBER 1157720035.200SUBJECT SIB Theoretical Asbestos Ore noted inBY 3/SHEET 2 of 2

Test Pits w/ volumes

\* Estimate of Waste Volume Based on 12/19/07 Test Pit data using approximate 6 in over excavation.

\* i.e. TP-2, asbestos ore noted in excavation pit therefore assume until complete vertical depth

\* Assume: 100 ft length x 7 ft width

From Test Pit Log Data w/assumptions:

TP-1 = 4.0 ft depth

TP-2 = 3.0 ft depth

TP-3 = 2.0 ft depth

TP-4 = 4.0 ft depth

TP-5 = 2.5 ft depth

TP-6 = 3.0 ft depth

TP-1 to TP-2

$$4.0 \text{ ft depth @ TP-1} \times 7 \text{ ft width} \times 20 \text{ ft length} + (3.0 - 4.0 \text{ ft depth @ TP-2 - TP-1}) \times 7 \text{ ft} \times 20 \text{ ft} \\ \times .5 \text{ (due to } -0. \text{ depth shown past } 3.0 \text{ ft)} \\ = \boxed{490 \text{ ft}^3}$$

TP-2 to TP-3

$$3.0 \text{ ft depth @ TP-2} \times 7 \text{ ft width} \times 20 \text{ ft length} + (2.0 - 3.0 \text{ ft depth @ TP-3 - TP-2}) \times 7 \text{ ft} \times 20 \text{ ft} \\ \times .5 \text{ (due to } -0. \text{ depth shown past } 3.0 \text{ ft)} \\ = \boxed{350 \text{ ft}^3}$$

TP-3 to TP-4

$$2.0 \text{ ft depth @ TP-3} \times 7 \text{ ft width} \times 20 \text{ ft length} + (4.0 - 2.0 \text{ ft depth @ TP-4 - TP-3}) \times 7 \text{ ft} \times 20 \text{ ft} \\ \times .5 \text{ (due to } -0. \text{ depth shown past } 2.0 \text{ ft)} \\ = \boxed{420 \text{ ft}^3}$$

TP-4 to TP-5

$$4.0 \text{ ft depth @ TP-4} \times 7 \text{ ft width} \times 20 \text{ ft length} + (2.5 - 4.0 \text{ ft depth @ TP-5 - TP-4}) \times 7 \text{ ft} \times 20 \text{ ft} \\ \times .5 \text{ (due to } -0. \text{ depth shown past } 4.0 \text{ ft)} \\ = \boxed{455 \text{ ft}^3}$$

TP-5 to TP-6

$$2.5 \text{ ft depth @ TP-5} \times 7 \text{ ft width} \times 20 \text{ ft length} + (3.0 - 2.5 \text{ ft depth @ TP-6 - TP-5}) \times 7 \text{ ft} \times 20 \text{ ft} \\ \times .5 \text{ (due to } -0. \text{ depth shown past } 2.5 \text{ ft)} \\ = \boxed{385 \text{ ft}^3}$$

$$\text{Total} = 2,100 \text{ ft}^3$$

$$= \boxed{78 \text{ yd}^3}$$





TETRA TECH

CLIENT City of BozemanDATE 6/14/18JOB TITLE CNC Bozeman Facility - SE Work PlanJOB NUMBER 1157720055.200SUBJECT Heeb's Alley Actual Asbestos Ore Material inBY JLL SHEET 1 of 2

Test Pits

Waste Volume (Asbestos Ore) Calculations

- \* Estimate of asbestos ore based on 12/20/17 Test Pits visual data
- \* Assume 18 ft width of alley and 170 ft length of alley behind Heeb's structure minus 12 ft apron that is asphalt-paved on east side of alley
- \* Estimate based on vertical depth (horizontally) of 2.5 yds test pits

From Test Pit Log Data:

Heeb's TP-1 : 0-1.5 ft visible asbestos ore  
 Heeb's TP-2 : 0-0 ft visible asbestos ore  
 Heeb's TP-3 : 0-1.5 ft visible asbestos ore  
 Heeb's TP-4 : 0-1.5 ft visible asbestos ore  
 Heeb's TP-5 : 0-1.5 ft visible asbestos ore

TP-1 to TP-2

1.5 ft depth @ TP-1 x 18 ft width x (45 ft length from sidewalk - 12 ft apron) x .5 (due to 0-0 depth visible ore present post 0-0 depth @ TP-2)

$$= 607.5 \text{ ft}^3$$

TP-2 to TP-3

0 ft depth @ TP-2 x 18 ft width x (75 ft @ TP-3 - 45 ft @ TP-2) + (1.5 ft @ TP-3 - 0-0 ft @ TP-2) x 18 ft width x (75 ft - 45 ft (TP-3 - TP-2)) x .5 (due to 0-0 depth visible ore present 0-0 depth @ TP-2)

$$= 405 \text{ ft}^3$$

TP-3 to TP-4

1.5 ft @ TP-3, TP-4 x 18 ft width x (120 ft - 75 ft (TP-4 - TP-3))

$$= 1215 \text{ ft}^3$$

TP-4 to TP-5

1.5 ft @ TP-4, TP-5 x 18 ft width x (160 ft - 120 ft (TP-5 - TP-4))

$$= 1080 \text{ ft}^3$$

$$\text{Total} = 3307.5 \text{ ft}^3$$

$$= 122.5 \text{ yd}^3$$





TETRA TECH

CLIENT City of BozemanDATE 6/14/08JOB TITLE CMC Bozeman Facility - SI Work PlanJOB NUMBER 1157720035.200SUBJECT Heb's Alley Theoretical Asbestos OreBY 3/11SHEET 2 of 2

noted in Alley Bailed Heb's

- \* Estimate of Waste Volume Based on 12/19/07 Test Pit data using approximate 6 in over excavation
- \* For TP-2 asbestos ore noted in cracks of concrete driveway apron approx 2 ft south therefore assume that randomly T2 did not discover and/or see asbestos ore; however it shall be shown to be removed @ 6 in post interface @ 2'
- \* Due to asbestos ore in TP-1 @ interface of gravel/soil alley and east (12' asphalt (newly-paved) apron, assume asbestos ore present beneath.
- \* Due to asbestos ore in TP-5 @ ~160' from side walk (east alley), assume asbestos ore extends to entire 170' length of building using same visible Test Pit data

Therefore,

Assume 2' depth, 18' width, and 170' Length

Waste Volume =

$$2' \times 18' \times 170' \\ = 6,120 \text{ ft}^3 \approx \boxed{227 \text{ yd}^3}$$





TETRA TECH

CLIENT City of BozemanDATE 6/16/08JOB TITLE CML Bozeman Facility - SI Work PlanJOB NUMBER 1157726035.200SUBJECT Story Actual Asbestos Ore Noted inBY JLSHEET 1 of 2

Property →

Waste Volume (Asbestos Ore) Calculations

- \* Estimate of Asbestos Ore based on 10/25/07 Test Pits visual data
- \* Assume 15 ft width and 100 ft length test area south of SHB
- \* Estimate based on vertical depth (horizontally) run of 'zig-zag' test pits

From Test Pit Log Data

Story TP-1:	0 - 1.5 ft	visible asbestos ore
Story TP-2:	0 - 3.5 ft	visible asbestos ore
Story TP-3:	0 - 1.5 ft	visible asbestos ore
Story TP-4:	0 -	Asbestos ore noted
Story TP-5:	0 -	Asbestos ore noted
Story TP-6:	0 -	Asbestos ore noted
Story TP-7:	0 -	Asbestos ore noted

TP-1 to TP-2

$$1.5 \text{ ft depth @ TP-1} \times 15 \text{ ft width} \times 20 \text{ ft length} + (3.5 - 1.5 (\text{TP-2} - \text{TP-1})) \times 15 \text{ ft width} \times 20 \text{ ft length} \times .5 (\text{due to } 0 - \text{additional visible ore depth past } 1.5 \text{ ft @ TP-1})$$

$$= \boxed{750 \text{ ft}^3}$$

TP-2 to TP-3

$$3.5 \text{ ft depth @ TP-2} \times 15 \text{ ft width} \times 20 \text{ ft length} + (1.5 - 3.5 (\text{TP-3} - \text{TP-2})) \times 15 \text{ ft width} \times 20 \text{ ft length} \times .5 (\text{due to } 0 - \text{additional visible ore depth past } 1.5 \text{ ft @ TP-3})$$

$$= \boxed{750 \text{ ft}^3}$$

TP-3 to TP-4

$$1.5 \text{ ft depth @ TP-3} \times 15 \text{ ft width} \times 20 \text{ ft length} + (0 - 1.5 (\text{TP-4} - \text{TP-3})) \times 15 \text{ ft width} \times 20 \text{ ft length} \times .5 (\text{due to } 0 - \text{additional visible ore @ TP-4})$$

$$= \boxed{225 \text{ ft}^3}$$

total =  $1725 \text{ ft}^3 = \boxed{64 \text{ yd}^3}$





TETRATTECH

CLIENT City of BazemanDATE 6/16/08JOB TITLE CMC Bazeman Facility - ST Work PlanJOB NUMBER 1157720035 200SUBJECT Story Theoretical Asbestos Ore notedBY JKSHEET 2 of 2

on Property

\* Estimate of Waste Volume Based on 12/14/07 Test Pit data using  
6-inch over excavation

TP-1 to TP-2

$$2 \text{ ft depth @ TP-1} \times 15 \text{ ft width} \times 20 \text{ ft length} + (4.0 - 2.0 (\text{TP-2} - \text{TP-1})) \times 15 \text{ ft width} \\ \times 20 \text{ ft length} \times .5 \text{ (due to } -0- \text{ additional visible ore depth past } 20 \text{ ft @ TP-1)} \\ = \boxed{900 \text{ ft}^3}$$

TP-2 to TP-3

$$4.0 \text{ ft depth @ TP-2} \times 15 \text{ ft width} \times 20 \text{ ft length} + (2.0 - 4.0 (\text{TP-3} - \text{TP-2})) \times 15 \text{ ft width} \\ \times 20 \text{ ft length} \times .5 \text{ (due to } -0- \text{ additional visible ore depth past } 20 \text{ ft @ TP-3)} \\ = \boxed{900 \text{ ft}^3}$$

TP-3 to TP-4

$$2.0 \text{ ft depth @ TP-3} \times 15 \text{ ft width} \times 20 \text{ ft length} + (0 - 2.0 (\text{TP-4} - \text{TP-3})) \times 15 \text{ ft width} \\ \times 20 \text{ ft length} \times .5 \text{ (due to } -0- \text{ additional visible ore depth past } -0-) \\ = \boxed{300 \text{ ft}^3}$$

$$\text{total} = 2,100 \text{ ft}^3$$

$$= \boxed{78 \text{ yd}^3}$$



## **APPENDIX H**

### **Soil Sample Analytical Laboratory Results**



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: [westmontaslab@EMSL.com](mailto:westmontaslab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAXI56  
Customer PO:  
Received: 12/28/07 9:40 AM  
EMSL Order: 040731709

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: CMC BOZEMAN-1157720035.200

EMSL Proj:  
Analysis Date: 1/12/2008  
Report Date: 1/15/2008

**PLM Analysis of Bulk Samples for Asbestos via EPA 600/R-93/116 Method with CARB  
435 Prep (Milling) Level A for 0.25% Target Analytical Sensitivity**

Sample	Location	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
1-HEEBS-TP-1 040731709-0001		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
2-HEEBS-TP-2 040731709-0002		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
3-HEEBS-TP-2 040731709-0003		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
4-HEEBS-TP-3 040731709-0004		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
5-HEEBS-TP-3 040731709-0005		Black Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
6-HEEBS-TP-4 040731709-0006		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
7-HEEBS-TP-4 040731709-0007		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
8-HEEBS-TP-5 040731709-0008		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
9-HEEBS-TP-5 040731709-0009		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
10-SHB-TP-1 040731709-0010		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected

Analyst(s)

Delores Beard (18)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

This report relates only to the samples listed above and may not be reproduced except in full, without EMSL's written approval. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the federal government. EMSL is not responsible for sample collection activities or method limitations. The samples may contain asbestos fibers below the resolution limit of PLM. EMSL recommends that samples reported as none detected or less than the limit of detection undergo fibrous analysis via TEM. Samples received in good condition unless otherwise noted.



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: [westmontasplab@EMSL.com](mailto:westmontasplab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAXI56  
Customer PO:  
Received: 12/28/07 9:40 AM  
EMSL Order: 040731709

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: CMC BOZEMAN-1157720035.200

EMSL Proj:  
Analysis Date: 1/12/2008  
Report Date: 1/15/2008

**PLM Analysis of Bulk Samples for Asbestos via EPA 600/R-93/116 Method with CARB  
435 Prep (Milling) Level A for 0.25% Target Analytical Sensitivity**

Sample	Location	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
11-SHB-TP-2 040731709-0011		Black Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
12-SHB-TP-2 040731709-0012		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
13-SHB-TP-3 040731709-0013		Black Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
14-SHB-TP-4 040731709-0014		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
15-SHB-TP-4 040731709-0015		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
16-SHB-TP-5 040731709-0016		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
17-SHB-TP-5 040731709-0017		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
18-SHB-TP-6 040731709-0018		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected

Analyst(s)

Delores Beard (18)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

This report relates only to the samples listed above and may not be reproduced except in full, without EMSL's written approval. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the federal government. EMSL is not responsible for sample collection activities or method limitations. Some samples may contain asbestos fibers below the resolution limit of PLM. EMSL recommends that samples reported as none detected or less than the limit of detection undergo additional analysis via TEM. Samples received in good condition unless otherwise noted.



**EMSL Analytical, Inc.**


107 Haddon Avenue, Westmont, NJ 08108 Phone: 800-220-3675 Fax: 856-858-4960

Client: Tetra Tech/Maxim Technologies  
1601 2nd Avenue N. Suite 116  
Great Falls, MT 59401

EMSL Reference: 040800539

Attention: Kenh Cron  
Fax: email Phone: 781-251-0040  
Project: 1157720035.200 CMC BOZEMAN FACILITY - SIDate Received: 01/09/08  
Date Analyzed: 01/18/08  
Date Reported: 03/06/08**Asbestos Analysis of Soil Samples via Modified EPA 600/R-93/116 Method Utilizing  
Analytical Electron Microscopy (Section 2.5.5.2) with CARB 435 Prep (Milling)  
Level B for 0.1% Target Analytical Sensitivity**

Client Sample ID	Location	EMSL Sample ID	Asbestos Type(s)	# of Asbestos Structures Detected	Analytical Sensitivity %	Asbestos Weight %	Comments
19-STORY-TP-1	COMPOSITE 1.5' -4'	040800539-0001	None Detected	None Detected	0.1	<0.1	
20-STORY-TP-1	BASE 4' DEPTH	040800539-0002	None Detected	None Detected	0.1	<0.1	
21-STORY-TP-2	3.5' -4' DEPTH	040800539-0003	Chrysotile	1	0.1	<0.1	
22-STORY-TP-2	4' - DEPTH	040800539-0004	None Detected	None Detected	0.1	<0.1	
23-STORY-TP-3	1.5' -3' COMPOSITE	040800539-0005	None Detected	None Detected	0.1	<0.1	
24-STORY-TP-3	3' DEPTH	040800539-0006	None Detected	None Detected	0.1	<0.1	
26-STORY-TP-4	0' -3' COMPOSITE	040800539-0007	None Detected	None Detected	0.1	<0.1	
27-STORY-TP-4	3' DEPTH	040800539-0008	None Detected	None Detected	0.1	<0.1	
28-STORY-TP-5	0 -3' COMPOSITE	040800539-0009	None Detected	None Detected	0.1	<0.1	
29-STORY-TP-5	3' DEPTH	040800539-0010	None Detected	None Detected	0.1	<0.1	
30-STORY-TP-7	0' -3' COMPOSITE	040800539-0011	None Detected	None Detected	0.1	<0.1	
31-STORY-TP-7	3' DEPTH (STORY TP-7)	040800539-0012	None Detected	None Detected	0.1	<0.1	

Debbie Little  
Analyst  
Stephen Siegel, CH or Approved EMSL Signatory

EMSL maintains liability limited to cost of analysis. This method requires the laboratory to analyze the sample until the first fiber found comprises 5% of the total mass. Due to the size and mass of different asbestos fibers, the analytical variable

samples and may prevent the laboratory from achieving the target sensitivity on all samples. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. EMSL is not responsible for

activities or analytical method limitations, interpretation and use of results are the responsibility of the client.





## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

040800539

<b>Company:</b> Tetra Tech	<b>Bill To:</b> Tetra Tech
<b>Address1:</b> 1601 2nd Avenue North	<b>Address1:</b> 1601 2nd Avenue North
<b>Address2:</b> Suite 116	<b>Address2:</b> Suite 116
<b>City, State:</b> Great Falls, Montana	<b>City, State:</b> Great Falls, Montana
<b>Zip/Post Code:</b> 59404	<b>Zip/Post Code:</b> 59404
<b>Country:</b> USA	<b>Country:</b> USA
<b>Contact Name:</b> Keith Cron	<b>Attn:</b> Keith Cron
<b>Phone:</b> 406.453.1641	<b>Phone:</b> 406.453.1641
<b>Fax:</b> 406.771.0743	<b>Fax:</b> 406.771.0743
<b>Email:</b> Keith.Cron@tetratech.com	<b>Email:</b> Keith.Cron@tetratech.com
<b>EMSL Rep:</b> Stephen Siegel	<b>P.O. Number:</b>
<b>Project Name/Number:</b> 1157720035.200 CMC Bozeman Facility - SI	

MATRIX			TURNAROUND			
<input type="checkbox"/> Air	<input checked="" type="checkbox"/> Soil	<input type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours. Please call ahead to schedule. There is a premium charge for 3-hour tat, please call 1-800-220-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00a.m. Mon-Fri.). Please Refer to Price Quote

<b>PCM - Air</b> <input type="checkbox"/> NIOSH 7400(A) Issue 2: August 1994 <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input type="checkbox"/> ASTM D 5755-95 (quantitative method) <input type="checkbox"/> Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method fibers/gram	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500
<b>OTHER</b> <input checked="" type="checkbox"/> CARB 435		

SAMPLES ACCEPTED  
FOR ANALYSIS BY  
EMSL ANALYTICAL, INC.

Sent Via Fed Ex Tracking #

798347004364

W/TEM EPA 1000  
Point Count Method



040800539



# Chain of Custody

## Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) 19 31 minus 25Total Samples #: 12Relinquished: [Signature] Date: 1/8/08Time: P.M.Received: DM-FX-915A Date: \_\_\_\_\_

Time: \_\_\_\_\_

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	VOLUME (if applicable)
19 - Story-TP-1	Composite 1.5' - 4' (Story TP-1)	N/A
20 - Story-TP-1	Base 4' depth (Story-TP-1)	
21 - Story-TP-2	3.5' - 4' depth (Story TP-2)	
22 - Story-TP-2	4' - depth (Story TP-2)	
23 - Story-TP-3	1.5' - 3' Composite (Story TP-3)	
24 - Story-TP-3	3' depth (Story TP-3)	
25 - Story-TP-3	<del>3' depth duplicate (Story TP-3)</del>	
26 - Story-TP-4	0' - 3' Composite (Story TP-4)	
27 - Story-TP-4	3' depth (Story TP-4)	
28 - Story-TP-5	0-3' Composite (Story TP-5)	
29 - Story-TP-5	3' Depth (Story TP-5)	
30 - Story-TP-7	0' - 3' Composite (Story TP-7)	
31 - Story-TP-7	3' Depth (Story TP-7)	

SAMPLES ACCEPTED  
FOR ANALYSIS BY  
EMSL ANALYTICAL, INC.



## **APPENDIX I**

### **Asbestos Dust Sample Field Log Notes**





TETRA TECH, INC.

CLIENT City of BozemanDATE 12/17/07

JOB TITLE \_\_\_\_\_

JOB NUMBER 1157720035.200SUBJECT Dust SamplingBY 3/11/NS SHEET 1 of 6

North Harrington Building - Main Level Southwest Office / Men's / Women's Bathroom				Sample ID # NAB-1 1-min sample / 4 directions		
Subsample #	Location	Accessibility	(Min) Time	Photo Log	Notes	
1	<del>Southwest Office</del> Office bookshelf	None	100		N. Wall bookshelf (NAB)	
2	Office	None	1		W. Wall top of chest (fabric) (7.5 ft) stacked chairs	
3	Women's Bath	<del>None</del> Accessible	1		E Wall 12x14 floor tile	
4	Women's Bath	<del>In Frequent</del> In Frequent	1		N. Wall behind toilet (black)	
5	Men's Bath	Accessible	1		E Wall @ door threshold 12x12 floor tile	
6	Men's Bath	In Frequent	1		S. Wall white toilet 12x12 floor tile	
7	Men's Bath	Accessible	1		S. Wall top of ceramic vanity 3 feet	
8	Men's Bath	In Frequent	1		S. Wall top of 6' foot wooden shelving unit	
9	Office	Accessible	1		middle room carpet	
10	Office	In Frequent	1		S. Wall Sheet vinyl behind shelving	





TETRA TECH, INC.

CLIENT City of BozemanDATE 12/17/07

JOB TITLE \_\_\_\_\_

JOB NUMBER 1157720035.200SUBJECT Dust SamplingBY PL/NS SHEET 2 of 6North Hittington Building - Main Level  
Show room / closet AreaSample ID # NHB-2  
1-min sample / aliquot  
w/ directions

Subsample #	Location	Accessibility	Time	Photo Log	Notes
1	Star NW Showroom	inaccessible	1		storage area w/ plywood deck
2	S. Showroom	accessible	1		tongue-and-groove wooden floor traffic area
3	N/E Showroom	in frequent	1		top of <del>steel</del> <sup>micro metal</sup> 4' from ground steel surface
4	N/E Showroom	accessible	1		blue wooden floor access
5	NW Showroom	accessible	1		carpet N area within glass case area
6	Closet	accessible	1		carpet wooden floor middle of room
7	S. Show	in frequent	1		S. wall top of blue desk shelf ~ 5'
8	S. Show	in accessible	1		above SW office storage area plywood deck
9	S show	in frequent	1		top of steel filing cabinet along S. wall
10	NW show	in frequent	1		blue window sill plywood painted

Photo Log





TETRA TECH, INC.

CLIENT City of BozemanDATE 12/17/07

JOB TITLE \_\_\_\_\_

JOB NUMBER 1157720035.200SUBJECT Dust SamplingBY KL/NSSHEET 3 of 6

North Harrington Building - Main Level Main Office/Storage Room # 1, 2				Sample ID # <u>NAB-3</u> 1-min sample/aliquot 4 draw hands
Subsample #	Location	Accessibility	Time	Notes
1	Entrway	accessible	1	Front entryway carpet mat brown powder
2	Entrway	in frequent	1	On 12x12 floor tile by Coke Machine
3	Main Office	accessible	1	In front entryway on carpet
4	Main Office	in frequent	1	On top of E. Wall computer approx 4' off ground on plastic
5	Storage 1	in frequent	1	In closet along hardwood unfinished/shined floor
6	Storage 1	accessible	1	In main entry/pothway along carpet
7	Storage 2	accessible	1	In front of door along carpet E. wall
8	Storage 2	in frequent	1	top of cardboard box w. wall
9	Storage 2	inaccessible	1	above 2x4 drop down ceiling panel on w. side of light
10	Storage 1	inaccessible	1	along w. wall above sink in base of wine rack along wood # filter loaded





TETRA TECH, INC.

CLIENT City of BroomfieldDATE 12/17/07

JOB TITLE \_\_\_\_\_

JOB NUMBER 1157720055.000SUBJECT Dust SamplingBY JL/USSHEET 4 of 6North Harrington Building - Main Level  
~~Main Level Office / Storage Room #1~~ 2 DeckSample ID # NH8-4  
1-min Sample/stop

Subsample #	Location	Accessibility	Time	Notes
1	North Deck	accessible	1	Loading dock middle of concrete
2	North Deck	accessible	1	Loading dock on top of package 3 ft S. Wall
3	North Deck	infrequent	1	Loading dock on wood ~3 ft on top of saw
4	North Deck	accessible	1	Loading dock concrete N side
5	North Deck	infrequent	1	Loading dock east wall top of wood pallet
6	South Deck	accessible	1	Loading dock S. Room @ threshold on carpet
7	South Deck	infrequent	1	Loading dock S. Room NW corner MDF book shelf ~ 6' above ground
8	South Deck	inaccessible	1	Loading dock W wall top of plywood shelf ~ 7.5'
9	North Deck	inaccessible	1	Loading dock top of wooden crate ~ 8'
10	North Deck	infrequent	1	Loading dock S. Stairs N Wall Concrete (top)





TETRA TECH, INC.

CLIENT City of BozemanDATE 12/17/07

JOB TITLE \_\_\_\_\_

JOB NUMBER 1157720035.200SUBJECT Dust SamplingBY JCC/US SHEET 5 of 6

South Harrington Building - Main Level Salvation Army shop & Bathroom				Sample ID # SHB-1 1 min Sample / aliquot	
Subsample #	Location	Accessibility	Time	Notes	
1	Bathroom	accessible	1	S location along door using chance to bathroom sheet vinyl	
2	shop	accessible	1	black steel flashing along transition from N to S building	
3	shop	infrequent	1	N wall concrete near building transition	
4	shop	infrequent	1	Top of wood speaker along E wall	
5	shop	accessible	1	middle of shop area concrete floor along crack (joint) in concrete	
6	shop	infrequent	1	S wall middle of shop along concrete floor in between boxes	
7	shop	infrequent	1	middle of room on top of boxes (cardboard) approx. 3-4 ft from ground	
8	shop	accessible	1	top of 2' counter along middle of west wall	
9	shop	infrequent	1	E wall concrete floor N. side S. of garage door	
10	shop	accessible	1	middle bathroom floor along sheet vinyl	

\* - by 5<sup>th</sup> aliquot samples collected

\* No inaccessible



North Hunnington Building - 3rd Level

Big Sky A. Kido

Sample ID # NHB-5

1 min / aliquot

Subsample #	Location	Accessibility	Time	Notes
1	main room	non	1	top of <del>no</del> changing room partition wall east side wood
2		non	1	top of changing room partition wall west side wood
3		accessible infrequent	1	bottom shelf of coffee table wood
4		accessible	1	Carpet floor in front of E changing room threshold
5		infrequent	1	stair ledge <del>infrequent</del> wooden S wall
6		Accessible	1	Carpet floor in front of <del>the</del> changing room threshold
7		infrequent	1	W window sill wooden 2' from ground
8		infrequent	1	Inside East Wall bookcase (armour) 4.5 ft from ground
9/10		accessible	1	Middle of canvas dog mat
10/9		accessible		1st step coming up stairs from attic level Carpet



North Harington Building - ~~3rd Floor~~ Main Level  
Bitterroot Stained Glass Shop and Storage Room

Sample ID # NHB-6  
1 min / a liquid  
4 Passes

Subsample #	Location	Accessibility	Time	Notes
1	Shop	in frequent	1	West wall white painted wood window sill ~ 3' above
2	Shop	Accessible	1	West side in entryway along brown carpet
3	shop	in frequent	1	N Wall white painted wood window sill ~ 3' above ground
4	shop	accessible	1	middle of room carpeted table ~ 3' above floor
5	shop	inaccessible	1	middle of room above ceiling 2x4' tile approx. 7.5' ft above floor used as platform
6	Storage	accessible	1	West room @ doorway entrance on Carpet
7	Storage	accessible	1	East room near Freight Door along wood floor
8	Storage	in frequent	1	N. Wall white painted window sill 3' above ground
9	Storage	in frequent	1	S Wall bookshelf wooden 6' above ground
10	Storage	inaccessible	1	Middle of Room above 2x4' ceiling tile approx 7.5' ft above ground



North Harrington Building - Basement  
Show room

Sample ID # NHB-7  
1 min / aliquot  
4 per 100

Subsample	Location	Accessibility	Time	Notes
1	Show Room	accessible	1	Concrete Floor NW side of Building near Freight elevator
2	Show Room	accessible	1	Carpet Floor near stairs middle
3	Cleaning Area	inaccessible	1	on top of steel shelf along west wall ~ 7 ft off ground
4	Cleaning Area	infrequent	1	middle wooden shelf S. side of cleaning room ~ 3 ft off ground
5	Stairwell	accessible	1	bottom of stairwell on carpet step
6	Shop	infrequent	1	top of wooden shelf ~ 4 ft off ground
7	Shop	accessible	1.03	South side of basement along carpet
8	Shop	infrequent	1	W. wall plastic window sill ~ 5 ft from ground
9	Shop	inaccessible	1	top of galvanized HVAC duct
10	Shop	infrequent	1	N side concrete floor near Freight elevator



North Harrington Building - Basement HVAC Room					Sample ID # NHB-8 1 min / aliquot 4 passes
Subsample	Location	Accessibility	Time	Notes	
1	HVAC Room	accessible	1	SW corner	Concrete floor near south door
2	HVAC Room	accessible	1	SE corner	Concrete floor
3	HVAC Room	accessible	1	NW corner (N. Door)	Concrete floor
4	↓	accessible	1	NE corner of door	Concrete floor
5	↓	in frequent	1	N. Top of Furnace (metal)	approx. 4' from ground
6	↓	in frequent	1	S. Top of Furnace (metal)	approx. 4' from ground
7	↓	in frequent	1	Top of hot water heater	SI= Conn metal - 5 ft from ground
8	↓	in frequent	1	Top of metal 6" vent duct	~ 6.5' from ground
9	↓	inaccessible	1	bottom of HVAC Furnace (S)	not in operation on concrete
10	↓	inaccessib	1	bottom of N HVAC Furnace	in operation on concrete



North Harrington Building - Basement  
Shop/Office/Vault

Sample ID #  
NH3-9

Subsample	Location	Accessibilit	Time	Notes
1	Office	accessible	1	along carpet in front of sofa
2	office	in frequent	1	along N. Wall carpeted window sill 4"
3	office	inaccessible	1	top of 2x4' ceiling tile pouring 7' above
4	office	in frequent	1	top of clock wooden SW corner
5	Shop	accessible	1	Concrete floor middle of shop
6	Shop	accessible	1	E. Wall counter top (MDF) 3' from ground
7	Vault	accessible	1	middle of room concrete floor
8	Shop	in frequent	1	N. middle of room top of drill (metal) 5' from ground
9	Vault	in frequent	1	top of bridge metal 5' from ground
10	Vault	inaccessible	1	top of metal shelving unit along north wall 6.5' from ground



North Harrington Building - Attic South Showroom					Sample ID # NHB-10
Subsample	Location	Accessibility	Time	Notes	
1	S. Building	accessible	1	Carpet @ top of stairs	
2	S. Showroom	accessible	1	Carpet in middle of space	
3	S. Show room	accessible	1	Carpet in front of freight elevator	
4	S. Showroom	accessible	1	N. Showroom floor @ top of stair wall	
5	S. Showroom	in frequent	1	W side plywood @ edge of space on floor	
6	S. Showroom	in frequent	1	top of steel freight elevator approx. 8' from ground	
7	S. Show room	in frequent	1	E side along plywood floor	
8	S. Showroom	in frequent	1	E. side along exposed ceiling joist (original construction)	
9	S. Showroom	inaccessible	1	S. side top of ceiling truss approx 6.5 ft above floor	
10	S. Show room	inaccessible	1	N side near stairwell (behind TVs) <del>plywood structure</del> Steel pipe	



JOB TITLE CMC Bazaar Facility

BY Keith Cron / NS

DATE 12/18/02

JOB NUMBER 115-7720035.200

SUBJECT Dust Sampling

SHEET 6/7

North Huntington Building - Attic  
North Show room

Sample ID #  
NHBS-11

Subsample	Location	Accessability	Time	Notes
1	<del>show room</del>	accessible	1	NE corner along carpet
2	" "	accessible	1	middle of room along carpet
3	" "	accessible	1	SW side of room along carpet
4	" "	in frequent	1	SW side of corner on Fan sill plywood
5	" "	inaccessible	1	middle of room above 2x4' ceiling tile 8'
6	" "	in frequent	1	SW side of room along wooden book shelf "Dusty" 3'
7	" "	accessible	1	NW corner carpet
8	" "	in frequent	1	NW corner window sill wooden white 3' above floor
9	" "	in frequent	1	N wall white wooden window sill 3'
10		inaccessible	1	E wall ceiling 2x4' ceiling tile above 8'



North Harrington Building - Attic				Sample ID #
Breakroom / East Office / Hallway				NHB-12
Subsample	Location	Accessibility	Time	Notes
1	Break Room	accessible	1	brown carpet along floor
2	" "	infrequent	1	top of refrigerator steel surface 5'-5" off ground
3	" "	inaccessible	1	top of steel light ballast 7' from within steel grid ceiling structure
4	office	accessible	1	carpet @ door threshold
5	" "	infrequent	1	Top of wooden MOF book case w. wall 1' off ground
6	" "	" "	1	Top of wooden bookcase 6.5' off floor NW wall
7	" "	inaccessible	1	Top of 2x4 ceiling tile above ceiling plenum
8	hall	accessible	1	bottom of big sky Akdo stairs along laminate floor
9	" "	infrequent	1	w. wall top shoe rack 5' above floor
10	hall	accessible	1	Start of Big sky Akdo hall Laminated floor





TETRA TECH

## Daily Log

Project Name: CMC Boxerman Facility		Project No.: 1157720035-200	
Building:		Date: 12/17/07	
Area: Dust Samples		Project Day No.: 1 of 1	
Contractor:		Tetra Tech Personnel: NS/KC	
Contractor Personnel:		Sheet: 1 of 1	
ACM Removed:			
Estimated Percent of Phase Completed:		On Schedule? (circle):	Yes No
GENERAL REMARKS/METINGS/SITE VISITS/CONTRACTOR PROGRESS:			
0930 - N/S Calibrate Dust Sample using			
NHB - <del>1</del> - 1 Time off Post Cal North Harrington Building Main Level Southwest Office/Men's and Women's Restroom			
Start 0945 Stop ~ 1045 Pre/post Cal after each Composite Sample			
NHB - 2 Start NHB Main Level Show Room / closet Start <del>1045</del> 1100 Stop 1145 1150 post cal			
Media Blank #1, Media Blank #2 - sent from lot #60719 of 25mm Dust Monitoring Cassettes 0.8um MCE Filter (1055)			
FB - 1 30 sec in air sample (1100) - 1145 post cal			
12 - 1300 Lunch			
1300 - 1310 Pre Cal NHB - 3 Main Level front office Storage Room #1, 2 Start 1300 End - 1350 post cal 1400			
1400 - 1430 Pre Cal NHB - 4 Main Level East Deck Area 1430 Post Cal for clock			
Industrial Hygiene Technician:		Reviewed By:	





TETRA TECH

## Daily Log

Project Name: CMC Bozeman Facility		Project No.: 1157720035.200	
Building: Harrington N. Building		Date: 12/18/07	
Area: Dust Sampling		Project Day No.: 2 of	
Contractor: NA		Tetra Tech Personnel: RC/NS	
Contractor Personnel: NA		Sheet: 1 of 1	
ACM Removed: NA			
Estimated Percent of Phase Completed:		On Schedule? (circle):	Yes No
GENERAL REMARKS/MEETINGS/SITE VISITS/CONTRACTOR PROGRESS:			
- 0830 - Mob to site, wait for Jeff to open doors			
- 0900 - Enter Building Mob in			
0930 - Start Stained Glass 1005 Finish			
10			
1115 - Basement Show Roo 1145 finish 1220			
1250 - 1220 - Dismiss			
1h-			
1335 1445 - NHB Attic South Showroom			
12/19/07			
1650 - NHB - Big Sky Aikido			
1725 Return Plenum sample in their HVAC			
Space in middle of ceiling 2min sample			
1730 NHB - 74 Main Level Return Plenum steel			
- subsample <del>1 min</del> 1 min / aliquot			
- no 2nd Level Return viewable			
- was abandoned only ran 1 min due to subsample could not be run			
Industrial Hygiene Technician:		Reviewed By:	



FB-1 → 30 SEC (NHB) 12.17.07

MEDIA BLANKS 1 & 2 → 12.17.07



**TETRA TECH** MICROVAC CASSETTE  
LOT # 60719

# AIR SAMPLE COLLECTION

Project: CMC - ROZEMAN Facility		Date: 12.17.07/12.18.07												
Building: 5I WORKMAN (Dust Samples) / Basement		Calibration Instrument: Dry Cal (Bios) SN 102680												
Location: HARRINGTONS		IH Technician: Nathan Sheehan												
Project No.: 1157720035, 200		Checked By:												
Sample ID	Sample Description and Location	Pump ID	Start Time	Stop Time	Total Minutes	PRECALIBRATION			PRE Average Flow	POSTCALIBRATION			POST Average Flow	Volume (liters)
NHB-1	main level - in office & men & women restroom	767954	10:30	10:50	10	Test #1	Test #2	Test #3		Test #1	Test #2	Test #3		
						Date/Time: 12.17.07				Date/Time: 12.17.07/10:50				
NHB-2	main level - S. Showroom & N. Showroom all closets		11:10	11:50	10	2.004	2.004	2.004	2.004	2.085	2.087	2.089	2.087	20.46
						Date/Time: 12.17.07/11:10				Date/Time: 12.17.07/11:49				
NHB-3	main level - E. Showroom, main office, storage I, Storage 2		13:15	13:55	10	2.057	2.064	2.065	2.062	2.097	2.092	2.093	2.091	20.77
						Date/Time: 12.17.07/13:15				Date/Time: 12.17.07/13:50				
NHB-4	main level - E. dock AREA		14:00	14:40	10	2.075	2.084	2.086	2.082	2.104	2.125	2.105	2.111	20.97
						Date/Time: 12.17.07/14:00				Date/Time: 12.17.07/14:30				
NHB-5	SAVINGTON army Shop & Bathroom 3rd level - Big Sky Aikido		14:40	15:15	10	2.014	2.014	2.013	2.014	1.960	1.962	1.963	1.962	19.89
						Date/Time: 12.17.07/14:40				Date/Time: 12.17.07/15:15				
NHB-6	main level - Bathroom, Showroom, Storage 2, Storage	767994	15:20	15:55	10	2.003	1.987	1.989	1.993	2.012	2.034	2.015	2.020	20.07
						Date/Time: 12.17.07/15:20				Date/Time: 12.17.07/15:50				
NHB-7	NHB - basement		16:40	17:15	10	2.007	2.033	2.014	2.018	2.017	2.024	2.024	2.022	20.20
						Date/Time: 12.18.07/16:40				Date/Time: 12.18.07/17:15				
NHB-8	NHB - basement		17:20	17:55	10	2.039	2.058	2.039	2.045	2.061	2.040	2.039	2.047	20.46
						Date/Time: 12.18.07/17:20				Date/Time: 12.18.07/17:55				
NHB-9	NHB - basement	NA			0.5				NA				NA	NA
						Date/Time: 12.18.07/11:00				Date/Time:				
NHB-10	NHB - basement	NA												
						Date/Time: 12.18.07/11:03				Date/Time:				
NHB-11	NHB - basement	767994	11:10	11:45	10									
						Date/Time: 12.18.07/11:10				Date/Time: 12.18.07/11:45				
NHB-12	NHB - basement	767994	13:40	14:30	10	2.016	1.996	2.014	2.009	2.048	2.054	2.055	2.052	20.31
						Date/Time: 12.18.07/13:40				Date/Time: 12.18.07/14:20				
NHB-13	NHB - basement	767994	14:35	15:10	10	2.050	2.030	2.030	2.037	2.047	2.047	2.048	2.047	20.42
						Date/Time: 12.18.07/14:35				Date/Time: 12.18.07/15:00				
NHB-14	NHB - basement	767994	15:10	16:20	10	2.038	2.039	2.021	2.033	2.027	2.012	2.028	2.022	20.28
						Date/Time: 12.18.07/15:10				Date/Time: 12.18.07/16:15				
NHB-15	NHB - attic	767994	16:20	17:00	10	2.007	2.024	2.008	2.015	2.034	2.054	2.036	2.041	20.28
						Date/Time: 12.18.07/16:20				Date/Time: 12.18.07/16:50				
NHB-16	NHB - attic	767994	17:00	17:45	10	2.023	2.029	2.026	2.026	2.031	2.031	2.030	2.031	20.29
						Date/Time: 12.18.07/17:00				Date/Time: 12.18.07/17:37				
NHB-17	NHB - attic	767994	17:00	17:45	10	2.016	2.021	2.040	2.026	2.033	2.034	2.032	2.033	20.30
						Date/Time: 12.18.07/17:00				Date/Time: 12.18.07/17:37				

user pump

12.17

12.18





## AIR SAMPLE COLLECTION

Project: CMC Bozeman		Date: 12.19.07															
Building: NHB		Calibration Instrument: Bios Dryer															
Location:		IH Technician: NS/KC															
Project No.: 1 NOT CONTINUOUS																	
Checked By:																	
Sample ID	Sample Description and Location	Pump ID	Start Time	Stop Time	Total Minutes	PRECALIBRATION			POSTCALIBRATION			PRE Average Flow	POST Average Flow			Volume (liters)	
						Test #1	Test #2	Test #3	Test #1	Test #2	Test #3		Test #1	Test #2	Test #3		
NHB-13	Big Sky Area -3rd floor HVAC RETURN AIRFLOW	798134	16:45	17:30	2	Date/Time: 12.19.07/16:45	Date/Time: 12.19.07/16:45	Date/Time: 12.19.07/16:45	Date/Time: 12.19.07/17:25	Date/Time: 12.19.07/17:25	Date/Time: 12.19.07/17:25	1.983	Date/Time: 12.19.07/17:25	Date/Time: 12.19.07/17:25	Date/Time: 12.19.07/17:25	1.983	3.97
NHB-14	main floor HVAC RETURN	798134	17:30	17:45	1	Date/Time: 12.19.07/17:25	Date/Time: 12.19.07/17:25	Date/Time: 12.19.07/17:25	Date/Time: 12.19.07/17:40	Date/Time: 12.19.07/17:40	Date/Time: 12.19.07/17:40	1.983	Date/Time: 12.19.07/17:40	Date/Time: 12.19.07/17:40	Date/Time: 12.19.07/17:40	1.964	1.97
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:	Date/Time:		Date/Time:	Date/Time:	Date/Time:		
						Date/Time:	Date/Time:	Date/Time:	Date/Time:								



## **APPENDIX J**

### **Asbestos Dust Sample Analytical Results**





EMSL Analytical, Inc.

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: westmontlab@EMSL.com

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAX056  
Customer PO:  
Received: 12/28/07 9:40 AM  
EMSL Order: 040731699

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: CMC BOZEMAN-1157720035.200

EMSL Proj:  
Analysis Date: 2/2/2008  
Report Date: 2/3/2008

### Asbestos Analysis via Transmission Electron Microscopy ASTM Method D5755-03

SAMPLE ID	AREA SAMPLED (cm <sup>2</sup> )	ASBESTOS TYPE	ASBESTOS STRUCTURES	Sensitivity (str/cm <sup>2</sup> )	CONCENTRATION (str/cm <sup>2</sup> )	COMMENTS
20 040731699-0001	0	None Detected	<3			Blank
21 040731699-0002	0	None Detected	<3			Blank
22 040731699-0003	1000	None Detected	<3	1990	<5970	
20 040731699-0020	0	None Detected	<3			Blank
21 040731699-0021	0	None Detected	<3			Blank
22 040731699-0022	1000	None Detected	<3	1990	<5970	
23 040731699-0023	0	None Detected	<3			Blank
24 040731699-0024	0	None Detected	<3			Blank
25 040731699-0025	1000	None Detected	<3	332	<996	
26 040731699-0026	1000	None Detected	<3	996	<2990	
27 040731699-0027	1000	None Detected	<3	332	<996	

Analyst(s)

Theodore Xu (22)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted.

TEMMicro-1



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: [westmontlab@EMSL.com](mailto:westmontlab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAX156  
Customer PO:  
Received: 12/28/07 9:40 AM  
EMSL Order: 040731699

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: CMC BOZEMAN-1157720035.209

EMSL Proj:  
Analysis Date: 2/2/2008  
Report Date: 2/3/2008

**Asbestos Analysis via Transmission Electron Microscopy ASTM Method D5755-03**

SAMPLE ID	AREA SAMPLED (cm <sup>2</sup> )	ASBESTOS TYPE	ASBESTOS STRUCTURES	Sensitivity (str/cm <sup>2</sup> )	CONCENTRATION (str/cm <sup>2</sup> )	COMMENTS
28 040731699-0028	1000	None Detected	<3	3320	<9960	
29 040731699-0029	1000	None Detected	<3	199	<597	
30 040731699-0030	1000	None Detected	<3	996	<2990	
31 *31699-0031	1000	Amosite Chrysotile	<3	332	<996	
32 040731699-0032	1000	None Detected	<3	9960	<29900	
33 040731699-0033	1000	None Detected	<3	9960	<29900	
34 040731699-0034	1000	None Detected	<3	9960	<29900	
35 040731699-0035	1000	None Detected	<3	3320	<9960	
36 040731699-0036	1000	None Detected	<3	1990	<5970	
37 040731699-0037	100	None Detected	<3	1990	<5970	
38 040731699-0038	100	None Detected	<3	19900	<59700	

revised report- asbestos structure counting criteria of 3:1 used

Analyst(s)

Theodore Xu (22)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted.



**TETRA TECH****Tetra Tech**1601 2<sup>nd</sup> Avenue North, Suite 116

Great Falls, Montana 59401

Tel: 406.453.1641 Fax: 406.771.0743

**Fax**

Date:

1/28/08

No. of pages including cover sheet:

8

To:

Steve Siegel

Company:

EMSL

Phone:

856 858 4800

Fax:

856 858 4960

CC:

From:

Keith Cron

Dept:

IH

Phone:

406 4531641

Fax:

☐ Urgent ☐ For your review ☒ Reply ASAP ☐ Please comment

Steve,

Please find attached (2) EMSL Laboratory Reports you provided analytical services for. For the NIOSH 7402 Method run on the provided samples, please analyze them for (ISO Method 10312).

For the ASTM D 5755-03, please provide analytical results for a fiber ratio of 3:1 instead of the method-specified 5:1. Additionally, please note the changes to the area with dust wipe sampling as ~~was~~ all were greater than the 100 cm<sup>2</sup> specified.

Please call me with any additional questions. We can have a 6+ day turnaround time as well.

Thanks.



FED Ex # 7909-0467-1511

Page 1 of 2<sup>13</sup>

## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

<b>Company:</b> Tetra Tech	<b>Bill To:</b> Tetra Tech
<b>Address1:</b> 1601 2nd Avenue North Suite 116	<b>Address1:</b> 1601 2nd Avenue North Suite 116
<b>Address2:</b>	<b>Address2:</b>
<b>City, State:</b> Great Falls, Montana	<b>City, State:</b> Great Falls, Montana
<b>Zip/Post Code:</b> 59401	<b>Zip/Post Code:</b> 59401
<b>Country:</b> U.S.A.	<b>Country:</b> U.S.A.
<b>Contact Name:</b> Keith Cron	<b>Attn:</b> Keith Cron
<b>Phone:</b> 406.453.1641	<b>Phone:</b> 406.453.1641
<b>Fax:</b> 406.771.0743	<b>Fax:</b> 406.771.0743
<b>Email:</b> Keith.Cron@Tetrattech.com	<b>Email:</b> Keith.Cron@Tetrattech.com
<b>EMSL Rep:</b>	<b>P.O. Number:</b>
<b>Project Name/Number:</b> CMC Bozeman - 1157720035.200	

MATRIX			TURNAROUND			
<input type="checkbox"/> Air	<input type="checkbox"/> Soil	<input checked="" type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours, Please call ahead to schedule. There is a premium charge for 3-hour test, please call 1-800-220-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00a.m. Mon-Fri.), Please Refer to Price Quote

<b>PCM - Air</b> <input type="checkbox"/> NIOSH 7400(A) Issue 2, August 1994 <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input checked="" type="checkbox"/> ASTM D 5755-95 (quantitative method) <input type="checkbox"/> Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method fibers/gram	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500  <b>OTHER</b> <input type="checkbox"/>



Page 2 of 2  
3

## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) 20 38Total Samples #: 19Relinquished: Nathan Shumate Date: 12-27-07Time: p.m.

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	VOLUME (if applicable)	Area Sampled cm <sup>2</sup>
20	NHB - media blank 1	NA	
21	NHB - media blank 2	↓	
22	SHB-1 - Salvation Army Shop 3 bathroom	20.1 L	1,000 cm <sup>2</sup>
23	NHB - Field blank (FB-1)	NA	
24	NHB - Field blank (FB-2)	↓	
25	NHB-1: SW office / mens 3 women's bath	20.46 L	1,000 cm <sup>2</sup>
26	NHB-2: S. Showroom / N. Showroom w/ closet	20.77 L	1,000 cm <sup>2</sup>
27	NHB-3: main floor: • entry hall • main office • storage 1 & 2	20.97 L	1,000 cm <sup>2</sup>
28	NHB-4: main level - east dock area	19.9 L	1,000 cm <sup>2</sup>
29	NHB-5: 3rd level - Big sky Atrium	20.2 L	1,000 cm <sup>2</sup>
30	NHB-6: main floor: • Bitterroot stained glass shop & storage	20.5 L	1,000 cm <sup>2</sup>
31	NHB-7: BASEMENT showroom	20.5 L	1,000 cm <sup>2</sup>
32	NHB-8 - BASEMENT HVAC room	20.4 L	1,000 cm <sup>2</sup>
33	NHB-9 - BASEMENT: • Shop • office • vault	20.3 L	1,000 cm <sup>2</sup>



Page 2 of 2  
3 3



## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) SEE Pg. 2 of 3

Total Samples #: \_\_\_\_\_

Relinquished: Nathan Shumate Date: 12-27-07

Time: p.m.

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

[illegible]



## **APPENDIX K**

### **Asbestos Occupational Air Sample Analytical Results**





Attention: Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

Customer ID: MAXI53  
Customer PO:  
Received: 01/27/08


Fax: 406-771-0743 Phone: 406-453-1641  
Project: CMC Bozeman  
1157720035.200

EMSL Order: 040802108  
Analysis Date: 6/3/2008  
Report Date: 06/04/08

## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0001	
Customer Sample #:	45	
Date sampled:	12/27/2007	
Initials of Analyst:	DL/DY	
Air volume:	0	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	133	
Analytical Sensitivity:	0.58	Structure/square mm
Number of Primary Asbestos Structures Counted:	None Detected	
Number of total asbestos structures counted:	None Detected	
Number of Asbestos Structures > 5 microns:	None Detected	
Number of Asbestos fibers and bundles > 5 microns:	None Detected	
Number of PCM equivalent asbestos structures:	Not Analyzed	
Number of PCM equivalent asbestos fibers:	Not Analyzed	
Concentration of Chrysotile Asbestos:	< 1.73	Structure/square mm
Concentration of Amphibole Asbestos:	< 1.73	Structure/square mm
Lower 95% Confidence Limit (Chrysotile)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 1.73	Structure/square mm
Lower 95% Confidence Limit (Amphibole)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 1.73	Structure/square mm
Concentration of Asbestos (total):	< 1.73	Structure/square mm

**Comments:** Additional grid openings analyzed under  
EMSL order ID:04081235. Analysis occurred from original  
grid preps.

  
Approved Signatory





**Attention:** Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

**Customer ID:** MAXI53  
**Customer PO:**  
**Received:** 01/27/08

**Fax:** 406-771-0743      **Phone:** 406-453-1641  
**Project:** CMC Bozeman  
1157720035.200

**EMSL Order:** 040802108  
**Analysis Date:** 6/3/2008  
**Report Date:** 06/04/08

## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0002	
Customer Sample #:	46	
Date sampled:	12/27/2007	
Initials of Analyst:	DL/DY	
Air volume:	0	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	66	
Analytical Sensitivity:	1.17	Structure/square mm
Number of Primary Asbestos Structures Counted:	None Detected	
Number of total asbestos structures counted:	None Detected	
Number of Asbestos Structures > 5 microns:	None Detected	
Number of Asbestos fibers and bundles > 5 microns:	None Detected	
Number of PCM equivalent asbestos structures:	Not Analyzed	
Number of PCM equivalent asbestos fibers:	Not Analyzed	
Concentration of Chrysotile Asbestos:	< 3.48	Structure/square mm
Concentration of Amphibole Asbestos:	< 3.48	Structure/square mm
Lower 95% Confidence Limit (Chrysotile)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 3.48	Structure/square mm
Lower 95% Confidence Limit (Amphibole)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 3.48	Structure/square mm
<b>Concentration of Asbestos (total):</b>	<b>&lt; 3.48</b>	<b>Structure/square mm</b>

**Comments:** Additional grid openings analyzed under  
EMSL order ID:04081235. Analysis occurred from original  
grid preps.

  
Approved Signatory





Attention: Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

Customer ID: MAXI53  
Customer PO:  
Received: 01/27/08

Fax: 406-771-0743 Phone: 406-453-1641  
Project: CMC Bozeman  
1157720035.200

EMSL Order: 040802108  
Analysis Date: 6/3/2008  
Report Date: 06/04/08

## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0003	
Customer Sample #:	47	
Date sampled:	12/27/2007	
Initials of Analyst:	DL/DY	
Air volume:	0	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	124	
Analytical Sensitivity:	0.62	Structure/square mm

Number of Primary Asbestos Structures Counted:	None Detected
Number of total asbestos structures counted:	None Detected
Number of Asbestos Structures > 5 microns:	None Detected
Number of Asbestos fibers and bundles > 5 microns:	None Detected
Number of PCM equivalent asbestos structures:	Not Analyzed
Number of PCM equivalent asbestos fibers:	Not Analyzed

Concentration of Chrysotile Asbestos:	<	1.85	Structure/square mm
Concentration of Amphibole Asbestos:	<	1.85	Structure/square mm
Lower 95% Confidence Limit (Chrysotile)		NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	<	1.85	Structure/square mm
Lower 95% Confidence Limit (Amphibole)		NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	<	1.85	Structure/square mm
<b>Concentration of Asbestos (total):</b>	<b>&lt;</b>	<b>1.85</b>	<b>Structure/square mm</b>

**Comments:** Additional grid openings analyzed under  
EMSL order ID:04081235. Analysis occurred from original  
grid preps.

  
Approved Signatory





**Attention:** Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

**Customer ID:** MAXI53  
**Customer PO:**  
**Received:** 01/27/08

**Fax:** 406-771-0743      **Phone:** 406-453-1641  
**Project:** CMC Bozeman  
1157720035.200

**EMSL Order:** 040802108  
**Analysis Date:** 5/30/2008  
**Report Date:** 05/30/08

## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0004	
Customer Sample #:	48	
Date sampled:	12/27/2007	
Initials of Analyst:	DL/RD	
Air volume:	932.6	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	144	
Analytical Sensitivity:	0.22	Structures/L
Number of Primary Asbestos Structures Counted:	1	
Number of total asbestos structures counted:	1	
Number of Asbestos Structures > 5 microns:	1	
Number of Asbestos fibers and bundles > 5 microns:	1	
Number of PCM equivalent asbestos structures:	Not Analyzed	
Number of PCM equivalent asbestos fibers:	Not Analyzed	
Concentration of Chrysotile Asbestos:	< 0.66	Structures/L
Concentration of Amphibole Asbestos:	< 0.66	Structures/L
Lower 95% Confidence Limit (Chrysotile)	Not Applicable	Structures/L
Upper 95% Confidence Limit (Chrysotile)	< 0.66	Structures/L
Lower 95% Confidence Limit (Amphibole)	Not Applicable	Structures/L
Upper 95% Confidence Limit (Chrysotile)	< 1.05	Structures/L
<b>Concentration of Asbestos (total):</b>	<b>&lt; 0.66</b>	<b>Str./L</b>

  
Approved Signatory





**EMSL Analytical, Inc.**  
*EDXA Spectrum*

File: 040812357-0004 Anthophyllite  
Collected: May 30, 2008 06:06:31


Live Time: 102.11  
Beam Voltage: 20.00

Count Rate: 726  
Beam Current: 2.00

Dead Time: 10.40 %  
Takeoff Angle: 31.00

■ Sample\_38\_S001.pgt

FS: 1600







Attention: Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

Customer ID: MAXI53  
Customer PO:  
Received: 01/27/08

Fax: 406-771-0743 Phone: 406-453-1641  
Project: CMC Bozeman  
1157720035.200

EMSL Order: 040802108  
Analysis Date: 5/30/2008  
Report Date: 05/30/08


## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0005	
Customer Sample #:	49	
Date sampled:	12/27/2007	
Initials of Analyst:	DL	
Air volume:	857.7	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	92	
Analytical Sensitivity:	0.38	Structures/L

Number of Primary Asbestos Structures Counted:	None Detected
Number of total asbestos structures counted:	None Detected
Number of Asbestos Structures > 5 microns:	None Detected
Number of Asbestos fibers and bundles > 5 microns:	None Detected
Number of PCM equivalent asbestos structures:	Not Analyzed
Number of PCM equivalent asbestos fibers:	Not Analyzed

Concentration of Chrysotile Asbestos:	<	1.12	Structures/L
Concentration of Amphibole Asbestos:	<	1.12	Structures/L
Lower 95% Confidence Limit (Chrysotile)		Not Applicable	Structures/L
Upper 95% Confidence Limit (Chrysotile)	<	1.12	Structures/L
Lower 95% Confidence Limit (Amphibole)		Not Applicable	Structures/L
Upper 95% Confidence Limit (Chrysotile)	<	1.12	Structures/L


Concentration of Asbestos (total):	<	1.12	Structures/L
------------------------------------	---	------	--------------

  
Approved Signatory





# EMSL Analytical, Inc Photomicrograph Report



1880 : 1

10µm

## Image Information

Micrograph Number: 580519  
Sample ID: 48  
Order ID: 040802108  
Asbestos Type: Anthophyllite  
Magnification: 2500x  
Camera Length: NA  
Row Spacing: NA  
Laboratory ID: EMSL 04

Comments:



**Cron, Keith**

---

**From:** Cron, Keith  
**To:** rdenton@emsl.com  
**Cc:**  
**Subject:** CMC Bozeman Facility EMSL Reference Order No. ( 040802108)  
**Attachments:**

**Sent:** Thu 5/22/2008 7:05 AM

Robyn,

Per our conversations the past couple of days please find this email as notice to proceed with the reprocessing/reanalysis of the five samples previously analyzed by the ISO 10312 Method. For the reanalysis, I would like the sensitivity to be reduced to 0.0002 structures per cubic centimeter; therefore, I understand that EMSL will have to open approximately 160 new grids to perform the additional analysis to be included in the analytical result per sample. After discussing this with EMSL representatives, they have agreed on a price of \$5/additional grid opening based on a normal turnaround schedule. The additional stipulation that I would like to put on the reanalysis is that a minimum of 10 grid openings be analyzed and continued to count structures until the required analytical sensitivity has been reached, based on the sample volume and the number of grid openings counted. The count may be terminated upon completion of the grid opening containing the 50<sup>th</sup> structure, regardless of whether or not the target analytical sensitivity has been reached.

If you have any additional question, feel free to call or email me. Please let me know when you think you will be done with the analysis as I may need to ask for an extension – on my end.

Thanks for all you help!

Keith Cron, CIH | Branch Manager  
Cell: 406.788.5318 | Main: 406.453.1641 | Fax: 406.771.0743

Tetra Tech | Complex World, Clear Solutions™  
1601 2nd Avenue North, Suite 116 | Great Falls, Montana 59401 | [www.tetratech.com](http://www.tetratech.com)



**TETRA TECH****Tetra Tech**1601 2<sup>nd</sup> Avenue North, Suite 116

Great Falls, Montana 59401

Tel: 406.453.1641 Fax: 406.771.0743

**Fax**

Date:

1/28/08

No. of pages including cover sheet:

8

To:

Steve Siegel

Company:

EMSL

Phone:

856 858 4800

Fax:

856 858 4960

CC:

From:

Keith Cron

Dept:

IH

Phone:

406 453 1641

Fax:

In Reply To:

☐ Urgent ☐ For your review ☒ Reply ASAP ☐ Please comment

Steve,

Please find attached (2) EMSL Laboratory Reports you provided analytical services for. For the NIOSH 7402 Method run on the provided samples, please analyze them for (ISO Method 10312).

For the ASTM D 5755-03, please provide analytical results for a fiber ratio of 3:1 instead of the method-specified 5:1. Additionally, please note the changes to the area with dust wipe sampling as ~~was~~ all were greater than the 100 cm<sup>2</sup> specified.

Please call me with any additional questions. We can have a 6+ day turnaround time as well.

Thanks.



040802108 - ISO 10312

FED Ex # 7909-0467-1511

Page 1 of 2



## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Company: Tetra Tech	Bill To: Tetra Tech
Address1: 1601 2nd Avenue North Suite 116	Address1: 1601 2nd Avenue North Suite 116
Address2:	Address2:
City, State: Great Falls, Montana	City, State: Great Falls, Montana
Zip/Post Code: 59401	Zip/Post Code: 59401
Country: U.S.A.	Country: U.S.A.
Contact Name: Keith Cron	Attn: Keith Cron
Phone: 406.453.1641	Phone: 406.453.1641
Fax: 406.771.0743	Fax: 406.771.0743
Email: Keith.Cron@Tetrattech.com	Email: Keith.Cron@Tetrattech.com
EMSL Rep:	P.O. Number:
Project Name/Number: CMC Bozeman - 1157720035.200	

MATRIX			TURNAROUND			
<input checked="" type="checkbox"/> Air	<input type="checkbox"/> Soil	<input type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours. Please call ahead to schedule. There is a premium charge for 3-hour test, please call 1-800-226-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00a.m. Mon-Fri.), Please Refer to Price Quote

<b>PCM - Air</b> <input type="checkbox"/> NIOSH 7400(A) (rev. 2: August 1994) <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart F <input checked="" type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input type="checkbox"/> ASTM D 5755-95 (qualitative method) <input type="checkbox"/> Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method (fibers/gram)	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500  <b>OTHER</b> SAMPLES ACCEPTED FOR ANALYSIS BY EMSL ANALYTICAL, INC.

040731694



FED EX # 7909-0467-1511

Page 2 of 2



## Chain of Custody

### Asbestos Lab Services

**EMSL Analytical, Inc.**  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) 45 47

Total Samples #: 5

Relinquished: Nathan Shumate Date: 12-27-07

Time: 9.00 p.m.

Received: KW FK Date: \_\_\_\_\_

Time: 540

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

[illegible]

TYPE  
1/30/08



## **APPENDIX L**

### **Quality Assurance Laboratory Results for Soil, Dust, and Air Samples**



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: [westmontasblab@EMSL.com](mailto:westmontasblab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAXI56  
Customer PO:  
Received: 01/09/08 9:15 AM  
EMSL Order: 040800536

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: 1157720035.200 CMC BOZEMAN FACILITY - SI

EMSL Proj:  
Analysis Date: 1/16/2008  
Report Date: 1/16/2008

**PLM Analysis of Bulk Samples for Asbestos via EPA 600/R-93/116 Method with CARB  
435 Prep (Milling) Level A for 0.25% Target Analytical Sensitivity**

Sample	Location	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
25-STORY-TP-3 040800536-0001	3' DEPTH DUPLICATE (STORY TP-3)	Brown Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
MDT-111307-Q1 040800536-0002	LAB QC	Brown Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected

Analyst(s)

Delores Beard (2)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

This report relates only to the samples listed above and may not be reproduced except in full, without EMSL's written approval. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the federal government. EMSL is not responsible for sample collection activities or method limitations. Some samples may contain asbestos fibers below the resolution limit of PLM. EMSL recommends that samples reported as none detected or less than the limit of detection undergo additional analysis via TEM. Samples received in good condition unless otherwise noted. Samples received in good condition unless otherwise noted.





## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608

<http://www.emsl.com>

Please print all information legibly.

040800536

<b>Company:</b> Tetra Tech	<b>Bill To:</b> Tetra Tech
<b>Address1:</b> 1601 2nd Avenue North	<b>Address1:</b> 1601 2nd Avenue North
<b>Address2:</b> Suite 116	<b>Address2:</b> Suite 116
<b>City, State:</b> Great Falls, Montana	<b>City, State:</b> Great Falls, Montana
<b>Zip/Post Code:</b> 59404	<b>Zip/Post Code:</b> 59404
<b>Country:</b> USA	<b>Country:</b> USA
<b>Contact Name:</b> Keith Cron	<b>Attn:</b> Keith Cron
<b>Phone:</b> 406.453.1641	<b>Phone:</b> 406.453.1641
<b>Fax:</b> 406.771.0743	<b>Fax:</b> 406.771.0743
<b>Email:</b> Keith.Cron@tetratech.com	<b>Email:</b> Keith.Cron@tetratech.com
<b>EMSL Rep:</b> Stephen Siegel	<b>P.O. Number:</b>
<b>Project Name/Number:</b> 1157720035.200 CMC Bozeman Facility - S1	

MATRIX			TURNAROUND			
<input type="checkbox"/> Air	<input checked="" type="checkbox"/> Soil	<input type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours. Please call ahead to schedule. There is a premium charge for 3-hour tat, please call 1-800-220-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00a.m. Mon-Fri.). Please Refer to Price Quote

<b>PCM - Air</b> <input type="checkbox"/> NIOSH 7400(A) Issue 2 August 1994 <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002; <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input type="checkbox"/> ASTM D 5755-95 (quantitative method) <input type="checkbox"/> Wipe Qualitative  <b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method (fibers/grain)	<b>OTHER</b> <input checked="" type="checkbox"/> CARB 435w/PLM <input type="checkbox"/> EPA 400 Point Count Method

Seal Via Fed Ex Tracking # 798347004364

EPA 400 Point Count Method



040800536



## Chain of Custody

## Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800

Fax: (856) 858-4960

(856) 427-1608

<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s)

25

and 32

Total Samples #:

2

Relinquished:

Date:

1/8/08

Time:

P.M.

Received:

Date:

Time:

Relinquished:

Date:

Time:

Received:

Date:

Time:

SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	VOLUME (if applicable)
25-Story-TP-3	3' depth duplicate (Story TP-3)	N/A
	Lab QC	
	Re Analysis of EMSL	
	Sample # 040728462-0001	
	Tetra Tech Sample # MDT-111307-Q1	

SAMPLES ACCEPTED  
FOR ANALYSIS BY  
EMSL ANALYTICAL INC.



# EMSL Analytical, Inc.

107 Haddon Avenue, Westmont, NJ 08108 Phone: 800-220-3675 Fax: 856-858-4960

Client: Tetra Tech/Maxim Technologies  
1601 2nd Avenue N Suite 116  
Great Falls, MT 59401  
Attention: Keith Cron  
Fax: email Phone: 781-251-0040  
Project: CMC BOZEMAN-1157720035.200


EMSL Reference: 040731711

Date Received: 12/28/07  
Date Analyzed: 01/04/08  
Date Reported: 01/07/08

Asbestos Analysis of Soil via EPA 600/R-93/116 Method Utilizing  
Analytical Electron Microscopy (Section 2.5) with CARB 435 Prep (Milling)  
Level B for 0.1% Target Analytical Sensitivity

Client Sample ID	EMSL Sample ID	Asbestos Type(s)	# of Asbestos Structures Detected	Analytical Sensitivity %	Asbestos Weight %	Comments
19-HEEBS-TD-4	040731711-0001	None Detected	0	0.1	<0.1	

Debbie Little  
Analyst

  
Stephen Siegel, CIH or Approved EMSL Signatory

EMSL maintains liability limited to cost of analysis. This method requires the laboratory to analyze the sample until the first fiber found compromises 5% of the total mass. Due to the size and mass of different asbestos fibers, the analytical sensitivity will vary between samples and may prevent the laboratory from achieving the target sensitivity on all samples. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. EMSL is not responsible for sample collection activities or analytical method limitations. Interpretation and use of results are the responsibility of the client.





## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly

MAXI 56

<b>Company:</b> Tetra Tech	<b>Bill To:</b> Tetra Tech
<b>Address 1:</b> 1601 2nd Avenue North Suite 116	<b>Address 1:</b> 1601 2nd Avenue North Suite 116
<b>Address 2:</b>	<b>Address 2:</b>
<b>City, State:</b> Great Falls, Montana	<b>City, State:</b> Great Falls, Montana
<b>Zip/Post Code:</b> 59401	<b>Zip/Post Code:</b> 59401
<b>Country:</b> U.S.A.	<b>Country:</b> U.S.A.
<b>Contact Name:</b> Keith Cron	<b>Attn:</b> Keith Cron
<b>Phone:</b> 406.453.1647	<b>Phone:</b> 406.453.1647
<b>Fax:</b> 406.771.0743	<b>Fax:</b> 406.771.0743
<b>Email:</b> Keith.Cron@TetraTech.com	<b>Email:</b> Keith.Cron@TetraTech.com
<b>EMSL Rep:</b>	<b>P.O. Number:</b>
<b>Project Name/Number:</b> CMC Borgman - 157720035 200	

MATRIX			TURNAROUND			
Air	Soil	Micro-Vac	3 Hours	6 Hours	Same Day or 12 Hours*	24 Hours (1 day)
Bulk	Drinking Water		48 Hours (2 days)	72 Hours (3 days)	96 Hours (4 days)	120 Hours (5 days)
Wipe	Wastewater		144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours. Please call ahead to schedule. There is a premium charge for 3-hour lab, please call 1-800-228-2675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours must arrive by 11:00am, Mon-Fri. Please Refer to Price Quote

*BASE DUPLICATE*

<b>PCM - Air</b> NIOSH 7400A (Rev. 2 August 1998) OSHA w/PWA Other:	<b>TEM Air</b> AHERA 40 CFR, Part 763 Subpart E NIOSH 7402 EPA Level II	<b>TEM WATER</b> EPA 100.1 EPA 100.2 NYS 198.2
<b>PLM - Bulk</b> EPA 600/R-95/116 EPA Point Count NY Stratified Point Count PLM NOB (Gravimetric) NYS 198.1 NIOSH 9002: EMSL Standard Addition:	<b>TEM BULK</b> Drop Mount (Qualitative) Chatfield SOP - 1988-02 TEM NOB (Gravimetric) NYS 198.4 EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> ASTM D 5755-95 (qualitative method) Wipe Qualitative
<b>SEM Air or Bulk</b> Qualitative Quantitative	<b>PLM Soil</b> EPA Protocol Qualitative EPA Protocol Quantitative EMSL MSD 9001 Method (bioassay)	<b>OTHER</b> Asbestos Silica NIOSH 7500
CARB 435 w/TEM EPA 1000 point count method		

SAMPLE ACCEPTED  
FOR ANALYSIS BY  
EMSL ANALYST





## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Hadden Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4900  
(856) 427-1608  
<http://www.enisl.com>

Please print all information legibly.

Client Sample # (s) 19

Total Samples #: 2

Relinquished: NATHAN SHUMATE Date: 12-27-07

Time: P.M.

Received: KW PL Date: \_\_\_\_\_

Time: 7:40

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

[illegible]



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: [westmontlab@EMSL.com](mailto:westmontlab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAX156  
Customer PO:  
Received: 12/28/07 9:40 AM  
EMSL Order: 040731699

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: CMC BOZEMAN-1157720035.200

EMSL Proj:  
Analysis Date: 2/2/2008  
Report Date: 2/3/2008

**Asbestos Analysis via Transmission Electron Microscopy ASTM Method D5755-03**

SAMPLE ID	AREA SAMPLED (cm <sup>2</sup> )	ASBESTOS TYPE	ASBESTOS STRUCTURES	Sensitivity (str/cm <sup>2</sup> )	CONCENTRATION (str/cm <sup>2</sup> )	COMMENTS
20 040731699-0001	0	None Detected	<3			Blank
21 040731699-0002	0	None Detected	<3			Blank
22 040731699-0003	1000	None Detected	<3	1990	<5970	
20 731699-0020	0	None Detected	<3			Blank
21 040731699-0021	0	None Detected	<3			Blank
22 040731699-0022	1000	None Detected	<3	1990	<5970	
23 040731699-0023	0	None Detected	<3			Blank
24 040731699-0024	0	None Detected	<3			Blank
25 040731699-0025	1000	None Detected	<3	332	<996	
26 040731699-0026	1000	None Detected	<3	996	<2990	
27 040731699-0027	1000	None Detected	<3	332	<996	

Analyst(s)

Theodore Xu (22)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted.



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4800 Fax: (856) 858-4960 Email: westmontasblab@EMSL.com

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAXI56  
Customer PO:  
Received: 12/28/07 9:40 AM  
EMSL Order: 040731699

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: CMC BOZEMAN-1157720035.200

EMSL Proj:  
Analysis Date: 2/2/2008  
Report Date: 2/3/2008

**Asbestos Analysis via Transmission Electron Microscopy ASTM Method D5755-03**

SAMPLE ID	AREA SAMPLED (cm <sup>2</sup> )	ASBESTOS TYPE	ASBESTOS STRUCTURES	Sensitivity (str/cm <sup>2</sup> )	CONCENTRATION (str/cm <sup>2</sup> )	COMMENTS
28 040731699-0028	1000	None Detected	<3	3320	<9960	
29 040731699-0029	1000	None Detected	<3	199	<597	
30 040731699-0030	1000	None Detected	<3	996	<2990	
31 040731699-0031	1000	Amosite Chrysotile	<3	332	<996	
32 040731699-0032	1000	None Detected	<3	9960	<29900	
33 040731699-0033	1000	None Detected	<3	9960	<29900	
34 040731699-0034	1000	None Detected	<3	9960	<29900	
35 040731699-0035	1000	None Detected	<3	3320	<9960	
36 040731699-0036	1000	None Detected	<3	1990	<5970	
37 040731699-0037	100	None Detected	<3	1990	<5970	
38 040731699-0038	100	None Detected	<3	19900	<59700	

revised report- asbestos structure counting criteria of 3:1 used

Analyst(s)

Theodore Xu (22)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. Samples received in good condition unless otherwise noted.



**TETRA TECH****Tetra Tech**1601 2<sup>nd</sup> Avenue North, Suite 116

Great Falls, Montana 59401

Tel: 406.453.1641 Fax: 406.771.0743

**Fax**Date: 1/25/08No. of pages including cover sheet: 8To: Steve SiegelCompany: EMSLPhone: 856 858 4800Fax: 856 858 4960

CC:

From: Keith CronDept: IHPhone: 406 453 1641

Fax:

☐ Urgent ☐ For your review ☒ Reply ASAP ☐ Please comment


Steve,

Please find attached (2) EMSL Laboratory Reports you provided analytical services for. For the NIOSH 7402 Method run on the provided samples, please analyze them for (ISO Method 10312).

For the ASTM D 5755-03, please provide analytical results for a fiber ratio of 3:1 instead of the method-specified 5:1. Additionally, please note the changes to the area with dust wipe sampling as ~~was~~ all were greater than the 100 cm<sup>2</sup> specified.

Please call me with any additional questions. We can have a 6+ day turnaround time as well.

Thanks.



PLEASE NOTE: This message, including any attachments, may include privileged, confidential and/or inside information. Any distribution or use of this communication by anyone other than the intended recipient is strictly prohibited and may be unlawful. If you are not the intended recipient, please notify the sender by replying to this message and then delete it from your system.



FED Ex # 7909-0467-1511

Page 1 of 2<sup>3</sup>

## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Company: Tetra Tech	Bill To: Tetra Tech
Address1: 1601 2nd Avenue North Suite 116	Address1: 1601 2nd Avenue North Suite 116
Address2:	Address2:
City, State: Great Falls, Montana	City, State: Great Falls, Montana
Zip/Post Code: 59401	Zip/Post Code: 59401
Country: U.S.A.	Country: U.S.A.
Contact Name: Keith Cron	Attn: Keith Cron
Phone: 406.453.1641	Phone: 406.453.1641
Fax: 406.771.0743	Fax: 406.771.0743
Email: Keith.Cron@Tetrattech.com	Email: Keith.Cron@Tetrattech.com
EMSL Rep:	P.O. Number:
Project Name/Number: CMC Bozeman - 1157720035.200	

MATRIX			TURNAROUND			
<input type="checkbox"/> Air	<input type="checkbox"/> Soil	<input checked="" type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours, Please call ahead to schedule. There is a premium charge for 3-hour test, please call 1-800-220-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00am, Mon-Fri.), Please Refer to Price Quote

<b>PCM - Air</b> <input type="checkbox"/> NIOSH 7400(A) Issue 2: August 1994 <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input checked="" type="checkbox"/> ASTM D 5755-95 (quantitative method) <input type="checkbox"/> Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method fibers/grm	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500  <b>OTHER</b> <input type="checkbox"/>



Page 2 of 2  
3

## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) 20 38Total Samples #: 19Relinquished: Nathan Shumate Date: 12-27-07Time: p.m.

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	VOLUME (if applicable)	Area Sampled cm <sup>2</sup>
20	NHB - media blank 1	NA	
21	NHB - media blank 2	↓	
22	SHB-1 - SALVATION ARMY SHOP 3 bathroom	20.1 L	1,000 cm <sup>2</sup>
23	NHB - Field blank (FB-1)	NA	
24	NHB - Field blank (FB-2)	↓	
25	NHB-1: SW OFFICE/MENS 3 WOMANS BATH	20.46 L	1,000 cm <sup>2</sup>
26	NHB-2: S. SHOWROOM/N. SHOWROOM W/ CLOSET	20.77 L	1,000 cm <sup>2</sup>
27	NHB-3: MAIN FLOOR: ENTRY HALL MAIN OFFICE STORAGE 1 & 2	20.97 L	1,000 cm <sup>2</sup>
28	NHB-4: MAIN LEVEL - EAST DOCK AREA	19.9 L	1,000 cm <sup>2</sup>
29	NHB-5: 3 <sup>rd</sup> LEVEL - Big Sky Atrium	20.2 L	1,000 cm <sup>2</sup>
30	NHB-6: MAIN FLOOR: BITTERROOT STAINED GLASS SHOP & STORAGE	20.5 L	1,000 cm <sup>2</sup>
31	NHB-7: BASEMENT SHOWROOM	20.5 L	1,000 cm <sup>2</sup>
32	NHB-8: BASEMENT HVAC ROOM	20.4 L	1,000 cm <sup>2</sup>
33	NHB-9: BASEMENT: SHOP OFFICE VAULT	20.3 L	1,000 cm <sup>2</sup>





## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) SEE Pg. 2 of 3

Total Samples #: \_\_\_\_\_

Relinquished: Nathaniel Shumate Date: 12.27.07Time: p.m.

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

[illegible]





Attention: Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

Fax: 406-771-0743 Phone: 406-453-1641  
Project: CMC Bozeman  
1157720035.200


Customer ID: MAXI53  
Customer PO:  
Received: 01/27/08

EMSL Order: 040802108  
Analysis Date: 6/3/2008  
Report Date: 06/04/08

## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0001	
Customer Sample #:	45	
Date sampled:	12/27/2007	
Initials of Analyst:	DL/DY	
Air volume:	0	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	133	
Analytical Sensitivity:	0.58	Structure/square mm
Number of Primary Asbestos Structures Counted:	None Detected	
Number of total asbestos structures counted:	None Detected	
Number of Asbestos Structures > 5 microns:	None Detected	
Number of Asbestos fibers and bundles > 5 microns:	None Detected	
Number of PCM equivalent asbestos structures:	Not Analyzed	
Number of PCM equivalent asbestos fibers:	Not Analyzed	
Concentration of Chrysotile Asbestos:	< 1.73	Structure/square mm
Concentration of Amphibole Asbestos:	< 1.73	Structure/square mm
Lower 95% Confidence Limit (Chrysotile)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 1.73	Structure/square mm
Lower 95% Confidence Limit (Amphibole)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 1.73	Structure/square mm
<b>Concentration of Asbestos (total):</b>	<b>&lt; 1.73</b>	<b>Structure/square mm</b>

**Comments:** Additional grid openings analyzed under  
EMSL order ID:04081235. Analysis occurred from original  
grid preps.

  
Approved Signatory





Attention: Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

Customer ID: MAXI53  
Customer PO:  
Received: 01/27/08

Fax: 406-771-0743 Phone: 406-453-1641  
Project: CMC Bozeman  
1157720035.200

EMSL Order: 040802108  
Analysis Date: 6/3/2008  
Report Date: 06/04/08

## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0002	
Customer Sample #:	46	
Date sampled:	12/27/2007	
Initials of Analyst:	DL/DY	
Air volume:	0	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	66	
Analytical Sensitivity:	1.17	Structure/square mm
Number of Primary Asbestos Structures Counted:	None Detected	
Number of total asbestos structures counted:	None Detected	
Number of Asbestos Structures > 5 microns:	None Detected	
Number of Asbestos fibers and bundles > 5 microns:	None Detected	
Number of PCM equivalent asbestos structures:	Not Analyzed	
Number of PCM equivalent asbestos fibers:	Not Analyzed	
Concentration of Chrysotile Asbestos:	< 3.48	Structure/square mm
Concentration of Amphibole Asbestos:	< 3.48	Structure/square mm
Lower 95% Confidence Limit (Chrysotile)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 3.48	Structure/square mm
Lower 95% Confidence Limit (Amphibole)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 3.48	Structure/square mm
Concentration of Asbestos (total):	< 3.48	Structure/square mm

**Comments:** Additional grid openings analyzed under  
EMSL order ID:04081235. Analysis occurred from original  
grid preps.

  
Approved Signatory





Attention: Keith Cron  
Tetra Tech / Maxim Technologies  
1601 2nd Avenue N, Suite 116  
Great Falls, MT 59401

Fax: 406-771-0743 Phone: 406-453-1641  
Project: CMC Bozeman  
1157720035.200

Customer ID: MAXI53  
Customer PO:  
Received: 01/27/08

EMSL Order: 040802108  
Analysis Date: 6/3/2008  
Report Date: 06/04/08

## ISO 10312-Ambient Air - Determination of Asbestos Fibers Direct Transfer Transmission Electron Microscopy

EMSL Sample #:	040802108-0003	
Customer Sample #:	47	
Date sampled:	12/27/2007	
Initials of Analyst:	DL/DY	
Air volume:	0	Liters
Area of collection filter:	385	square mm
Level of analysis (chrysotile):	CD	
Level of analysis (amphibole):	ADX	
Magnification used for fiber counting:	~20,000	X
Aspect ratio for fiber definition:	5:1	
Mean dimension of grid openings:	0.013	square mm
Number of Grid Openings Analyzed:	124	
Analytical Sensitivity:	0.62	Structure/square mm
Number of Primary Asbestos Structures Counted:	None Detected	
Number of total asbestos structures counted:	None Detected	
Number of Asbestos Structures > 5 microns:	None Detected	
Number of Asbestos fibers and bundles > 5 microns:	None Detected	
Number of PCM equivalent asbestos structures:	Not Analyzed	
Number of PCM equivalent asbestos fibers:	Not Analyzed	
Concentration of Chrysotile Asbestos:	< 1.85	Structure/square mm
Concentration of Amphibole Asbestos:	< 1.85	Structure/square mm
Lower 95% Confidence Limit (Chrysotile)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 1.85	Structure/square mm
Lower 95% Confidence Limit (Amphibole)	NA	Structure/square mm
Upper 95% Confidence Limit (Chrysotile)	< 1.85	Structure/square mm
Concentration of Asbestos (total):	< 1.85	Structure/square mm

**Comments:** Additional grid openings analyzed under  
EMSL order ID:04081235. Analysis occurred from original  
grid preps.

  
Approved Signatory



**Cron, Keith**

---

**From:** Cron, Keith  
**To:** rdenton@emsl.com  
**Cc:**  
**Subject:** CMC Bozeman Facility EMSL Reference Order No. ( 040802108)  
**Attachments:**

**Sent:** Thu 5/22/2008 7:05 AM

Robyn,

Per our conversations the past couple of days please find this email as notice to proceed with the reprocessing/reanalysis of the five samples previously analyzed by the ISO 10312 Method. For the reanalysis, I would like the sensitivity to be reduced to 0.0002 structures per cubic centimeter; therefore, I understand that EMSL will have to open approximately 160 new grids to perform the additional analysis to be included in the analytical result per sample. After discussing this with EMSL representatives, they have agreed on a price of \$5/additional grid opening based on a normal turnaround schedule. The additional stipulation that I would like to put on the reanalysis is that a minimum of 10 grid openings be analyzed and continued to count structures until the required analytical sensitivity has been reached, based on the sample volume and the number of grid openings counted. The count may be terminated upon completion of the grid opening containing the 50<sup>th</sup> structure, regardless of whether or not the target analytical sensitivity has been reached.

If you have any additional question, feel free to call or email me. Please let me know when you think you will be done with the analysis as I may need to ask for an extension – on my end.

Thanks for all you help!

Keith Cron, CIH | Branch Manager  
Cell: 406.788.5318 | Main: 406.453.1641 | Fax: 406.771.0743

Tetra Tech | Complex World, Clear Solutions™  
1601 2nd Avenue North, Suite 116 | Great Falls, Montana 59401 | [www.tetratech.com](http://www.tetratech.com)



**TETRA TECH****Tetra Tech**1601 2<sup>nd</sup> Avenue North, Suite 116

Great Falls, Montana 59401

Tel: 406.453.1641 Fax: 406.771.0743

**Fax**

Date:

1/28/08

No. of pages including cover sheet:

8

To:

Steve Siegel

Company:

EMSL

Phone:

856 858 4800

Fax:

856 858 4960

CC:

From:

Keith Cron

Dept:

IH

Phone:

406 4531641

Fax:

in fax:

☐ Urgent ☐ For your review ☒ Reply ASAP ☐ Please comment

Steve,

Please find attached (2) EMSL Laboratory Reports you provided analytical services for. For the NIOSH 7402 Method run on the provided samples, please analyze them for (ISO Method 10312).

For the ASTM D 5755-03, please provide analytical results for a fiber ratio of 3:1 instead of the method-specified 5:1. Additionally, please note the changes to the area with dust wipe sampling as ~~mm~~ all were greater than the 100 cm<sup>2</sup> specified.

Please call me with any additional questions. We can have a 6+ day turnaround time as well.

Thanks.



040802108 - ISO 10312

FED EX # 7909-0467-1511

Page 1 of 2



## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

<b>Company:</b> Tetra Tech	<b>Bill To:</b> Tetra Tech
<b>Address1:</b> 1601 2nd Avenue North Suite 116	<b>Address1:</b> 1601 2nd Avenue North Suite 116
<b>Address2:</b>	<b>Address2:</b>
<b>City, State:</b> Great Falls, Montana	<b>City, State:</b> Great Falls, Montana
<b>Zip/Post Code:</b> 59401	<b>Zip/Post Code:</b> 59401
<b>Country:</b> U.S.A.	<b>Country:</b> U.S.A.
<b>Contact Name:</b> Keith Cron	<b>Attn:</b> Keith Cron
<b>Phone:</b> 406.453.1641	<b>Phone:</b> 406.453.1641
<b>Fax:</b> 406.771.0743	<b>Fax:</b> 406.771.0743
<b>Email:</b> Keith.Cron@Tetrattech.com	<b>Email:</b> Keith.Cron@Tetrattech.com
<b>EMSL Rep:</b>	<b>P.O. Number:</b>
<b>Project Name/Number:</b> CMC Bozeman - 1157720035.200	

MATRIX			TURNAROUND			
<input checked="" type="checkbox"/> Air	<input type="checkbox"/> Soil	<input type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input checked="" type="checkbox"/> 144+ hours (6-10 days)			

TEM Air, 3 hours, 6 hours, Please call ahead to schedule. There is a premium charge for 3-hour lat. please call 1-800-220-5675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00am, Mon-Fri). Please Refer to Price Quote

<b>PCM - Air</b> <input type="checkbox"/> NIOSH 7400(A) (later 2: August 1994) <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input checked="" type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: <input type="checkbox"/> EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 <input type="checkbox"/> EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input type="checkbox"/> ASTM D 5755-95 (quantitative method) <input type="checkbox"/> Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method (fibers/grm)	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500  <b>OTHER</b>

SAMPLES ACCEPTED  
FOR ANALYSIS BY  
EMSL ANALYTICAL

040731694



FED EX # 7909-0467-1511

Page 2 of 2



## Chain of Custody

### Asbestos Lab Services

**EMSL Analytical, Inc.**  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.ernsl.com>

Please print all information legibly.

Client Sample # (s) 45 49

Total Samples #: 5

Relinquished: Nathan Shumate Date: 12-27-07

Time: P.m.

Received: K2 FY Date: \_\_\_\_\_

Time: 790

Retinquired: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_

[illegible]

SAMPLES ACCEPTED  
FOR ANALYSIS AT  
EMSL ANALYTICAL

TYPE  
1/30/00



**EMSL Analytical, Inc.**

107 Haddon Ave., Westmont, NJ 08108

Phone: (856) 858-4900 Fax: (856) 858-4960 Email: [westmontlab@EMSL.com](mailto:westmontlab@EMSL.com)

Attn: **Keith Cron**  
**Tetra Tech/Maxim Technologies**  
**1601 2nd Avenue N**  
**Suite 116**  
**Great Falls, MT 59401**

Customer ID: MAXI56  
Customer PO:  
Received: 06/11/08 10:40 AM  
EMSL Order: 040814203

Fax: (406) 771-0743 Phone: (406) 453-1641  
Project: 1157720035.200

EMSL Proj:  
Analysis Date: 6/13/2008  
Report Date: 6/13/2008

**PLM Analysis of Bulk Samples for Asbestos via EPA 600/R-93/116 Method with CARB  
435 Prep (Milling) Level A for 0.25% Target Analytical Sensitivity**

Sample	Location	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
SHB-TP2 040814203-0001		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected
SHB-TP2 DUPLICATE 040814203-0002		Gray Non-Fibrous Homogeneous		100.00% Non-fibrous (other)	None Detected

Analyst(s)

Delores Beard (2)

Stephen Siegel, CIH, Laboratory Manager  
or other approved signatory

This report relates only to the samples listed above and may not be reproduced except in full, without EMSL's written approval. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the federal government. EMSL is not responsible for sample collection activities or method limitations. Some samples may contain asbestos fibers below the resolution limit of PLM. EMSL recommends that samples reported as none detected or less than the limit of detection undergo additional analysis via TEM. Samples received in good condition unless otherwise noted. Samples received in good condition unless otherwise noted.





# Chain of Custody

## Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800

Fax: (856) 858-4960

(856) 427-1608

<http://www.emsl.com>

Please print all information legibly.

MAXI 56

<b>Company:</b>	Tetra Tech	<b>Bill To:</b>	Tetra Tech
<b>Address1:</b>	1601 2nd Avenue North	<b>Address1:</b>	1601 2nd Avenue North
<b>Address2:</b>	Suite 116	<b>Address2:</b>	Suite 116
<b>City, State:</b>	Great Falls, Montana	<b>City, State:</b>	Great Falls, Montana
<b>Zip/Post Code:</b>	59401	<b>Zip/Post Code:</b>	59401
<b>Country:</b>	USA	<b>Country:</b>	USA
<b>Contact Name:</b>	Keith Cron	<b>Attn:</b>	Keith Cron
<b>Phone:</b>	406.453.1641	<b>Phone:</b>	406.453.1641
<b>Fax:</b>		<b>Fax:</b>	
<b>Email:</b>	Keith.Cron@tetratech.com	<b>Email:</b>	Keith.Cron@tetratech.com
<b>EMSL Rep:</b>	Stephen Siegel	<b>P.O. Number:</b>	
<b>Project Name/Number:</b> 1157720035.200			

MATRIX			TURNAROUND			
<input type="checkbox"/> Air	<input checked="" type="checkbox"/> Soil	<input type="checkbox"/> Micro-Vac	<input type="checkbox"/> 3 Hours	<input type="checkbox"/> 6 Hours	<input type="checkbox"/> Same Day or 12 Hours*	<input type="checkbox"/> 24 Hours (1 day)
<input type="checkbox"/> Bulk	<input type="checkbox"/> Drinking Water		<input checked="" type="checkbox"/> 48 Hours (2 days)	<input type="checkbox"/> 72 Hours (3 days)	<input type="checkbox"/> 96 Hours (4 days)	<input checked="" type="checkbox"/> 120 Hours (5 days)
<input type="checkbox"/> Wipe	<input type="checkbox"/> Wastewater		<input type="checkbox"/> 144+ hours (6-10 days)			

TEM AIR, 3 hours, 6 hours. Please call ahead to schedule. There is a premium charge for 3-hour lab, please call 1-800-220-3675 for price prior to sending samples. You will be asked to sign an authorization form for this service.

\*12 hours (must arrive by 11:00a.m. Mon-Fri.). Please Refer to Price Quote

<b>PCM - Air</b> <input type="checkbox"/> NIOSH 7400(A) Issue 2: August 1994 <input type="checkbox"/> OSHA w/TWA <input type="checkbox"/> Other:	<b>TEM Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 Subpart E <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II	<b>TEM WATER</b> <input type="checkbox"/> EPA 100.1 <input type="checkbox"/> EPA 100.2 <input type="checkbox"/> NYS 198.2
<b>PLM - Bulk</b> <input type="checkbox"/> EPA 600/R-93/116 <input type="checkbox"/> EPA Point Count <input type="checkbox"/> NY Stratified Point Count <input type="checkbox"/> PLM NOB (Gravimetric) NYS 198.1 <input type="checkbox"/> NIOSH 9002: EMSL Standard Addition:	<b>TEM BULK</b> <input type="checkbox"/> Drop Mount (Qualitative) <input type="checkbox"/> Chatfield SOP - 1988-02 <input type="checkbox"/> TEM NOB (Gravimetric) NYS 198.4 EMSL Standard Addition:	<b>TEM Microvac/Wipe</b> <input type="checkbox"/> ASTM D 5755-95 (quantitative method) Wipe Qualitative
<b>SEM Air or Bulk</b> <input type="checkbox"/> Qualitative <input type="checkbox"/> Quantitative	<b>PLM Soil</b> <input type="checkbox"/> EPA Protocol Qualitative <input type="checkbox"/> EPA Protocol Quantitative <input type="checkbox"/> EMSL MSD 9000 Method fibers/gram	<b>XRD</b> <input type="checkbox"/> Asbestos <input type="checkbox"/> Silica NIOSH 7500
<b>OTHER</b> <input checked="" type="checkbox"/> CARB Method 4/BS w/PLM EPA 400 Point Count Method		

Sent via FedEx 79105377447





## Chain of Custody

### Asbestos Lab Services

EMSL Analytical, Inc.  
107 Haddon Avenue  
Westmont, NJ 08108

Phone: (856) 858-4800  
Fax: (856) 858-4960  
(856) 427-1608  
<http://www.emsl.com>

Please print all information legibly.

Client Sample # (s) SIB-TP2 0-.5' - SIB-TP2 2.5-3.0' Total Samples #: 6

Relinquished: [Signature] Date: 6/10/08 Time: PM

Received: DM-FX-1040A Date: \_\_\_\_\_ Time: \_\_\_\_\_

Relinquished: \_\_\_\_\_ Date: \_\_\_\_\_ Time: \_\_\_\_\_

Received: \_\_\_\_\_ Date: \_\_\_\_\_ Time: \_\_\_\_\_

SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	VOLUME (if applicable)
SIB-TP2	0 - 0.5'	
SIB-TP2	0.5' - 1.0'	
SIB-TP2	1.0' - 1.5'	Composite Samples and analyze as one for TP-2
SIB-TP2	1.5' - 2.0'	
SIB-TP2	2.0' - 2.5'	
SIB-TP2	2.5' - 3.0'	Duplicate 0-3'

EMSL Analytical, Inc.  
 107 Haddon Avenue  
 Westmont, NJ 08108  
 Phone: (856) 858-4800  
 Fax: (856) 858-4960  
 (856) 427-1608  
<http://www.emsl.com>



## **APPENDIX M**

### **Data Validation Reports**





June 16, 2008

Mr. Tim Cooper  
P.O. Box 1230  
Bozeman, Montana 59771

**RE: CMC Bozeman Facility – SI Work Plan  
Data Validation Report – Asbestos PLM  
Soil Investigation**

Mr. Cooper:

In accordance with the City of Bozeman's (City's) agreement with Tetra Tech dated December 7, 2007, Tetra Tech is providing data validation for soil samples we collected from the specified test pits as approved by the Montana Department of Environmental Quality's (DEQ) *CMC Bozeman Asbestos Facility DEQ-Approval of Supplemental Investigation (SI) Work Plan – Final Revision* dated December 6, 2007.

This validation report is applicable specifically to the 34 soil samples analyzed by polarized light microscopy (PLM) using the California Air Resources Board (CARB) Method 435 for sample preparation for both 0.1% and 0.25% analytical sensitivity, as stipulated. These samples included 10 test pit samples from the South Harrington Building (SHB) property including six base test pit samples, three composite test pit samples, and one composite duplicate sample; 10 test pit samples from the Heeb's Grocery (Heeb's) alleyway including five base test pit samples, four composite test pit samples, and one base duplicate sample; 12 test pit samples from the Story Distributing (Story) property including six base test pit samples, five composite test pit samples, and one base duplicate sample; additionally, one laboratory blank sample was reanalyzed and compared to an existing known value.

The samples were analyzed by EMSL Analytical, Inc. in five laboratory batches.

#### **DELIVERABLES**

All laboratory document deliverables were present as specified in the approved aforementioned DEQ-Approved SI Work Plan:

☒ YES ☐ NO

All documentation of field procedures was provided as required:

☒ YES ☐ NO





## **FIELD QUALITY CONTROL SAMPLES**

### **Blanks**

Work Plan Specified:

1 per 18 composite test pit side wall samples

1 per 18 base test pit samples

Actual Frequency:

0 per 12 composite test pit side wall samples

1 per 17 base test pit samples

### **Duplicates**

Work Plan Specified:

1 per 18 composite test pit side wall samples

1 per 18 base test pit samples

Actual Frequency:

1 per 12 composite test pit side wall samples

2 per 17 base test pit samples

### **Comments:**

One of the original test pit sample locations on the Story TP-6 was determined by visual inspection to have been previously excavated and replaced with engineered backfill material used as fill; therefore, soil sample collection was unnecessary. Additionally, several of the composite test pits throughout the study area were deemed unnecessary due to vertical depth of asbestos ore laden soil down to the native soil and/or three feet as is represented with only the collection of 12 composite samples. None of the 10 soil sample results were above limits of detection for their respective analytical method. The blank sample submitted did not contain asbestos above the limit of detection; one sample was only collected because the actual number of base and composite samples was reduced; thereby decreasing the blank sample requirement to samples collected ratio. One of the base samples was assessed to 0.1% point count analysis and confirmed not to contain asbestos ore laden soil as requested for 10% of the soil samples.

### **Laboratory Procedures**

Laboratory procedure followed for asbestos: EPA 600/R-93/116 Method with CARB 435 Prep (Milling) Level A for 0.25% and/or 0.1% analytical sensitivity.

☒ YES ☐ NO

### **Detection Limits**

Project detection limits were set at 0.25% using 400-point count PLM Method with 10% samples analyzed using 0.1% 1000-point count PLM Method





Reported detection limits complied with project required detection limits:

☒ YES ☐ NO

**Duplicate Readings**

According to EMSL Analytical, Inc., one out of every 10 samples is read by another analyst for quality control.

**Laboratory Control Standards**

The analysts are required to read prepared samples to maintain their National Voluntary Laboratory Accreditation Program (NVLAP) certifications. Analysts are tested quarterly.

**Data Quality Objectives**

Project data quality objectives met:

☒ YES ☐ NO

**Accuracy**

The overall accuracy objectives were met, as the analysts are certified and routinely tested to ensure they can accurately read laboratory quality control samples.

**Precision**

The overall precision objectives were met, as the duplicate samples were within control limits.

**Completeness**

All of the test pits intended for asbestos PLM analysis were sampled and analyzed using the methods specified in the SI Work Plan. The overall completeness objectives were met and data deemed valid.

Report Prepared By:



Keith Cron, CIH

Report Reviewed By:



Daphne Digridakis





**TETRA TECH**

June 16, 2008

Mr. Tim Cooper  
P.O. Box 1230  
Bozeman, Montana 59771

**RE: CMC Bozeman Facility – SI Work Plan  
Data Validation Report – Asbestos TEM  
Occupational Air Investigation**

Mr. Cooper:

In accordance with the City of Bozeman's (City's) agreement with Tetra Tech dated December 7, 2007, Tetra Tech is providing data validation for the occupational air samples collected from areas in the North Harrington Building (NHB) and South Harrington Building (SHB), as approved by the Montana Department of Environmental Quality's (DEQ) *CMC Bozeman Asbestos Facility DEQ-Approval of Supplemental Investigation (SI) Work Plan – Final Revision* dated December 6, 2007, throughout a typical work day for Mr. Jeff Harrington.

This validation report is applicable specifically to the dust samples analyzed in accordance with International Standards Organization (ISO) Method 10312:1995, with the caveat of performing analysis using an analytical sensitivity level of 0.0002 structure per cubic centimeter, as specified in the aforementioned work plan. These samples included two occupational air samples of two separate day's work tasks.

The samples were analyzed by EMSL Analytical, Inc. in one laboratory batch.

#### **DELIVERABLES**

All laboratory document deliverables were present as specified in the approved aforementioned DEQ-Approved SI Work Plan:

☒ YES ☐ NO

All documentation of field procedures was provided as required:

☒ YES ☐ NO

**Tetra Tech**

1601 2<sup>nd</sup> Avenue South, Suite 116 Great Falls, Montana 59401

Tel 406.453.1641 Fax 406.771.0743 [www.tetrattech.com](http://www.tetrattech.com)





## **FIELD QUALITY CONTROL SAMPLES**

### **Media Blank**

Work Plan Specified:

1 samples from the lot of filter media cassettes

Actual Frequency:

2 samples from Lot No. 7209770275 from Environmental Monitoring Systems

### **Field Blank**

Work Plan Specified:

1 per 10 samples analyzed (10%)

Actual Frequency:

1 per 2 samples analyzed (50%)

### **Comments:**

One single asbestos fiber (anthophyllite) was noted in sample number P-121807-01, when the analytical sensitivity was at 0.00022 structures per cubic centimeter of air. Field blank and field media samples did not indicate a detectable quantity with respect to asbestos fibers.

## **Laboratory Procedures**

Laboratory procedure followed for asbestos: ISO Method 10312 using Transmission Electron Microscopy.

☒ YES ☐ NO

## **Detection Limits**

Detection limits were set at 0.0002 structures per cubic centimeter of air. Due to the reanalysis of the grid openings and the fact that some grid openings could not be opened, the two sets of data collected were at detection limits of 0.00022 and 0.00038 structures per cubic centimeter of air. These respective detection limits were within 91% and 53% of the specified amount; however, were within the same order of magnitude.

Reported detection limits complied with project required detection limits:

☐ YES ☒ NO

## **Duplicate Readings**

According to EMSL Analytical, Inc., one out of every 10 samples is read by another analyst for quality control.



### **Laboratory Control Standards**

The analysts are required to read prepared samples to maintain their National Voluntary Laboratory Accreditation Program (NVLAP) certifications. Analysts are tested quarterly.

### **Data Quality Objectives**

Project data quality objectives met:

☒ YES ☐ NO

### **Accuracy**

The overall accuracy objectives were met, as the analysts are certified and are routinely tested to ensure they can accurately read laboratory quality control samples.

### **Precision**

The overall precision objectives were met, as the duplicate samples were within control limits.

### **Completeness**

The two air samples analyzed for asbestos TEM analysis were sampled and analyzed using the methods specified in the SI Work Plan. The overall completeness objectives were met and data deemed valid for respective analytical sensitivities.

Report Prepared By:

  
Keith Cron, CIH

Report Reviewed By:

  
Daphne Digrindakis





June 16, 2008

Mr. Tim Cooper  
P.O. Box 1230  
Bozeman, Montana 59771

**RE: CMC Bozeman Facility – SI Work Plan  
Data Validation Report – Asbestos TEM  
Dust Investigation**

Mr. Cooper:

In accordance with the City of Bozeman's (City's) agreement with Tetra Tech dated December 7, 2007, Tetra Tech is providing data validation for the dust samples collected from areas in the North Harrington Building (NHB) and South Harrington Building (SHB), as approved by the Montana Department of Environmental Quality's (DEQ) *CMC Bozeman Asbestos Facility DEQ-Approval of Supplemental Investigation (SI) Work Plan – Final Revision* dated December 6, 2007.

This validation report is applicable specifically to the dust samples analyzed in accordance with American Standard for Testing and Materials (ASTM) Method D 5755-03, with the caveat of performing analysis using a 3 to1 aspect ratio as specified in the aforementioned work plan. These samples included one dust sample from the South Harrington Building (SHB) interior, 14 dust samples from the North Harrington Building (NHB) interior, two media blanks, and two field blanks. The interior samples were collected to gather a subsample ratio of four accessible areas, four infrequently accessed areas, and two inaccessible areas to arrive at a total of 10 subsamples for each assessed area.

The samples were analyzed by EMSL Analytical, Inc. in one laboratory batch.

#### **DELIVERABLES**

All laboratory document deliverables were present as specified in the approved aforementioned DEQ-Approved SI Work Plan:

☒ YES ☐ NO

All documentation of field procedures was provided as required:

☒ YES ☐ NO



**FIELD QUALITY CONTROL SAMPLES****Media Blank**

Work Plan Specified:

2 samples from the lot of filter media cassettes

Actual Frequency:

2 samples from Lot No. 60719 from Environmental Monitoring Systems

**Field Blank**

Work Plan Specified:

1 per 10 samples analyzed (10%)

Actual Frequency:

2 per 15 samples analyzed (13%)

**Comments:**

One single sample had a detectable chrysotile fiber (NHB – 6) collected from the Main Floor (Bitterroot Stained Glass in the shop and storage room). Additional samples including media and field blanks did not have detectable quantities of asbestos. Two samples (NHB-13 and NHB-14) collected from the 3<sup>rd</sup> Floor Big Sky Aikido Heating Ventilation and Air Conditioning (HVAC) Return Plenum and Main Floor HVAC Return Plenum, respectively were collected with only one aliquot comprising 100 square centimeters; these specific aliquot samples represent separate HVAC zones on different floors, and did not have any additional HVAC return plenums associated along these separate HVAC zones.

**Laboratory Procedures**

Laboratory procedure followed for asbestos: ASTM Method D5755-03 with 3 to 1 aspect ratio specified using Transmission Electron Microscopy.

☒ YES ☐ NO

**Detection Limits**

Sensitivity and/or detection limit based on dilution values used during dispersion techniques as “less” dirty samples allow for higher quantification levels due to dilution factors.

Reported detection limits complied with project required detection limits:

☒ YES ☐ NO





### **Duplicate Readings**

According to EMSL Analytical, Inc., one out of every 10 samples is read by another analyst for quality control.

### **Laboratory Control Standards**

The analysts are required to read prepared samples to maintain their National Voluntary Laboratory Accreditation Program (NVLAP) certifications. Analysts are tested quarterly.

### **Data Quality Objectives**

Project data quality objectives met:

  x   YES           NO

### **Accuracy**

The overall accuracy objectives were met, as the analysts are certified and routinely tested to ensure they can accurately read laboratory quality control samples.

### **Precision**

The overall precision objectives were met, as the duplicate samples were within control limits.

### **Completeness**

The dust sample areas intended for asbestos TEM analysis were sampled and analyzed using the methods specified in the SI Work Plan. The overall completeness objectives were met and data deemed valid.

Report Prepared By:

  
Keith Cron, CIH

Report Reviewed By:

  
Daphne Digirindakis